


# DREDGED MATERIAL RESEARCH PROGRAM



CONTRACT REPORT D-75-5

## LANDSCAPE CONCEPT DEVELOPMENT FOR CONFINED DREDGED MATERIAL SITES

by

Roy Mann, William A. Niering  
Robert Sabbstini, Peter Wells

Roy Mann Associates, Inc.  
180 Franklin Street  
Cambridge, Mass. 02139


December 1975

Final Report

---

Approved For **Public** Release: Distribution **Unlimited**

---



Prepared for Environmental Effects Laboratory  
U.-S. Army Engineer Waterways Experiment Station  
P. O. Box 631, Vicksburg, Miss. 39180

Under Contract No. DACW39-74-C-0 104  
(DMRP Work Unit No. 5E01)

Destroy this report when no longer needed. Do not return  
it to the originator.



**DEPARTMENT OF THE ARMY**  
WATERWAYS EXPERIMENT STATION. CORPS OF ENGINEERS  
P. O. BOX 631  
VICKSBURG. MISSISSIPPI 39180

IN REPLY REFER TO: WESYV

31 December 1975

SUBJECT: Transmittal of Contract Report D-75-5

TO: All Report Recipients

1. The contract report transmitted herewith represents the results of one of the research efforts (work units) initiated to date as part of Task 2C (Containment Area Operation Research) of the Corps of Engineers' Dredged Material Research Program (DMRP). Task 2C is included as part of the Disposal Operations Project of the DMRP, which, among other considerations, includes research into various ways of improving the efficiency and acceptability of facilities for confining dredged material on land.
2. Confining dredged material on land is a relatively recent disposal alternative to which practically no specific design or construction improvement investigations, much less applied research, have been addressed. Being a form of waste-product disposal, dredged material placement on land has seldom been evaluated on other than purely economic grounds with emphasis nearly always on lowest possible cost. There has been a dramatic increase in the last several years in the amount of land disposal necessitated by confining dredged material classified as polluted. Attention necessarily is directed more and more toward the environmental consequences of this disposal alternative as well as to sociopolitical issues.
3. DMRP work units in progress are investigating improved facility design and construction and concepts for increasing facility capacities for both economic and environmental protection purposes. However, the total picture would be incomplete without considering methods of improving the appearance of facilities. To this end, the investigation reported herein was accomplished under contract with Roy Mann Associates, Inc. This study is considered a step leading to the implementation of improved planning, operation, and management practices emphasizing aesthetics.
4. This study reviews the principles and practices of confined disposal area operations and associated constraints and potentials for landscape

WESYV

31 December 1975

SUBJECT: Transmittal of Contract Report D-75-5

development. The study also documents landscape techniques directly applicable to the development of containment areas. Finally, a synthesis of information desired from the study was used in the development of landscaping guidance that can serve as an aid in planning, design, operation, and management of containment areas. It was concluded from the study that landscape development, if considered in the earliest project stages, can aid planners and engineers in achieving effective resolution of aesthetic problems and site reuse questions while accomplishing dredged material disposal objectives in full.

A handwritten signature in black ink, appearing to read 'G. H. Hilt', with a stylized flourish extending from the end.

G. H. HILT

Colonel, Corps of Engineers  
Director

**Unclassified**

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER <b>Contract Report D-75-5</b>	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) <b>LANDSCAPE CONCEPT DEVELOPMENT FOR CONFINED DREDGED MATERIAL SITES</b>		5. TYPE OF REPORT & PERIOD COVERED <b>Final report</b>
		6. PERFORMING ORG. REPORT NUMBER
7. AUTHOR(s) <b>Roy Mann                      Robert Sabbatini William A. Niering        Peter Wells</b>		8. CONTRACT OR GRANT NUMBER(e) <b>DACW39-74-C-0104 (DMRP Work Unit No. 5E01)</b>
3. PERFORMING ORGANIZATION NAME AND ADDRESS <b>Roy Mann Associates, Inc. 180 Franklin Street Cambridge, Mass. 02139</b>		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
11. CONTROLLING OFFICE NAME AND ADDRESS <b>U. S. Army Engineer Waterways Experiment Station Environmental Effects Laboratory P. O. Box 631, Vicksburg, Miss. 39180</b>		12. REPORT DATE <b>December 1975</b>
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		13. NUMBER OF PAGES <b>169</b>
		15. SECURITY CLASS. (of this report) <b>Unclassified</b>
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report)  <b>Approved for public release; distribution unlimited.</b>		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number)  <b>Disposal areas Dredged material disposal Landscaping</b>		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) <b>Confined dredged material disposal (CDMD) facilities have long been recognized as environmentally problematic for a number of physical, chemical, biological, and aesthetic reasons. The specific problem area of the aesthetic development of CDMD facilities is one that has received insufficient attention to date. The purpose of this study was to provide guidance for landscape development of CDMD sites. The approach of this study has been to: (1) examine the principle and practices of CDMD operations and the associated constraints (Continued)</b>		

**Unclassified**

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

**20. ABSTRACT (Continued)**

and potentials to landscape development, through a review of the literature, and to extend knowledge through field reconnaissance and data gathering in selected Corps Districts and from other sources of scientific and technical information; (2) to document landscape techniques directly applicable to the development of CDMD facilities, including those techniques abstracted from research of analogous facilities; and (3) to synthesize the information derived from the first two steps into appropriate landscape development guidance that can serve as an aid in the planning and design of CDMD sites. Landscape development, if considered in the earliest project stages, can aid CDMD planners and engineers in achieving effective resolution of aesthetic problems and site reuse questions while accomplishing dredged material disposal objectives in full

**THE CONTENTS OF THIS REPORT ARE NOT TO BE  
USED FOR ADVERTISING, PUBLICATION, OR  
PROMOTIONAL PURPOSES. CITATION OF TRADE  
NAMES DOES NOT CONSTITUTE AN OFFICIAL EN-  
DORSEMENT OR APPROVAL OF THE USE OF SUCH  
COMMERCIAL PRODUCTS.**

## **PREFACE**

**This report presents the results of an investigation entitled "Landscape Concept Development for Confined Dredged Material Sites." The study was conducted as part of the Corps of Engineers Dredged Material Research Program (DMRP). The DMRP is sponsored by the Office, Chief of Engineers, and is assigned to the U.S. Army Engineer Waterways Experiment Station (VES), Vicksburg, Mississippi, under the Environmental Effects Laboratory (EEL).**

**The study was funded under contract No. DACW39-74-C-0104 with Roy Mann Associates, Inc., Cambridge, Massachusetts. The contract was directed by Roy Mann, principal investigator, with the assistance of research associates Robert Sabbatini and Peter Wells. Howard C. Ris, Jr., provided editorial assistance. During the course of this study site visits were conducted to the Great Lakes, Atlantic, Gulf and Pacific coasts U.S. Army Corps of Engineers District offices. In addition, requests were distributed to all Districts as well as to state agencies to obtain information dealing with natural or induced vegetation at CDMD facilities. Assisting in the preparation of the plant lists, under the guidance of Dr. William A. Niering, were Michele M McKay and Sara Schneeberg of Roy Mann Associates, and Carolyn Weynouth and Cheryl Foote of the Department of Botany, Connecticut College, New London, Connecticut.**

**Technical advice on earth preparation and plant establishment techniques was provided by Martin E. Weeks, Professor of Soil Science, University of Massachusetts; John M. Zak, Associate Professor of Agronomy, Plant and Soil Science Department, University of Massachusetts; Robert N. Morehouse, District Conservationist, U.S. Soil Conservation Service, Acton, Massachusetts; and Ralph H. Goodno, Community Resource Development Specialist, Massachusetts Cooperative Extension Service, Danvers, Massachusetts. Preparation of the manuscript was conducted by Susan Tucker Yaro and Elizabeth Bouche.**

**The contract was monitored by Ms. Jean Hunt and Dr. Luther**



**Holloway under the supervision of Dr. Roger T. Saucier, Charles C. Calhoun, Jr., and CPT William C. Allanach, Jr., all personnel assigned to the DMRP. The Director of WES during the course of this contract was COL G. H. Hilt, and the Technical Director was Mr. F. R. Brown. The Chief of EEL was Dr. John Harrison.**

## INTRODUCTION

The disposal methods employed in dredging operations have long been recognized as environmentally problematic for a number of physical, chemical, biological, and aesthetic reasons. In particular, the confined disposal method has received increasing attention and opposition from the general public with regard to aesthetic factors. Reasons for these aesthetic dissatisfactions include: the unnatural appearance of the disposal materials and retention structures, the great size of the areas covered, visual incompatibilities with adjacent natural and man-made environments, disturbing odors, visible turbidity of the adjacent waters resulting from suspension of dredged material, interference with existing and proposed land-use patterns, and a number of other intangible effects, such as the public connotation of confined dredged material disposal (CDMD) facilities as being derelict lands.

For these and other reasons, the Corps of Engineers has commissioned a number of research studies. This study is a component of the Dredged Material Research Program (DMRP). The DMRP is sponsored by the Office of the Chief of Engineers and is under assignment to the U.S. Army Waterways Experiment Station (WES), Vicksburg, Mississippi. The objective of this program is to provide information on the environmental impacts of dredging and dredged material disposal operations and to develop acceptable technical, environmental, and economic methods of dredging and disposal.

This study is coordinated under Task 2C, Containment Area Operation Research, the purpose of which is to create new and improved methods for the operation and management of CDMD sites. Several other areas of research within the DMRP are of interest to this study. These include but are not limited to the contracts commissioned under the following tasks: 2A, Upland and Marsh Disposal Environmental Impacts; 4A, Artificial Marsh and Island Creation; 4B, Habitat Development Research; 4D, Products Research; 5A, Dredged Material Densification; 5C, Disposal Area Reuse Research; and 5D, Disposal Area Land-Use Concepts.

**CONVERSION FACTORS, BRITISH TO METRIC (SI)**  
**UNITS OF MEASUREMENT**

**British units of measurement used in this report can be converted to metric (SI) units as follows:**

<u>Multiply</u>	<u>By</u>	<u>To Obtain</u>
<b>inches</b>	<b>2.54</b>	<b>centimeters</b>
<b>feet</b>	<b>0.3048</b>	<b>meters</b>
<b>yards</b>	<b>0.9144</b>	<b>meters</b>
<b>miles (U. S. statute)</b>	<b>1.609344</b>	<b>kilometers</b>
<b>miles (U. S. nautical)</b>	<b>1.852</b>	<b>kilometers</b>
<b>square inches</b>	<b>6.4516</b>	<b>square centimeters</b>
<b>square feet</b>	<b>0.092903</b>	<b>square meters</b>
<b>square yards</b>	<b>0.836127</b>	<b>square meters</b>
<b>square miles</b>	<b>2.58999</b>	<b>square kilometers</b>
<b>acres</b>	<b>4046.856</b>	<b>square meters</b>
<b>cubic feet</b>	<b>0.0283168</b>	<b>cubic meters</b>
<b>cubic yards</b>	<b>0.764555</b>	<b>cubic meters</b>
<b>quarts (U. S. liquid)</b>	<b>946.353</b>	<b>cubic centimeters</b>
<b>tons (2000 pounds)</b>	<b>907.1847</b>	<b>kilograms</b>
<b>pounds per cubic foot</b>	<b>16.0185</b>	<b>kilograms per cubic meter</b>
<b>tons per square foot</b>	<b>9764.86</b>	<b>kilograms per square meter</b>

**CONVERSION FACTORS, BRITISH TO METRIC (SI)  
UNITS OF MEASUREMENT**

**British units of measurement used in this report can be converted to metric (SI) units as follows:**

<u>Multiply</u>	<u>By</u>	<u>To Obtain</u>
inches	2.54	centimeters
feet	0.3048	meters
yards	0.9144	meters
miles (U.S. statute)	1.609344	kilometers
miles (U.S. nautical)	1.852	kilometers
square inches	6.4516	square centimeters
square feet	0.092903	square meters
square yards	0.836127	square meters
square miles	2.58999	square kilometers
acres	4046.856	square meters
cubic feet	0.0283168	cubic meters
cubic yards	0.764555	cubic meters
quarts (U.S. liquid)	946.353	cubic centimeters
tons (2000 pounds)	907.1847	kilograms
pounds per cubic foot	16.0185	kilograms per cubic meter
tons per square foot	9764.86	kilograms per square meter

## INTRODUCTION

The disposal methods employed in dredging operations have long been recognized as environmentally problematic for a number of physical, chemical, biological, and aesthetic reasons. In particular, the confined disposal method has received increasing attention and opposition from the general public with regard to aesthetic factors. Reasons for these aesthetic dissatisfactions include: the unnatural appearance of the disposal materials and retention structures, the great size of the areas covered, visual incompatibilities with adjacent natural and man-made environments, disturbing odors, visible turbidity of the adjacent waters resulting from suspension of dredged material, interference with existing and proposed land-use patterns, and a number of other intangible effects, such as the public connotation of confined dredged material disposal (CDMD) facilities as being derelict lands.

For these and other reasons, the Corps of Engineers has commissioned a number of research studies. This study is a component of the Dredged Material Research Program (DMRP). The DMRP is sponsored by the Office of the Chief of Engineers and is under assignment to the U.S. Army Waterways Experiment Station (WES), Vicksburg, Mississippi. The objective of this program is to provide information on the environmental impacts of dredging and dredged material disposal operations and to develop acceptable technical, environmental, and economic methods of dredging and disposal.

This study is coordinated under Task 2C, Containment Area Operation Research, the purpose of which is to create new and improved methods for the operation and management of CDMD sites. Several other areas of research within the DMRP are of interest to this study. These include but are not limited to the contracts commissioned under the following tasks: 2A, Upland and Marsh Disposal Environmental Impacts; 4A, Artificial Marsh and Island Creation; 4B, Habitat Development Research; 4D, Products Research; 5A, Dredged Material Densification; 5C, Disposal Area Reuse Research; and 5D, Disposal Area Land-Use Concepts.

**The purpose of this study was to aid personnel of the Army Corps of Engineers in the landscape development of CDMD facilities. The study was approached first through a comprehensive review of literature on the operation of CDMD facilities. Knowledge of operations thus obtained was augmented by interviewing personnel and visiting disposal sites at the following selected Corps Districts: Philadelphia, Pennsylvania; Norfolk, Virginia, (Craney Island); Charleston, South Carolina, (Daniel Island, Drum Island); New Orleans, Louisiana; Galveston, Texas, (Pelican Island, Pasadena Site #5 and #6); Mobile, Alabama; Buffalo, New York, (Times Beach Site #2); Detroit, Michigan, (Grassy Island, Mud Island); Portland, Oregon. Data were requested of all Corps Districts and selected state agencies as to the adaptability of vegetation at existing disposal sites. Analysis was then applied to determine the constraints to landscape development inherent in CDMD facility operations. Landscape architectural modes and civil works analogous to CDMD sites were reviewed to identify applicable principles and techniques of landform modification and vegetative management. Landscape development concepts were synthesized from the analysis and screened for technical, economic, and environmental feasibility. Finally, concept and technical guidelines were developed and plant lists of known and potential dredged material adaptive species were compiled.**

**This report is therefore essentially divided into three parts. Part I reviews the state-of-the-art in the design, construction, maintenance, and operation of confined dredged material disposal facilities for the purpose of identifying the engineering constraints and variables relevant to landscape development. Part II presents a general discussion of the principles and practices of the profession of landscape architecture as they relate to the landscape development of CDMD facilities. Part III synthesizes appropriate landscape architectural design, planting, and construction technique concepts with the constraints and variables identified in Part I in an illustrated format suitable for use by Corps of Engineers personnel and consultants responsible for the landscape development of CDMD facilities.**

**A CDMD facility can and should be effective in a functional and**

aesthetic sense. Through a program of development carefully coordinated with engineers and landscape architects, CDM sites can become integral and acceptable components of the existing landscape, environmentally and aesthetically. Although many recommendations and alternatives applicable to the landscape development of CDM sites are dealt with in depth in ensuing sections, two principles merit emphasis here.

1. A CDM facility should not be treated as a separate entity, but should reflect in its design a consideration for the present and future patterns of adjacent land use and land form
2. The landscape development of a CDM facility should be planned on an equal level and in concert with the engineering and functional requirements of the facility.

Aesthetic inputs into any project development need not and should not be a hindrance to the functioning of the facility. Landscape development of CDM sites can aid in the functional operation of the facilities and contribute to improved acceptability in the eyes of the public.

## **PART I: EXISTING CDMD DESIGN AND CONSTRUCTION CONCEPTS - CONSTRAINTS AND VARIABLES FOR LANDSCAPE DEVELOPMENT**

### **A. INTRODUCTION**

The purpose of Part I is to present a concise summary of the pertinent concepts related to the design and construction of CDMD sites in order to define how these concepts will constrain or enhance potential landscape development of the sites. The material is subdivided into three major sections: planning considerations, engineering considerations, and operation and maintenance of CDMD facilities. Within each section, constraints and/or variables related to landscape development are identified by means of verbal and graphic explanation.

### **B. PLANNING CONSIDERATIONS**


#### **1. General**

To date, the dredging contractor, and to some degree the Corps, is generally responsible for: a) selecting disposal sites for dredging projects; b) securing public ownership of the sites or obtaining easements to allow temporary use of the sites for disposal operations; c) designing and constructing containment facilities; and d) filling the sites with dredged material. The Corps' responsibility derives from statutory obligations, from internal Corps directives, and from contractual agreements that the Corps may enter into with private owners, contractors, or other public agencies.


Other agencies and groups are increasingly involved in the Planning Process, particularly since public and private groups are becoming increasingly concerned about the environmental problems associated with CDMD projects. The questions of which sites to select for CDMD facilities and of how to determine future uses of the sites necessitate coordination with local public agencies and other interest groups.




Site selection should carefully consider economic and environmental factors, social and aesthetic concerns, and the initial and long-range relationship between anticipated site uses and adjacent land uses. Economic considerations require the selection of a site close to the source of the dredging operations to minimize transportation and construction costs. Environmental considerations necessitate the selection of locations where natural ecosystems will not be damaged and where adjacent human settlements will not be adversely affected by disposal operations. Land-use considerations require locations to be found that will be consistent with local community plans and development objectives, state land-use or coastal zone plans, environmental impact assessment requirements, and Federal permit system and other review requirements.



*Function of distance*




*Protection of resources*




*Proper land-use decisions*

In the future, it is likely that greater emphasis will be placed on selecting fewer but larger sites. Sites may also be located farther from the sources of the dredged material because of environmental considerations, improved technology, or the lack of available sites in proximity to the dredging area. Where large sites are still available, remote from population centers and fragile ecosystems but close to the rivers or harbors where maintenance dredging is needed, conventional transporting and filling practices can be used. Where more remote sites must be used, long-distance piping or hauling may be required.



Analysis of the relation of the proposed CDMD facility to the surrounding landscape in the planning phase will help in the determination

**of:** Land Uses  
Site Configuration  
Earth Forms  
Environmental Safeguards



Analysis of the existing vegetation surrounding the proposed CDMD site will help in the selection of plants which are suitable to the area. Native species will revegetate most easily.

### 3. Ownership of Sites

Project sites can be secured by the Corps; by a public project sponsor, such as a city, town, or port authority; or by a private contractor. Sites can either be purchased or leased by a public agency or be secured from private owners as easements for temporary use. In the latter case, owners can place restrictions on the use of the site, such as specifying the maximum height to which the dredged material may be dumped.

In such cases where Federal or state regulation prohibit open-water dumping of contaminated dredged material (e.g. EPA prohibition of open-water dumping in the Great Lakes), the Corps may require state and local sponsor agencies to obtain appropriate sites and provide containment facilities.

In any case, the public or private owner should be consulted with regard to land reuse objectives and community and aesthetic concerns. In the event that costs for landscape development are borne in whole or in part by the owner, the necessity for such consultation will be obvious. The desirability of constructive discussion with site

owners and local planners concerning community and aesthetic objectives should also be apparent.

#### 4. Interim and Future Uses of Sites

In planning for site utilization, concurrent and future use of the site must be considered. In the early history (20-30 years ago) of CMD projects, sites were generally selected and developed without much consideration for potential future uses; it was generally assumed that project sites would remain derelict land unless a private owner could generate constructive reuse plans for the area. Now, increasing attention is being placed on future uses of the site. Some feasible uses include wildlife preserves, public recreation areas, agricultural areas, livestock grazing areas, and industrial parks. Marsh habitats can also be restored in many areas where marshland has been lost as a result of natural causes or human development. New marshland can be also created in suitable areas. In the future, as land for urban needs becomes more and more scarce, CMD sites may be used for a greater variety of purposes and intensities of use.

Also, coordinated concurrent or interim use of CMD facilities should be considered, particularly where maintenance dredging operations occur at lengthy intervals. Temporary camping and trailer park uses are conceivable, as are grazing pastures for livestock or plant nurseries.

#### 5. Responsibility for Construction and Operation of Sites

The Corps must receive authorization from Congress for the planning and execution of all major projects.

Once a site is selected, ownership or agreement for use of the site is secured and future use commitments are made, then design and construction of the retention structures can proceed. The design process is clearly becoming a primary responsibility of the Corps since in the past, where this responsibility has been delegated to private contractors or local sponsors, the results have often proved to be

unsatisfactory. The Corps has the technical expertise and considerable experience in the preparation of design plans and specifications for containment facility construction; when engineers, landscape architects, and environmental or resource planners can be coordinated in a joint effort, results can be achieved of an unquestionable quality.

In those Corps Districts where equipment and manpower are available to perform actual construction, the need for private contractors may not arise. Ordinarily, such Corps manpower is not available and contractors perform this work under Corps supervision. In either case, site planning considerations and future landscape development should be considered during the preplanning stage and incorporated into the plans and specifications for CMDM site construction.

## **6. Environmental Review**

The National Environmental Policy Act (NEPA) requires environmental impact statements to be filed for Federal projects that induce adverse effects on the environment. Corps guidelines under NEPA require the preparation of environmental impact statements (EIS) for both proposed and existing dredged material disposal projects. These must be distributed to public agencies for comment.

The NEPA also authorizes the EPA to monitor the pollution content of dredged material. Monitoring of effluent quality is the responsibility of state or regional agencies.

Other legislation applicable to Corps dredged material containment projects include such legislation as the 1970 River and Harbor Act (PL 91-611), which restricted many Great Lakes disposal operations to confined sites, where polluted material was present.

## **7. Public Review and Response to Projects**

People traveling, living, working, or participating in recreation activities in the vicinity of CMDM facilities are becoming increasingly sensitive to CMDM facility appearance. A primary public

concern is the possibility of dike failure, which can cause flooding, turbidity, and the release of toxic pollutants. Other problems that can occur include erosion, excessive dust, disturbing odor, increased mosquito breeding, project unsightliness, disruption of ecological systems, nonconforming future uses of the disposal site, and decreases in the property values of adjacent lands (Harrison and Chisholm 1974). Although many of these sources of public or community dissatisfaction cannot be easily remedied by facility design, imaginative and feasible landscape development can, in many instances, ameliorate visual problems, improve recreation and amenity reuse, and increase public acceptability.

8. Corps Directives and Guidance on Landscape Development and Funding

The U.S. Army Corps of Engineers' policy strongly supports aesthetic protection on civil works projects. Personnel involved with landscape development of a CDM facility should be well acquainted with the two Corps documents that deal with this area of concern: ER 1165-2-2, "Consideration of Aesthetic Values in Water Resource Development," (1967) and EM 1110-2-38, "Environmental Quality in Design of Civil Works Projects" (1971). Engineering manuals (EM) are intended to aid design engineers in their design responsibilities on various projects. Engineering regulations (ER) are written in regards to Federal legislation applicable to U.S. Army Corps of Engineer work. Both are intended as guidance documents rather than as fixed directives relative to project design (Harrison and Chisholm 1974).

ER 1165-2-2 "requires that full consideration be given aesthetic factors in the planning and carrying out of the Civil Works Program" General policy instructs that Corps personnel "will consider both the economic and aesthetic consequences of its recommendations and actions," and "where it is found possible to improve natural conditions at a cost warranted by the aesthetic values created, the enhancement of natural beauty may be made a purpose of the project."

To date, funding for aesthetic development related to recreation

at Corps projects is authorized under PL 89-72, the Federal Water Project Recreation Act. Under the act, the Federal government will split recreational development costs with the State or other non-Federal agency involved on a 50%-50% cost-sharing basis. Costs for aesthetic development not relating to recreation or other economic benefits are assumed in total by the Federal government. By relating the aesthetic development of CDMO sites to future public recreation use, it may be possible to allocate a certain portion of landscape development costs to local sponsors and other local and State agencies. It is also important to realize that aesthetic development need not be thought of as an additive cost to a project, but rather as an integral part of any project in that it can promote public acceptance, aid in achieving such engineering requirements as erosion protection, and enhance programs for proposed future uses.

EM 1110-Z-38 deals with planning policies for environmental quality in design and emphasizes the maintenance and improvement of the environment from the initiation of a project: "Incorporating environmental quality in project design involves considerably more than a superficial treatment of aesthetics. It involves designing with nature in all of its dimensions--ecological, visual, and human-cultural--rather than against or onto it."

Since proper input and coordination with project engineering, construction, operation, and maintenance is essential, landscape development concepts and design guidance must be introduced to the design process when project planning is initiated. Project staff should also include qualified landscape architects, botanists, and other suitably trained professionals, or outside expertise should be secured when such capabilities are not present.

## **C.       ENGINEERING       CONSIDERATIONS**

### **1.       Introduction**


Of primary concern in assessing the potential for landscape development of CMDM sites are the limitations imposed by engineering factors affecting the functioning of the containment facility. Since the major function of the design of a CMDM facility is to confine the dredged material to a particular area, the degree to which landscape development concepts can be employed to enhance the appearance and future use of the site will be dependent on the extent to which the concepts can be applied without interfering with the functioning of the facility. Thus it is important for the design professional involved with formulating a landscape development plan to be familiar with the engineering constraints and variables associated with the functioning of a CMDM facility. These factors are discussed in the following sections.

### **2.       Dredging Techniques**

While the dredging operation itself will not directly affect the landscape development of the CMDM facility, the differing types of dredged material excavated by the various dredging techniques and the transport methods used to carry the material from the excavation site to the disposal area will pose certain constraints for earth-forming and vegetation planting. (Mechanically dredged material is generally transported via scow or barge to the CMDM sites). These constraints are discussed in Section C-5 below (Disposal Area Problems). A brief listing of the various types of machinery is given here, however, to familiarize the reader with the pertinent techniques.


#### **a.   Hydraulic dredges**

Hydraulic dredges may be either of two types:



**Pipeline:** The pipeline dredge is the most versatile and commonly used type of dredge plant. Large volumes of material (up to 5000 cubic yards/hour depending on pump size and

intake pipe diameter) can be handled using a cutterhead and suction head which sucks the sediment material from the bottom. The pipeline method can be used to dredge continuously at depths of up to 100 feet. The material is transported to the disposal site via pipeline.




**Hopper:** The hopper dredge is a self-propelled vessel that uses a drag to suck sediment from the bottom. The dredged material is then loaded into hoppers and dumped into a

rehandling basin or pumped to the CMD site. Hopper dredging is limited to depths of 60 to 70 feet. Dredging activities must be discontinued while the dredged material is transported to the disposal site.


#### b. Mechanical dredges

There are three types of mechanical dredges:




**Ladder:** The ladder dredge uses a continuous chain of buckets on a pivot arm. The dredger is mounted on a barge and usually cannot operate in depths greater than 40 feet.





**Dipper:** The dipper dredge consists of a power shovel mounted on a barge and is particularly useful for excavating hard bottom material, in depths less than 60 feet.



**Bucket:** The bucket dredge consists of a crane-operated bucket (clanshell, orange-peel, or dragline) mounted on a barge. It can operate in depths up to 100 feet.

### 3. Retention Structures


Since the dredged material to be disposed of at a confined site is usually in the form of a slurry, a retention structure or dike is commonly used to confine the material to the site. In addition, the retention structure functions to direct the water runoff from the dredged material to the point or points where the water is discharged to the adjacent water body, thus facilitating the drying out of the site. Obviously then, the design and construction of the retention structure will significantly determine the configuration of the dredged material disposal site and its subsequent aesthetic appearance.

On the following cross-section diagram given in Figure 1, a few of the key terms associated with dike construction are illustrated.

#### a. Types of dikes


The types of dikes which can be used for retention purposes will differ primarily in their construction material and not in their form. Dikes are often built in stages: the initial dike and subsequent incremental dikes that increase the height of the original structure as the height of the mass of disposed material rises. Since

**Figure: 1**      **Retention Structure Terminology**




the filling operations may continue for many years (in some cases for as many as 20 or 25), it is not usually necessary to construct the retention structure to its final height at the outset. In addition, the dike and foundation will gain in shear strength over time, as the material consolidates. However, in the situation where adequate construction material is initially available, it may be more economical to build the initial retention structure to its final height and long-range capacity since the machinery and manpower will be on site at the outset.


Incremental dikes may be of cast form or of stepped form as shown in the following illustrations.



- a. Cast dike placed directly on top of *initial dike*




- b. Minimum stepped dike placed on top of *initial dike* but stepped back from the face of the *initial dike*




- c. *Maximum* stepped dike is separated from the *initial dike* by a flat berm or a small drainage channel

With regard to the implications for landscape development, the final shape or configuration of the disposal area will be significantly influenced by the design of the initial dike, since the initial dike will provide the foundation for subsequent retention structures. The incremental dikes, on the other hand, will by their design affect significantly the visible height and silhouette appearance of the disposal site.




*Design of the initial dike determines the final configuration of the disposal site.*




*Design of incremental dikes affect the visible height and silhouette of the disposal site.*

#### **b. Structural criteria**


**The structural criteria diagrammatically illustrated below must be satisfied in dike construction and will constrain landscape development by affecting the dimensions of the dike and the types of construction materials used.**




*a. The slopes of the dikes must be stable under all foreseeable conditions and circumstances for the life of the disposal facility*




*b. The dike must not place excessive stresses on the foundation and must be stable against sliding*



*c. Seepage flow of water from inside to outside of the dike must be controlled to prevent sloughing of the outer slope of the dike*



- d. The freeboard must be great enough to prevent "overtopping" erosion by waves from inside the dike



- e. Unless overbuilt, a dike may settle and require placement of additional material. This may preclude *initial* earth-forming and planting of dikes.

#### c. **Foundation conditions**

Ideally, a firm foundation should be established before the dike is placed so that the stability of the dike can be ensured. However, in most locations where CMD facilities are sited, the underlying material is generally soft and susceptible to subsidence under the extreme loads of the dike material and the dredged material. To make the dike stable would require removing the material and replacing it with granular material. This is obviously expensive and is often difficult to do. Therefore, settling of the dike material must be accepted and accommodated.

A weak foundation condition many times requires the construction of a wide-based dike section. Even so, the dike material can be expected to consolidate considerably. In subsoil deposits of clay and silt, consolidation occurs slowly, but will occur nonetheless. In some cases the placement of dike foundation material on a soft existing material will actually cause the poorer material to be displaced, thus establishing a firmer foundation. This method reduces the width of base required.


#### d. **Types of material used**

Dike materials should be stable. This generally means the use of a granular material, either stone or gravel, or material

low in organic content. In a few cases this requires importing a granular material to the site from an off-site source, since most of the native soils that could be borrowed at the site (generally riparian) are silty and not ideal for dike construction. Clay, when properly compacted, is often acceptable. In some cases it may be possible to obtain gravel or bedrock materials from deep river-bottom excavations, which will facilitate transport to the site by boats. In some cases an inorganic material is used, such as in the Buffalo District where slag is available from nearby steel mills (Murphy and Zeigler, 1974). Generally an initial dredging operation involves the removal of virgin material, which characteristically is a stronger building material than the usually silty materials dredged from subsequent maintenance operations. In most cases, however, the dike material used is available at the site and therefore can impose constraints on the vegetation used.


#### e. Construction techniques

There are three basic techniques for constructing the dike as illustrated in the following diagrams. The determining factors for selecting one technique over another, or in combination, are the type of fill material, the source of the material, and, of course, the economics of the situation, including the transport distance and the availability and costs of various equipment and manpower.




##### a. Rolled or dumped fill:

*This type of dike is employed where a land borrow source of acceptable quality is available within reasonable hauling distance of the site*



- b. Hydraulic fill: The ideal situation for construction of a disposal area in the water is that in which suitable borrow material for a hydraulic

fill dike is encountered inside the disposal area.






- c. Dragline fill: When materials suitable for dike construction are available along the dike alignment, dike construction by barge-mounted dragline is often

the most economical method of construction. The best materials for this construction are sand and gravel.

**Table 1 summarizes the construction methods used to build the various types of dikes and lists several aesthetic and landscape development constraints.**

**Table: 1****Incremental Retention Structure Construction**

	DIKE BASE 2-8' 	PRIMARY DIKE 6-10' 	CAST INCREMENT 	SEE
PREDOMINANT FUNCTIONS	Base of dike in open water	Formed to increase height and improve cross-section of dike base.	Use of materials of low stability to increase dike height.	Used and are attached initially cast
CONSTRUCTION METHOD <sup>2</sup>	Hydraulic Placement  Rolled or Dumped Fill (by vehicles)  Dragline  NA	Dredged material (DM) spread in open water along axis of retention structure (RS).  NA	NA  Vehicles/equipment manipulate and form RS.  Dragline manipulates and forms RS.	Vehicles/equipment manipulate and form RS.  Dragline manipulates and forms RS.
CHARACTERISTIC SHEAR <sup>2</sup> STRENGTH OF DEPOSITED MATERIALS	Poor; material placed and attains natural slope.	Poor-good; engineered form increases stability.	Poor. Materials placed, self-attained slopes.	Good
ECONOMICS OF METHOD <sup>3</sup>	NA	NA	Generally least expensive to attain given height.	General model
AESTHETICS AND GENERAL CONSTRAINTS  LANDSCAPE DEVELOPMENT CONSTRAINTS	Barren but natural in appearance other than geometric/non-natural process form.  Initial construction stage, no landscape development possible	Barren in appearance. Slope facings may detract visually (see Table 4).  Vehicular access, if provided, constrains usable space for aesthetic improvements. If it is an incremental RS, planting and aesthetic improvements may be temporary/delayed.	Barren in appearance; generally not protected by riprap or other extensive coverings. Low height, therefore, minimal visual effect.  Since last increment for RS of poor quality DM, RS can be planted. Minimal vehicular access.	Height line with may dent step  Initial Vehicular appearance





<sup>1</sup>Interviews, District personnel (refer to Introduction)

<sup>2</sup>Murphy and Ziegler, 1974.

<sup>3</sup>Interviews, District personnel



# on Structure Construction

PRIMARY DIKE 6-10'	CAST INCREMENT 10-12'	SECONDARY DIKE 15-25'	SECONDARY DIKE (WITH SETBACK) 15-40'
			
Formed to increase height and improve cross-section of dike base.	Use of materials of low stability to increase dike height.	Used where added materials and foundation conditions are highly stable. Associated with inland sites. Usually constructed after initial RS in lieu of the cast RS.	Used where added materials and foundation conditions are highly stable and greater heights are needed. Associated with inland site.
NA (not applicable)	NA	NA	NA
Vehicles/equipment manipulate and form RS.	Vehicles/equipment manipulate and form RS.	Vehicles/equipment transport selected DM for addition to RS.	Vehicles/equipment transport selected DM for addition to RS.
Dragline manipulates and forms RS.	Dragline manipulates and forms RS.	Dragline raises DM and shapes RS.	Dragline raises DM and shapes RS.
Poor-good; engineered form increases stability.	Poor'. Materials placed, self-attained slopes.	Good.	Good.
NA	Generally least expensive to attain given height.	Generally inexpensive; low to moderate quantities of material are used.	Generally expensive; large quantities of material are used.
Barren in appearance. Slope facings may detract visually (see Table 4).	Barren in appearance; generally not protected by riprap or other extensive coverings. Low height, therefore, minimal visual effect.	Height predominates. Views and lines of site may be blocked without careful planning. Height may seem imposing in rural residential areas unless it is stepped back sufficiently.	Height predominates, minimized however by increased setback. Geometric shape less predominant due to setback.
Vehicular access, if provided, constrains usable space for aesthetic improvements. If it is an incremental RS, planting and aesthetic improvements may be temporary/delayed.	Since last increment for RS of poor quality DM, RS can be planted. Minimal vehicular access.	Initial RS can be planted. Vehicular access may move to upper RS crown, freeing additional areas.	Greater area can be planted. Planting can visually minimize effect of height and geometric shape.

**f. Embankment slopes and crown widths**

The slope of the dike embankment is dependent on: the foundation conditions, the embankment material used, the type of construction technique employed, and the necessity for additional erosion protection devices. For example, a weak foundation condition will necessitate the construction of a flat slope dike with a wide foundation base; in some cases exterior dike slopes as flat as 30H on 1V may be required. As a general rule, if the dike is composed of firm material, a steeper slope can be used. Retention structure slopes are normally limited to 3H on 1V. If the slope is to be protected from erosion by riprap or other materials, the slope can be made steeper.

A 2H on 1V slope is generally accepted as the steepest slope that permits machine placement of the riprap. In addition, the stability of the riprap is questionable on steeper slopes (Department of Army, in preparation).

Table 2 gives the slopes that the different types of material require to withstand the effects of erosion.

**Table 2** Optimal Slope Design

Erosion source: Cover	rain, wind	rain, wind	+ waves	+ waves*
	bare	vegetated	riprap	bare/vegetated
sand & silt	6H on 1V max. ** 6H on 1V opt.	2 or 3H on 1V max. 4H on 1V opt.	2H on 1V max. 4H on 1V opt.	15H on 1V max. 15H on 1V opt.
clays	2H on 1V max. 4H on 1V opt.	1H on 1V max. 3H on 1V opt.	2H on 1V max. 3H on 1V opt.	15H on 1V max. 15H on 1V opt.

\* Department of the Army, 1971, EM1110-2-28


\*\* Shallower slopes are more desirable to ensure success of the earth form planting, and maintenance; max: maximum slope which withstands erosion; opt: optimum desirable slope.

The slope of the dike may be varied: where poor foundation conditions must be accommodated a shallow slope below the water line may be necessitated; while above the water line, a steeper riprap slope can be constructed.


The width of the crowns of the dike can also vary greatly, depending on the design requirements of the dike. If the dike is to serve as a base for an incremental dike, it should be sufficiently wide, approximately six to eight feet, to accommodate the new material. If the dike is to accommodate operational and maintenance vehicles (dragline cranes, bulldozers, or trucks), the crown width should be increased to approximately 12 to 14 feet.

As shown below, the slopes and crown widths of the dikes will constrain the planting of vegetation and subsequent uses of the dike.

Care should be taken in the placement of vegetation during the operation of the CMD facility so as not to jeopardize the integrity of the retention structure. It should be noted that insufficient research has been conducted to date on the need for root-free zones on exterior dikes.



*A steep dike slope may require special planting techniques for vegetation*



*Crown widths determine the type and placement of planting which can occur, especially if vehicles have to move along the top of the dike*


#### **g. Water release devices**

Devices for releasing the excess water from the disposal operation are integrally related to the retention structure. Since water passing over the dike would cause erosion, several sluicing devices have been developed to let the water pass out of the disposal area. These include outfall pipes, siphons,


drop inlet sluices, and box sluices or flumes. There are various supplementary appurtenances that can accompany these basic types, such as silting basins, Y or E - gates, outlet channels, and oil skimmers. The relationship of the sluice gates to the discharge points and internal structures are explained in Section 6: Disposal Area Problems.

A discussion of the sluice types and accompanying appurtenances is not particularly relevant to landscaping enhancement of retention structures, since these devices are small and relatively inconspicuous compared to the total length and mass of the dike and disposal area. The water quality of the effluent is a significant problem but again not directly relevant to this study.

Another technique for removing water from a site allows the water to seep through the dike. This will occur naturally to some extent, especially when granular materials comprise the dike section. However, to maximize the efficiency of seepage dewatering and to prevent erosion due to sloughing, it may be desirable to use one of the filtering mechanisms illustrated below.



Dike filter: A stone blanket comprised of sand, gravel, and stone or a filter blanket and stone on the exterior side of the dike to filter effluent as the water seeps through the dike.



Vertical sand filter: Steel cells filled with a granular material to filter effluent; this structure can be incorporated into an earth dike

#### **4.      Retention Structure Physical Problems**

The problems that cause dike failure or damage can be summarized under three categories: 1) foundation failures; 2) surface erosion; and 3) seepage damage. In addition, certain visual problems may result from the construction of retention structures, such as the obstruction of views from certain vantage points and the intrusion of man-made elements with a mechanical appearance into the natural landscape.

##### **a.    Foundation failures**


Structural damage to dikes is often the result of foundation failures. A dike may sink into a soft, organic foundation or may spread due to the sliding of the foundation along soft clay strata or sandy seams. The remedies for these problems are dependent upon treatment of the foundation materials or a priori careful analysis of the foundation bed and the design of a suitable dike section, and as such can be little influenced by landscaping design.

##### **b.    Surface erosion**

Wave action is the primary cause of dike erosion. Where dikes are located within or directly adjacent to water bodies, waves can erode the exterior embankments of the dike. On all kinds of disposal facilities, regardless of the location, the water impounded in the interior of the dike can erode the inside face of the dike and often the entire dike due to overtopping. Rain, ice, and, to some extent wind forces can also cause erosion on dike surfaces. In some cases, erosion of the dike may occur near the sluicing device, especially when the discharge point is too close to the outfall pier or weir.

There are several possible engineering remedies to correct these problems of erosion. On the exterior face of the dike, the chief techniques call for armored protection (the use of riprapping) or the creation of a sand-filled beach at the

foot of the dike in water. The riprapping should extend from a point several feet below mean low water to an elevation at least several feet above mean high water, ideally meeting the protected crown. Its thickness will vary according to the degree of protection required. A sand beach should be constructed so that it maintains an average slope of 10H on 1V.



Riprapping may also be used on the interior face of the dike in large facilities. Impervious material such as polyethylene sheeting may also be used for interior slope protection. It may also be possible to stabilize the top surface of the dike by an impervious material; asphaltic concrete, which also serves as a roadway surface, is an obvious possibility. However, the use of such material, as with riprap, is considered an extreme measure to be used only when initial dikes are constructed in open water and thus exposed to the extreme forces of wind and waves (sometimes to hurricane forces).

The use of vegetation as an erosion-control device is a logical option to consider, either by itself or in conjunction with the above engineering solutions. This technique is used by some Corps Districts to a limited degree. The use of vegetation for erosion control, as well as other equally important uses, is discussed in Part II.


#### C. Seepage damage

Seepage, or passage of water through the dike, can cause

dike failure or damage by piping, an interior eroding of the dike material caused by the movement of water and resulting in the loss of the final particles, or by sloughing off, a sliding of materials away from the outer edge of the dike.

The release of pollutants, including salt to the surrounding area is another potential problem related to seepage. The polluted or saline material can detrimentally affect surrounding vegetation as well as animal life.

Solutions to seepage include providing an impermeable barrier either in the dike or on the inside surface of the dike. Another possibility is the use of dike filters, which allow water to pass through but which filter out pollutants in particulate form and prevent the erosive effects of seepage.



*Artificial seepage barriers, riprap, polyethylene, and asphalt, all restrict planting or use areas*

A summary of the physical problems associated with retention structures in relation to constraints on landscape development, earth-forming, and planting is given in Table 3.

#### d. Visual problems

Visual problems associated with the dike (as distinguished from the entire retention area) are significant to persons viewing the facility from the ground plane, i.e., from the adjacent shoreline or from boats on the water. The dike, when it is part of an island or peninsular facility, is a large physical obstruction to views across the body of water in which it lies. The artificial characteristics of the dike, namely its rigidity if linear, its hard surface quality if covered with riprap, and its disproportionate massiveness, can disrupt the visual harmony of the landscape. Methods of reducing such visual disruptions are discussed more

**Table: 3****Retention Structure Problems and Remedies**

<b>PROBLEMS</b>		<b>REMEDIES</b>		
<b>RETENTION STRUCTURE PROBLEMS</b>	<b>CONTRIBUTING FACTORS</b>	<b>BASIC REMEDIES</b>	<b>CRITICAL MEASURES</b>	
<b>Foundation failures</b>	<b>Soft bottom mt break- through or sliding failure</b>	<b>Reconstruction</b>	<b>Replacement of foundation and RS.</b>	
<b>Erosion</b>	<b>Waves Wind Rain Ice</b>	<b>Asphalt</b>	<b>Should cover entire crown and meet riprap to offset increased wave runup and possible overtopping</b>	<b>Extreme initial RS on to extr</b>
	<b>Waves Wind Rain Ice</b>	<b>Riprap, tetrapods, precast concrete revetments</b>	<b>Should extend Sufficiently above and below water line and be of sufficient thick- ness to withstand dynamic forces</b>	<b>Expensi</b>
	<b>Waves Wind Rain</b>	<b>Polyethelene sheeting (interior slope only)</b>	<b>Should be well secured</b>	<b>Tempora ates wi of inst sun's m niovemen this pr</b>
	<b>Waves</b>	<b>Sand Beach</b>	<b>Should average 10H on 1V slope from MHW to MLW lines</b>	<b>Natural elimina Placed</b>
	<b>Waves Wind Rain Ice</b>	<b>Vegetation</b>	<b>Should achieve a dense growth of grasses and other vegetation in minimum time possible.</b>	<b>Natural</b>
<b>Seepage/ Bleeding</b>	<b>Excessive per- meability or trapping of water and sub- sequent washout of RS section.</b>	<b>Polyethelene sheeting</b>	<b>Should be secured with sand bags or other means on interior slope prior to disposal operation.</b>	<b>Tempora until d suffici</b>



	AESTHETIC AND GENERAL CONSTRAINTS	LANDSCAPE DEVELOPMENT CONSTRAINTS	
		EARTH-FORMING	PLANTING
ation	NA	Height and slope of base limited by the strength characteristics of the foundation material.	NA
crown ffset and	Extremely expensive; used in initial construction of RS on large projects subject to extreme exposure.	Height and slope of RS limited according to method of erosion control employed; riprap and precast concrete allow greater heights. Intricate land forms may accentuate erosion process.	Placement prohibits vegetation until secondary RS is built.
ciently r line thick- namic	Expensive solution		Placement prohibits plantings.
ed	Temporary. Unusually deteriorates within 6 months to 1 year of installation. Action of sun's rays, rodents, wind, and movement of DM will speed up this process.		Polyethelene sheeting does' not allow immediate planting (on interior face of RS ); may generally disintegrate within 6 months to 1 year.
n IV W lines.	Natural appearance. May eliminate need for riprap. Placed on outside of RS only.		Vegetation will only grow above MLW in high wave energy areas.
se d other m time	Natural appearance.	Seepage must be controlled before earth-forming.	Possible time lag between end of construction period and establishment of an effective cover.
th sand on to	Temporary, but generally lasts until dike permeability is sufficiently reduced by fines.		Polyethelene sheeting does not allow immediate planting (on interior face of RS ); may generally disintegrate within 6 months to 1 year. Salts may leach out and destroy surrounding vegetation where material is dredged from saltwater bottom and placed in freshwater surroundings.

fully in Part III of this report. However a brief summary focusing on the characteristics of dike facings which affect visual quality is presented in Table 4.

5. Disposal Area

As stated earlier, "the principal objective of a dredged material containment facility is the retention of solid particles and the release of clean water to natural water." (Murphy and Zeigler,, 1974). Thus a potential land mass, the disposal area, is created as a result of the retention of the dredged material. Characteristics of the disposal area and methods for dispersing the dredged material within disposal sites are discussed in subsequent sections as they relate to constraints and variables affecting landscape development.

a. Shape, size, and height of the disposal area

The volume of material to be dredged and the number and frequency of times a site is to be filled will significantly affect the resultant shape, size, and height of the disposal area. When calculating the allowable volume and frequency of filling to occur at a disposal area, the type of foundation material already present at the CMD site and the composition of the dredged material to be added must be analyzed to determine the amount of settlement, consolidation, and/or bulking that will occur. Certain other factors, such as the slurry discharge rate, the ponding time, and the rate of excess water runoff, will also influence the size and height of the disposal area (Murphy and Zeigler, 1974).

Generally, CMD facilities are polygonal or follow convenient natural contours, primarily for ease of layout and construction. Where foundation materials are poor or structurally sound building material is scarce, the retention structure will be built along a natural deposit of solid material such as a low rise of land or a sandbar. In such cases,

**Table 4** Visual Characteristics of CDMD Facility Components

<p><b>SILHOUETTE</b>  <b>Consider lines of sight.</b> Views from surrounding land and water areas determined important by surrounding inhabitants and from an on-site investigation should be preserved and enhanced where possible.</p>			
<p><b>SHAPE</b>  <b>Consider the shape and form of the CDMD site in relation to the surrounding land forms :</b> undeveloped natural/rural areas generally suggest curvilinear shapes; developed urban/industrial areas may suggest the use of more geometric forms or the intermittent use of curvilinear forms.</p>			
FACINGS	NEAR VIEW	FAR VIEW	RECREATIONAL USE CONSTRAINTS
Tetrapods/ Dolos	Highly rigid and artificial in form, light, and color. Used primarily in break-water construction.	Impact diminishes with distance, but color will stand out considerably.	Access to/from water edge difficult.
Riprap	Rigid form unappealing, especially if used extensively in natural area	Impact diminishes with distance.	Access to/from water edge difficult.
Precast Concrete Revetments	Highly rigid, negative appearance when barren. Grid design and planting may provide visual interest.	Impact diminishes with distance. Appearance will remain uniform over time.	Access to/from water edge can be accommodated.
Polyethylene Sheeting	Artificial appearance, especially if colored sheeting is used.	Usually visible; however, deterioration will occur within 6 months to 1 year of installation. (Black color deteriorates less.) Impact diminishes with distance.	Prohibits immediate use of planting. Impact diminishes over time with disintegration of the material.
Dredged Material	May be compatible with existing shoreline appearance, but barren without protection. Erosion creates visual scars and unnatural contours.	Impact diminishes with distance.	Access should be controlled to minimize erosion.
Natural Vegetation	Compatible with existing shoreline appearance, but may establish unevenly resulting in a spotty appearance.	May produce desirable effect over the long term but may be spotty.	Use restricted until vegetation is well established.
Induced Vegetation	Compatible, immediate effect. Regularly spaced plantings may result in negative effect; random pattern preferred.	Compatible immediate effect, especially if tall species are planted.	Use restricted until vegetation is well established.

the confined disposal area takes on an irregular and curvilinear shape.

In order to avoid interference with normal water circulation, sediment transport, or salinity patterns in estuaries and other water bodies, disposal facilities must be carefully laid out with respect to currents and benthos.

The areal size of disposal facilities is a function of the frequency of the filling operation; the surface area and the distance from the point of discharge to the point of exit should be great enough to allow the dredged material to settle out before it reaches the exterior of the facility. The size of facilities varies from as small as three acres (Alameda Creek in San Francisco Bay) to as large as 3500 acres (Sabine Lake in Galveston). Size, of course, is limited by the availability of space in the vicinity of dredging operations. Where alternate sites (inland or more distant water edge locations) are beyond feasibility, the facility must be increased in height to accommodate the volume of material to be disposed).

The initial and ultimate height of the disposal facility overall will depend on a number of factors including the volume of material to be dredged over the time span of operations, the requirements for a single or incremental dikes, the aesthetic compatibility of high disposal facilities with the surrounding natural and man-made environment, and future site use.

Although shape, size, and height can be modified only to a limited degree, the modifications that can be made may be significant in visual terms if appropriate guidelines are followed. Briefly, in terms of size, very large projects should preferably be subdivided into several smaller components; in terms of shape, natural contours should be followed or simulated, for both visual and functional (e.g. small harbor) purposes; and in terms of height, the silhouette of the upper elevations of disposal facilities should be varied,


articulated with tree and shrub plantings to achieve aesthetic diversity. Depth above water table of disposed material within the facility will also help determine the types of vegetation which can adapt successfully.

**b. Disposal methods**

Hydraulic and mechanical methods are used to discharge the dredged material into the disposal area. By far the most common and efficient method for large-scale disposal into confined sites is by hydraulic means, i.e., pumping the slurry into the disposal area through pipes, located either above ground or buried underground and/or under water. The source of dredged material will usually be a pipeline dredge. Material pumped out of hopper dredges is common in some areas. A combination technique, which uses a rehandling basin (a deep-dredged pit in the water adjacent to the disposal site), allows the dredged material to be dumped from a variety of dredge types and dredging operations and subsequently pumped into the disposal site.


The hydraulic pumping method is useful for long-distance transport of the slurry. Pipeline distances of 7,000 to 10,000 feet are not uncommon with modern equipment. Distances of 5 miles have been traversed via piping and booster pumps in the Gulf Coast area, and various plans are under consideration by other Districts for longer distance piping.

The slurry which is pumped hydraulically into the disposal area is about 80% water and 20% solid material. The coarser materials settle out first, closer to the pipe outlet. The finer materials, silt and clay, remain in suspension in the slurry water pond and tend to settle out last, near the sluice (or they may also pass through the sluice, causing turbidity in the surrounding water).



*Location of coarse vs. fine material varies along cross section of disposal area.*

A bleedpipe may be used to reduce the velocity of the pumped material and settle out the coarse-grained materials. A diagrammatic illustration of the mechanism appears below




The bottom of the pipe is perforated to permit the coarse-grained material to settle out as the velocity of the slurry is decreased while rising to the elevated end of


the pipe. If appropriately placed, such a mechanism may be useful for reinforcing a dike with the coarse materials.

Mechanical methods of disposing of dredged material into contained sites include the use of dipper dredges, bucket dredges, and ladder dredges, which may be barge mounted or free standing, but these methods are commonly used only on smaller operations due to the limited capacity of such machines. They are also used where floating and/or submerged pipelines can interfere with shipping movements.

Table 5, Confined Disposal Operation Methods, lists these methods and the constraints and opportunities they impose on landscape development. The following two diagrams illustrate some of these concepts.



Hydraulic method provides greatest flexibility in disposal area shape. Compartmentalization will permit a selected portion of the CDMD site to be filled.



Hydraulic method allows CDMD facility to be a great distance from the dredge site.

### C. Characteristics of the material

Dredged material can be categorized according to its major physical properties, including grain size, moisture content, and plasticity.

The material from the maintenance dredging operations of the Corps has been roughly divided into five grain-size groups: A) mud, clay, topsoil, shale; b) silt and sand mixed; C) sand, gravel, shell; D) organic muck, sludge, peat, municipal-industrial waste; and E) mixed. The sand and gravel category is the only coarse-grained dredged material and is therefore generally acceptable for fill where foundation support is required. The finer grained materials generally have high water content, and are therefore not very firm. Organic content can produce objectionable odors when disposed of on land.

The most plentiful quantity of dredged material in the United States is the silt and sand category: 51% of the 300 million cubic yards dredged annually in the United States are in this category. The next most plentiful type (27%) is the mud, clay, silt category (Group A). The third most plentiful (16%) is the coarser grained material, sand and gravel (Group C) (Boyd, et al., 1972).

**Table: 5** Confined Disposal Operation Methods and Landsc

DISPOSAL METHOD	PRINCIPAL OPERATION	DREDGED MATERIAL CHARACTERISTIC	MAXIMUM ECONOMICAL DISTANCE TO DISPOSAL SITE, GENERAL COST CONSIDERATIONS	FLEXIBILITY DISPOSAL
<u>PIPELINE DISPOSAL</u>	Used universally except in areas of heavy navigation, e.g., harbors.	Slurry is generally 80% water, 20% solids.	5+ miles with the use of booster pumps; operations generally large-scale and cost efficient.	Continuous floating Point 0 varies station triple/rate of access retention (RS).
<u>HOPPER DISPOSAL</u> Direct pump-out or bottom dumping barge	Used principally in waters where pipelines would interfere with navigation.	Slurry is generally 80% water, 20% solids.	Slight limitations on distance. Slower and less continuous project executions. Economically suitable for small dredging projects.	Dredged material contained a) placed in barge for pump-out RS then merged from a) alongside
<u>MECHANICAL</u> Dipper Clanshell Bucket (includes drag-lines)	Used principally on very small jobs and in areas unsuitable for pipeline or hopper disposal method.	Oversized debris: mud, clay, rocks. Low water content if transferred directly to CDMD site without use of scows for transfer (which require hydraulic slurring and pump-out).	Slight limitations on distance. Slower and less continuous project execution. Economically suitable for small dredging projects.	Sediment dredged and transferred to CDMD site for lining barge



# Methods and Landscape Development Constraints

ECONOMICAL DISPOSAL AL COST TIONS	FLEXIBILITY OF DISPOSAL METHOD	PIPELINE PLACEMENT CONSTRAINTS	LANDSCAPE DEVELOPMENT CONSTRAINTS
the use of operations large-scale and nt.	Continuous operation, floating pipeline. Point of access varies from a fixed station(s) to mul- tiple/random points of access along retention structure (RS).	<div data-bbox="599 595 1025 1407"> <p><b>Fixed Access Point:</b> Controls placement of DM within the CDMD site with minimal disruption of the RS.</p> <p><b>Multiple/Random Access Points:</b></p> <p>a) Pipe laid directly over RS. Greatest possibility of disruption due to mechanics of pipeline placement</p> <p>b) Spillbarge: minimal disruption of RS in multiple access point operation. Floats along outside of RS 20 ft height and maximum 250 ft. boom Possibility of use within CDMD site which would increase flexibility of placement of DM</p> <p><b>Fixed Access Via Rehandling:</b> Allows greatest flexibility of placement of DM in that DM may be placed within the CDMD site at discretion of CDMD site operators.</p> </div>	<div data-bbox="1084 727 1445 1242"> <p><b>Multiple Access Points:</b> Possible disruption of planting and landforms at various points if access points not controlled and planned into the CDMD site.</p> <p><b>Fixed Access Point(s):</b> Least interference with plantings/landforms</p> </div>
ations on dis- r and less con- ect executions. suitable for ng projects.	Dredged material contained in hopper: a) placed in rehand- ling basin, b) dir- ect pump out into RS through sub- merged pipeline from a fixed point alongside CDMD site.		
ations on dis- er and less con- ect execution. suitable for ng projects.	Sediments are dredged into scows and transferred to CDMD site rehand- ling basin.		

Table 6, Dredged Material Characteristics, illustrates some of the constraints to landscape development characteristic of the different dredged material types. A further discussion may be found in Part III of this report in the section dealing with implementation concepts.

**d. Internal structures**

There are several different kinds of retention structures or dikes that can be constructed within a disposal area. A spur dike is a long arm of raised material that is generally constructed perpendicular to the outer containment structure. It is attached to the outer dike at one end but terminates in the middle of the disposal area. It is generally used to direct the flow of the slurry after it is pumped into the disposal area; this helps to prevent channelization.

A cross dike is a spur dike that is extended so that it connects one side of the containment structure with another and thereby divides the disposal area into compartments; such compartmentalization induces settling out in localized points to hasten the settling process.

A pipe dike, which is a raised linear mound, is often constructed to support a pipe when the point of discharge of the slurry is somewhere in the center of the disposal area. Often pipes are branched-off within the disposal area, and gate valves are inserted at pipe junctions to shut off and open the flow of slurry as required.

**6. Disposal Area Problems**

Typical problems associated with the design and functioning of disposal areas are: too rapid or too slow release of the impounded water; excessive exposure to climatic elements; or visual disruptions. These are discussed below.

**a. Water released too rapidly**

Water that is released too rapidly from the discharge pipe during hydraulic filling operations will tend to dig a channel in the deposited dredged material and follow the shortest route to the sluice. This kind of internal erosion interferes with the normal settlement of the solid dredged material from the slurry. The basic technique for correcting this situation is to direct the slurry flow so that it forms a pond between the discharge pipe and the sluice. The flow of water is slowed and allows the suspended solids to settle out before they can enter the sluice and become discharged into the surrounding water. Another technique is to construct spur dikes to direct the flow of water or to act as baffles to the rapid flow of slurry.

**b. Water released too slowly**

Although the ponding function is necessary, it can become a detriment to the operation if the water is not released through the sluice or the dike filter after a reasonable length of time. This long-term ponding can cause the production of adverse odors or can prevent the establishment of vegetation in the dredged material area. Sometimes excessive rainwater aggravates this condition within a disposal facility. The basic remedy for this problem is to ensure that the sluices or other dewatering devices are working adequately. Sometimes it is simply a matter of adding additional sluices to a large disposal area when only one sluice is present. It may, however, become necessary to reschedule the pumping operation to prohibit further release of the dredged material until the pond level is diminished.

**c. Exposure to the elements**

The effects of wind are generally adverse since wind-blown

**Table: 6****Dredged Material Characteristics and Landscape De**

<b>DREDGED MATERIAL TYPE<sup>1</sup></b>	<b>PARTICLE SIZE</b>	<b>USA DISTRIBUTION<sup>1</sup></b>	<b>SHEAR STRENGTH<sup>1</sup></b>	<b>SUITABILITY AS FOUNDATION MATERIAL</b>	<b>SUI CONST</b>
<b>A. Mid, clay, silt, top- soil, shale</b>	<b>Colloidal to fine</b>	<b>27%</b>	<b>Poor with high water content</b>	<b>Poor to very poor</b>	<b>Poor</b>
<b>B. Silt, sand</b>	<b>Fine to coarse</b>	<b>51%</b>	<b>Poor to fair; vari- able water content</b>	<b>Good to poor</b>	<b>Very fair<sup>1</sup></b>
<b>C. Sand, gravel</b>	<b>Coarse</b>	<b>16%</b>	<b>Good, large grained</b>	<b>Good</b>	<b>Reaso to ve</b>
<b>D. Peat, organ- ic muck, fin sludge, muni cipal wastes</b>	<b>Fine; organic</b>	<b>6%</b>	<b>Poor with high water content</b>	<b>Not suitable</b>	<b>Not s</b>
<b>E. Mixed types</b>	<b>Variable</b>		<b>Variable</b>	<b>Variable</b>	<b>Varial</b>

<sup>1</sup>Boyd, et al., 1972. Note that this is not a formal classification.

## ape Development Constraints

<b>SUITABILITY FOR CONSTRUCTING DIKES</b>	<b>DRAINAGE</b>	<b>AESTHETIC AND GENERAL CONSTRAINTS</b>	<b>LANDSCAPE DEVELOPMENT CONSTRAINTS</b>
<b>Poor stability</b>	<b>Slow</b>	<b>Cracking, rill formations and sloughing</b>	<b>High salt retention; 6 months to 1 year to leach out salts if at all. Shrinkage and cracking; unstable if water saturated</b>
<b>Very stable to fairly stable</b>	<b>Medium</b>	<b>Rill formation, but not as evident as in Type A</b>	<b>Most suitable type for larger vegetation species</b>
<b>Reasonably stable to very stable</b>	<b>Fast</b>	<b>May have barren appearance unless in formation resembling natural littoral land form</b>	<b>Poor fertility. Rapid drainage may promote excessive drought for some induced species</b>
<b>Not suitable</b>	<b>Slow</b>	<b>Objectionable odors; dark appearance; cracking, puddling.</b>	<b>Poor stability; high moisture content. Poor drainage; high organic content; high toxic and heavy metal content in many cases. Generally unsuitable for induced plants if not mixed with other DM types</b>
<b>Variable</b>	<b>Variable</b>	<b>Constraints vary according to component types</b>	<b>Constraints vary according to component types</b>

waves can cause erosion of the dike on the outside slope. If the disposal site is large enough, waves can be generated that may erode the interior slopes. Wind-induced waves can also increase the turbidity of the ponded water, while dust turbulence can be severe on dried-out sites. However, winds lower turbidity if their direction is against the direction of flow from the discharge point to the sluices. Prolonged exposure of the dredged material to the hot sun can create desiccation cracking on the exposed surface of silty, clayey dredged material. This is harmful in that breeding habitats for mosquitoes may be increased. On the other hand, the drying out of the material at greater depths will be hastened.

d. Adverse visual impact

In addition to the technical problems that may occur on disposal areas as described above, there may be other aesthetic problems. For instance, the repeated pumping of new dredged material on top of old dredged material on which vegetation has become established either kills the vegetation or covers it so that only the top branches of trees remain visible, resulting in a grotesque, unnatural appearance. Excessive ponding may result in vegetation kills.

Subsequently, the dead remains of trees reinforce the image of the CMD as a derelict facility. Even desiccation cracks in a hard-baked surface create to some degree the image of a derelict area.

Perhaps of greater concern is the inhuman connotation of an extremely large and undifferentiated disposal area, especially if it is located next to an inhabited area. While a large facility may be efficient from an engineering point of view, it may be out of scale and therefore visually objectionable to people who have to live or work nearby or who come into contact with it during recreational pursuits.

#### **D. OPERATION AND MAINTENANCE OF CDMD FACILITIES**

The primary operational concern of a CDMD facility once it has been constructed initially is the maintenance of the dikes and the control of the location of the pipe used to pump the slurry. This pipe has to be moved to permit the efficient functioning of the disposal operation: namely, to maintain the proper ponding time and discharge rate.

Often the pipe is moved along the face of the dike, especially with the floating pipeline technique used in the Gulf Coast. The Great Lakes Districts generally utilize a method whereby the slurry enters the CDMD site at a fixed point, but the pipe within the dredged material area is moved.

In the Galveston District, pipelines are often carried great distances across the land from the edge of the channels to the point of slurry discharge into a CDMD facility. At Pelican Island, in Galveston Bay, separate pipes pass on the surface of the land, but under a new roadway through culverts, to the disposal area. Permanent easements are usually provided. In either case, equipment is necessary to move the pipes at the disposal site itself. Generally a bulldozer is used for this operation.

Another operational concern is the future construction of incremental dikes or expansion of the site to increase the capacity of the facility. The technique used to construct the incremental dike must be anticipated, so that the equipment necessary to do the job can be accommodated. A dragline that moves along the initial dike or the inside toe of the dike on dredged material is usually required to build incremental dikes. A bulldozer or other earth-moving machine may also be required to shape the new secondary dike.

Another characteristic of the filling operation is its periodic nature. Rarely is this operation continuous throughout the year for any one disposal facility. There is generally not enough material from maintenance dredging operations in any District to warrant a year-round operation. Also, equipment is shared from one port or channel to another within a District, as in the Great Lakes ports where the hopper

dredges make the rounds. At the mouth of the Mississippi River, the sedimentation process is seasonal (February to June), thus necessitating only seasonal dredging operations.

In many Districts, maintenance dredging is not necessarily performed each year. Therefore, there does not have to be continuous surveillance and maintenance of the components of the CDMD. Dikes and weirs must of course be maintained during the filling and dewatering operation, and the free board must be maintained. It is advisable to have periodic inspection of the facility to check the condition of the dredged material and equipment.



## **PART II: LANDSCAPE ARCHITECTURE METHODOLOGY**

### **A. INTRODUCTION**

The profession of landscape architecture has been and continues to be largely concerned with the design and analysis of inter-relationships between human elements and the environment. The following discussion briefly describes the principles and practices of landscape architecture as they relate to the development of CDMD facilities. A brief overview of the history of the profession is presented in Section B, followed by a discussion in Section C of the technical and design principles applicable to CDMD development. Section D, an Examination of Selected Analogous Facilities, further examines the application of landscape architectural practices to projects and operations similar to CDMD facilities.

### **B. OVERVIEW OF THE HISTORY AND RELEVANCE OF LANDSCAPE ARCHITECTURE**

The pioneer builders of colonial America practiced the principles of landscape architecture by their use of indigenous materials for construction projects of all scales and by their understanding of the need to adapt their man-made structures with the landscape. Landscape architecture as a profession in America originated most notably with the planning, design, and construction of Central Park in New York City. Frederick Law Olmsted, along with his partner Calvert Vaux, designed this large open space for the benefit of the thousands of inhabitants of that crowded city. Their skilled effort met the diverse problems of engineering, horticulture, and design. They reduced the conflict between vehicular traffic and pedestrian movement through grade separation of the traffic flows in the park, and integrated the drainage and water-supply systems within the park design so as not to disrupt the visual and aesthetic unity of the park.

From this beginning, the efforts of landscape architecture

have been advanced to meet present day challenges. For instance, the planning of highways, characteristically rectilinear in design and unyielding in layout, have slowly evolved to the scenic highways of today. Overpasses now take on sweeping curvilinear forms and the horizontal alignments of the roadways are sensitive to the landscape. Large-scale planting within the rights-of-way has helped to harmonize the road with the land. The design of the Merritt Parkway in Connecticut is one of the pioneering examples of how a vehicular parkway can be well integrated with the environment through which it passes.

The siting and design of utility installations and the renovation of gravel pits, sanitary landfills, and similar previously neglected projects are now a matter of concern to public agencies with regard to environmental and aesthetic considerations. There are good examples, particularly in England, where the challenge of moderating the impact of large power stations upon the landscape has been met. At Snowdownia National Park, for instance, the landscape design scheme was to accept the main bulk of a large power station but to take advantage of the natural ground configuration by emphasizing it with new grading, and to hide the ancillary equipment from public view (Lovejoy, 1973).

The problems concerning the design and maintenance of CDMO facilities are already being studied under the direction of the U.S. Army Corps of Engineers. The principles and techniques of landscape architecture can make a positive contribution to this effort.

### **C. EXAMINATION OF LANDSCAPE ARCHITECTURAL CONSIDERATIONS**


The landscape is a continuum of natural forms and structures, and any project that may modify the landscape should carefully consider the potential impact of introducing new man-made elements. A new facility should complement the environment it will occupy, visually as well as functionally.

The visual quality of a facility is its most discernible characteristic, particularly if the facility is to be sited on open land or water. Projects may well comply with the requirements of Federal and State laws and regulations with regard to biophysical factors and yet still be visually intrusive within the landscape. Project planning and design must confront this concern.


1. General Design Concepts

a. Land configuration

An important part of the design process is a consideration of land configuration. This includes concern for those factors that have shaped the land as it exists: the requirements of the intended use on the landform, alterations of the land configuration for adaptation to the intended use, and the creative balance that may be attained between the functional layout and aesthetic appearance. The form of a facility must not only be functional and visually interesting by itself, but also must be integrated into the formal context of the scale and character of the surrounding environment.



*Each landform dictates different planning requirements*



*Earth-forming used to screen views*

b. Three-dimensional earth forming

Earth forming has long been employed to screen views partially or fully or to muffle sounds. Earth can be built up to form enclosures or to create vantage points or can be


excavated to form lakes and other desired depressions.

Munding can direct the flow of water, the direction and velocity of the wind, and the routes of people. If judiciously placed, mounds, berms, and earth forms, combined with plantings can screen undesired objects and reduce the apparent height and therefore the intrusiveness of some elements on the landscape.


Grading is required as the final step of land preparation prior to planting. Its basic function is to restore land that has been modified during construction so that it conforms with the original landscape; the new earth forms must be blended in with the landform of the adjacent area. Grading is also necessary to provide positive drainage of surface water.

#### c. Siting of structures

Possibly the most important concern of landscape architecture is the placement of buildings or other structures on the land (or water) such that an aesthetic as well as ecological balance is maintained with the natural characteristics of the environment. Structures should be related to landforms, vegetation, and the other elements for practical and aesthetic reasons. A building should be located so that there is natural drainage away from the building, and so that the landform can screen the view of the more utilitarian parts of the building and accentuate desirable views. Similarly, buildings can be carefully located next to trees that can aide in climate control or screen the impact of dominant structures. Buildings and natural elements of the landscape should be treated together so that both are harmoniously related.




*Buildings not related to natural landforms*



*Buildings sympathetically related to natural landforms*


#### **d. Planting design**

Planting is used for numerous reasons to solve a wide range of environmental problems: architectural, engineering, climatic, aesthetic, and conservation (Robinette, 1972). To do this effectively, the designer must have a working knowledge of plant characteristics, their individual functional roles, and the degree of effectiveness in performing these functions:



##### **1) Architectural uses.**


Whether singular or in groups, plants can be used to articulate space, screen views, and define elements in the landscape.



##### **2) Engineering uses.**

Engineers address problems of glare, traffic and sound control, the conditioning of air, filtration, and soil erosion. Through careful choice and siting,


plants can control glare, direct traffic, absorb sound, filter the air of gases and particles, and aid in filtering suspended sediments from water. Through transpiration, cover, and spreading root system plants can aid soil stabilization and denaturing.



##### **3) Climate control.**

The use of plants in controlling climate is well known. They aid in filtering the hot sun, thus lowering intolerable


temperatures. Federal projects have sponsored the planting of tree belts to control and direct winds.



#### 4) Aesthetic uses.

Plants as unique elements in themselves serve as focal points in a landscape composition because of the structure of branching sys-

tens, the texture of foliage, or the fragrance of flowers. Plants can unite unrelated objects in a landscape and screen those elements displeasing to view.




5) Conservation. Plants serve an important role in conservation, attracting various forms of wildlife, providing the necessary cover and organic elements

necessary to retain and build soil, and above all providing food for life.

#### e. Approaches, circulation, and observer viewpoints

In landscape architectural practice, careful consideration is given to the perception of form outline, texture, and placement along the sequences of space in any form of circulation. Enclosures are analyzed and valued and vistas are developed to their full potential to add purposeful interest and excitement. Circulation should be analyzed from the points of approach, sequence, and departure, each of which will have distinct visual implications.



## **2. Technical Considerations**

### **a. Soil**

**The correct assessment and analysis of soils is an essential requirement of landscape architecture. Soil is the medium which nourishes and sustains vegetation. It supports the root systems of plants, which in turn support the visible components of the plants. It absorbs and holds the water and mineral nutrients that are necessary to the plant. Its pH value, the degree of acidity or alkalinity, helps determine the type of vegetative growth. Its salt content, which at times can be altered, has a direct bearing on the quality and type of plant growth. Salts, including alkaline compounds, tend to concentrate in the root zone or at the soil surface.**

**Soil is categorized according to its mechanical and organic composition. For instance, clay is a fine grained, cohesive material which can be impervious to water movement and is unusable under certain stresses and forces. The characteristics and potentials of the different kinds of soil must be known before earth forms can be designed, trees can be planted, structures can be built, and knowledge of plant succession can be obtained.**

### **b. Water**

**The interaction of water with the land has a great bearing on land configuration and vegetation. Surface water from precipitation is one factor that forms the land by eroding soil away from hills and depositing it in valleys and other low points. Surface water that is not adequately drained from a site can adversely affect vegetative growth and development. Surface ponding stops air penetration in the soil and prevents aerobic activity. Evaporation of surface water takes heat from the soil; transpiration can decrease ambient temperatures.**

Ground water is also critical to the growth of vegetation. The water table (the upper surface of the saturated zone of free, unconfined ground water) can limit beneficial root growth if too high. The water table is dynamic and can change dramatically in response to inundations or droughts.

**C. Natural constraints**

The environment is subjected to a variety of natural constraints that constantly maintain or threaten the delicate balance between vegetation and the surrounding ecosystem. These factors include winds, particularly storm winds such as hurricanes and tornadoes; salt spray and salt in the ground water; floods and the erosive effects of heavy water runoff; and freezing and thawing cycles and other effects of extreme temperatures. These factors are normally considered in the design process such that the final development plans will reflect an understanding of the nature and extent of the constraining factors.

**D. OVERVIEW OF SELECTED ANALOGOUS FACILITIES**


Certain civil engineering facilities and projects are analogous to CMD facilities in terms of both the problems that arise during construction and operation and the solutions to these problems that have been developed through past research in related fields. A review of the following facilities has yielded solution principles which are applicable to landscape development of CMD's: highways, strip mines, sanitary landfills, Dutch polders, and artificial islands. The conclusion of this section summarizes the significant principles; specific applications of these principles to CMD development are found in the recommendations of this report (Part III).



## 1. Highways

Extensive research in the field of highway development has been conducted in the past to solve the problems of structural and surface instability of steep highway fill areas and of plant establishment and maintenance on highway embankments.

Particularly on fill slopes, slumping of newly-placed fill and slippage over time may cause problems. Although avoidance of these problems is basically an engineering concern, certain common principles and guidelines should be recognized. Flattening the slope of the fill material will obviously reduce some of the physical pressures that cause structural instability; in general, granular soil can support steeper slopes than can clay materials, which must be sloped at 3H on 1V or less (Department of Public Works, Canada, 1971). If it is unfeasible to thus widen the fill area, terracing or benching the slope can help to prevent slippage.



*Surface  
drainage*

*Impervious  
material*

*Terracing*

*Mulching and  
planting*

A steep slope is inherently subject to surface erosion, particularly that resulting from precipitation and runoff. Erodibility of a slope is dependent on the amount of precipitation, runoff patterns, soil characteristics, and slope length and angle, and can be calculated using standard formulae developed in soil engineering research. If the slope cannot be designed at a sufficiently shallow grade, a number of other measures may be taken to prevent erosion. Drainage systems that channel water away from the slope face can curtail sheet and gully erosion, as well as possibly prevent seepage behind the slope and resultant slippage.

Another technique involves covering the surface with an impervious material such as brick, stone, concrete, or bituminous pavement.

Vegetation prevents slope erosion as well as providing a visual amenity. Considerable research has been conducted on plant species and planting methods that are applicable in terms of the high erosion potential, difficulty of access, large surface areas, and limited maintenance programs on highway embankments (Zak et al., 1972).

Grasses and herbaceous legumes such as crown vetch, which are good soil stabilizers, can be planted by hydroseeding. In this process, a slurry of water, seed, and fertilizer are sprayed onto the slope; a filler of finely ground cellulose fibers or a mineral filler such as gypsum perlite, or vermiculite may be added to serve as a mulch. On slightly steeper slopes, a filler of oil, bitumin, or latex emulsion either alone or sprayed simultaneously with straw mulch will adhere to the soil to a greater degree. However, on slopes greater than  $2H$  on IV, a netting of kraft paper yarns or jute stapled to the slope may be necessary in order to prevent the seed and filler from washing away (Hudson, 1971).

Woody plants can be planted either by the broadcast or the spot-seeding methods, as well as by traditional planting techniques. In the broadcast method, seeds are sprayed on first, then hydro mulched with two inches of wood chip mulch; this is acceptable when the slope is  $3H$  on IV. In the spot seeding method, seeds are planted in spots cut through the mulch; this is recommended when the slope is greater than  $3H$  on IV.

The selection of plant species should be made only after site conditions have been evaluated, including soil texture and structure, drainage patterns, and slope orientation and steepness. Obviously, the species must be adaptable to the site conditions, as well as fulfilling any functional requirements in terms of growth rate, root structures, visual attractiveness, or screening ability.

Maintenance mowing programs may determine permissible slopes: a slope of  $3\frac{1}{2}H$  on IV is normally considered a maximum for safe and effective use of mowing equipment. Standards have also been developed for slope combinations and curve radii which enable

the economical operation of typical mowing equipment (Iurka and Tetelman, 1960).

## **2. Strip Mining and Sanitary Landfill**

The aspects of strip mining and sanitary landfill operations which are analogous to CMD facilities include the slopes and landforms of deposited or regraded spoil, the reclamation of disturbed, barren, or nuisance-generating spoil, and the capabilities of the spoil to support vegetation.

The reclamation of strip mined lands typically involves site regrading, using the stockpiled spoil or overburden which was removed from subsurface mineral deposits. Regrading plans should reflect an analysis of the effects of the plan on drainage patterns, particularly those that carry runoff from derelict mines onto adjacent lands, the water table, and the engineering requirements of slope and angle. A slope of 40H on IV or 50H on IV, depending on the material, is best for drainage of the regraded site; where slope embankments are necessary, a slope of 5H on IV or 6H on IV is appropriate (Downing, 1971). A basic decision to be made is whether the site should be graded in natural or geometric forms. This decision has aesthetic as well as cost implications: because the construction of undulating landforms requires the use of only one earth scraper, it is usually a less expensive operation (Downing, 1971).

Earth covers high in clay or with other impermeable materials are considered advisable over derelict strip mines in order to minimize leaching of acids and other toxic materials and to enable vegetation establishment (Hutnick and Davis, 1973). They are also necessary for sanitary landfills in order "to prevent insect and rodent infestation, blowing paper, fires,...and the release of gas and odor " (Sorg and Hickman, 1968), as well as to enable vegetative growth. Requirements for earth fill cover over strip mined sites have been established in five of the Appalachian states; Maryland requires a three-foot cover. For sanitary landfills, Massachusetts requires two feet of cover (Commonwealth of Massachusetts, 1971).

In cases where trees are to be planted, three feet of topsoil cover has been recommended (Sorg and Hickman, 1968; Commonwealth of Massachusetts, 1971).

In many cases where laws do not require it and when economic considerations preclude it, earth fill is not provided. Natural revegetation can and does take place on less than ideal sites. However, the success of colonization is dependent upon having a soil structure and texture to which native colonizing species can adapt, as well as an adequate seed source for such species.

The growth of colonizing species and of trees planted in a topsoil cover is moderated by such critical factors as the pH, the composition of the earth, and the amount of water that is retained in the soil. pH values are generally high on newly mined soil, but are reduced through time as the plant cover develops through the pioneer stage. A test site in Illinois indicated that soil condition with respect to nutrient levels was markedly improved under a growth of black locust trees (Ashby, 1964).


Experiments with various planting designs and techniques have been conducted on derelict land sites in England. A number of species, including perennial rye grasses, red fescues, and other grasses, as well as willows, dogwoods, mountain ash, hawthorns, and alders have been found to perform successfully for different uses on the project sites (Vyle, 1971).

### 3. Dutch Polders


A polder is constructed by building an enclosed dike around land submerged in shallow water, pumping the water out, and keeping the land permanently exposed to the air. After desalination, the land can be occupied for uses such as agriculture, parks and recreation, and residential communities.

The construction of these facilities requires the utmost concern for prevention of dike failure. However, the creative


modification and enhancement of the dikes as undertaken by the Dutch is of more interest to the development of landscape concepts for CDM facilities. The Dutch have tried to adapt the polder dikes to serve a variety of uses, as exemplified in the Eastern Flevoland polder now under construction in central Holland (Van Eesteren et al., 1963). The top of the dike is used for a roadway. The side of the dike facing the water has been modified by adding additional soil; this has created additional usable land and a more natural shoreline. The distance between the roadway and the water, from twenty-five to five hundred feet in width, is used successively as a wooded parkway, a sandy beach, a shallow-water marsh for a wildlife sanctuary, and a landscaped buffer strip. The flat slope of the dike at the water's edge facilitates the cultivation of marsh species which serve to control shoreline erosion and to visually naturalize the dike.




*Wooded parkway*



*wildlife sanctuary*



*Sandy beach*



*Landscaped buffer*

#### 4. Artificial Islands

The creation of artificial islands has been recommended and used in several cases where space is no longer conveniently

available on land. These islands can accommodate what McAleer (1974) describes as "development and nuisance uses", uses which are removed to an isolated location such as an island or artificial platform because of their potential for environmental harm or their objectionable nature. They are also suited to "conservation and attractive uses", such as wildlife sanctuaries and public or private recreation, which are less intense and can take advantage of the relative isolation.

An artificial island may be constructed in a number of forms and by several techniques. The most conventional is a diked and filled area using natural earth and stone materials in shallow water, similar to several CDM facilities that have been constructed by the Corps of Engineers. Islands can also be formed by caisson or cellular type dikes with earth fill, pile-supported platforms, and floating platforms.

Together with the potential benefits of such structures, a number of problems may be encountered. These include possible pollution from fill leachates and potential interference with the littoral and natural beach-replenishment functions of current. Care should be taken to select sites in shoals with little potential for biotic life.

In the design of artificial islands, several principles may be employed for ensuring high compatibility with adjacent or nearby shore areas. Wherever technical, operational, and economic constraints permit, artificial islands should be given natural forms in terms of both perimeter and elevational contours. Where recreational use is planned, the desirability of such design planning should be evident. Almost all artificial islands formed for park and recreational use are naturalistic in character. In addition, indented perimeters may provide anchorages for recreational boating. Perimeter dikes or island edges which are broader than technical requirements dictate may also be managed for multiple-use recreational opportunities (Roy Mann Associates, 1973). Where utilitarian facilities are involved, the rationale may be less apparent, but no

less desirable if visual incompatibility with adjacent scenic, recreational, or residential areas may be interpreted as adversely affecting the environment. Thus, offshore facilities are at times provided with naturalized perimeters. Superstructures are also provided appropriate treatment; for example, the 180-foot rigs at the THUMS oil drilling development at Long Beach, California, were baffled to resemble residential towers.

When wave erosion is a particular problem on an artificial island and when sand is available in sufficient quantities, it is often desirable to create a long, shallow-sloped beach. By building a retaining wall beneath the surface of the water, using rocks, sheet piling, or caissons, the sand on the beach can be retained at a shallow slope and may better withstand loss to storm wave action and littoral drift.

E. SUMMARY OF APPLICABLE PRINCIPLES

1. Creative Uses of Facilities which are Similar to CDMO Facilities

From the preceeding review of landscape architectural principles and the examination of selected analogous facilities, it is evident that an attempt is being made to provide creative new uses for projects that were originally intended to serve more utilitarian purposes. The most obvious examples are artificial islands, with their wide range of use possibilities. Also, through recent modification and enhancement measures, greater recreational and other use is being made of reclaimed areas. Creative reuse of surface-mined sites can be accomplished by developing recreation grounds, wildlife sanctuaries, and hunting and fishing sites. Planting on highway embankments can be used not only to ameliorate the view from the road, but also to screen the view to the highway from surrounding community areas.

## **2. Slope Stabilization**

The stability of the containment structure of a CDM is of prime concern to those involved in its construction, operation, maintenance and long-term use. From the research conducted, it can be concluded that two major principles apply to the design and construction of retainment dikes. The first is that for given foundation conditions, the shallower the slope, the stronger the dike. This principle applies to both surfaces of a slope, that is, a land-side slope that is exposed to the eroding effects of rain and wind and also to a water-side slope that is exposed to the eroding effects of waves in addition to rain and wind. In the first case, if highway embankments are designed to have shallower slopes, less constructional stabilization and maintenance is required and planting is facilitated. In the case of water-facing slopes, it has been demonstrated that artificial islands designed with perched beaches or Dutch polders designed with gently sloping dike edges effectively reduce dike erosion.

The second significant principle of slope stabilization is that surface erosion can be limited by reducing and controlling the force of water runoff. This can be achieved by a variety of techniques, including terracing, covering the surface with inorganic materials such as riprap, covering the surface with mulch, and using plant materials for slope stabilization.

## **3. Earth Forming and Preparation**

Earth forming and soil preparation are important for a number of reasons. They have practical requisites for providing good drainage and erosion control and for providing a suitable condition for vegetation. They also have applicability in the aesthetic enhancement of sites such as CDM facilities.

Regrading is the first step that must be taken to restore a strip-mined area. This is primarily for functional reasons, since the proper drainage of those areas where toxic minerals may be present is critical. Regrading has obvious visual justifications



also, since the scars of high walls and spoil heaps are obvious intrusions in the natural landscape.

Earth forming can be used imaginatively to create more acceptable habitats for wildlife or more useful and human-scaled spaces for people. Grading of man-made projects should be used to blend the newly structured earth with the surrounding land forms.

Soil preparation is obviously an important requirement for the reclamation of derelict land or recycling of waste disposal sites. At the completion of a sanitary landfill operation, a minimum of two feet of topsoil should be placed to sustain a grassy ground cover. Three feet of topsoil is necessary to support tree growth. Similarly, an earth fill is recommended for covering mining tailings; three feet of earth fill is recommended as a minimum

There are various ways of enriching the soil on top of recycled materials. To a certain extent, plant materials themselves enrich the soil and make it more productive to dominant species. Also, fertilizer is generally necessary to prepare the soil for planting or to sustain growth. However, nutrient runoff must be carefully controlled.

#### **4. Planting: Species Selection and Planting Techniques**

Plant material can enhance the image of large land-forming projects and facilitate erosion control. From the various examples discussed, it is possible to draw several conclusions that are pertinent to the landscape development of CMD sites.

A highway or steep-sloped embankment has unique characteristics that determine what species of vegetation should be planted. Because of access difficulties and the need for maintenance, a type of tree or ground cover must be selected for which appropriate planting equipment and manpower is available. For instance, hydroseeding and mechanical or artificial mulching methods may have to be used, and therefore only grasses or trees that can

**be broadcast-seeded can be selected. Other considerations in selecting plant species for sloping sites are to choose plants whose roots have sufficient soil stabilization properties and will reproduce and cover an exposed slope as rapidly as possible.**

**A principle guiding species selection for revegetating problem areas is that the properties of the existing soil or dredged material will dictate what will grow. Only if a suitable topsoil cover is provided or if the existing dredged material is effectively reconditioned can the designer have increased freedom in selecting species for planted or seeded revegetation.**

**Thus, it is evident that many landscape principles and concepts exist that are applicable to the design, construction, and maintenance of CDM facilities. Application of selected principles is further discussed in Part III of this report.**

## **PART III: PLANNING AND LANDSCAPE RECOMMENDATIONS AND ALTERNATIVES FOR CDMD SITE DEVELOPMENT**

### **A. INTRODUCTION**

The illustrated recommendations presented in Section B, "Recommendations and Guidelines," constitute the major design concepts resulting from the study effort on which this handbook is based. Design recommendations regarding earth preparation and planting may be found in Section C, "Implementation."

Although many of the concepts presented in the following sections have been tried, tested, and constructively used in other problem land planning and design applications, most of the concepts are new to the field of dredged material disposal. Because of this, adequate testing of the recommendations of this report should be planned, monitored, and reported on a District-by-District basis in order to determine their practicability and effectiveness in landscape improvement.


Their untried status notwithstanding, the concepts recommended in this report have been carefully reviewed as to adequacy and practicality in terms of the constraints and variables of CDMD facility engineering, operations, and maintenance technology. They are achievable, in the judgment of the authors of this report, and should assist the Districts in the pursuit of defined Corps of Engineers environmental and aesthetic resource policies and directives.

### **B. RECOMMENDATIONS AND GUIDELINES**

#### **1. Natural Forms**

##### **a. Recommendation**

Employ simple naturalized perimeter to enhance visual blending or similarity with islands and shorelines.




## b. Guidelines and specifications

- Use rhythmic curves that are easily noticed by observers at water or shore level (more important than actual design in plan view).
- Avoid unrhythmic, ragged, and straight edges (unless straight edges are intended for a specific reuse application).
- Employ buoys, markers, or other conventional means for ensuring accurate laying out of perimeters by disposal operators.
- Use shape and orientation of island to enhance harmony with nearby land or island forms and to minimize interference with littoral drift, currents, salinity regime, and other factors.


## 2. Proximity to Natural Islands

### a. Recommendation

Where conditions allow, construct disposal facility at sufficient distance from natural island to avoid damaging aesthetic, wildlife, or recreational qualities.



*Improper siting*



*Proper siting*


**b. Guidelines and Specifications**

- Carefully consider all environmental planning factors.
- Plan compatible use for sector of facility closest to island.

**3. Linear Natural Forms**

**a. Recommendation**

Use lee of existing or new breakwater for protected disposal material retention structure.




**b. Guidelines and Specifications**

- Construct breakwater and dike(s) as per standard design specifications but incorporate curving perimeters consistent with resistance to wave forces and related factors.
- Design breakwater lee to serve as protection for outer dike in lieu of riprap or revetments.
- When possible, place sluice at end of island where harbor currents are predominantly away from sensitive estuarine areas. Additional measures such as traps should be employed to control escape of suspended materials into sensitive areas, particularly where breakwaters (and islands) are short in length.

**4. Complex Natural Forms**

**a. Recommendation**

Develop island with complex, naturalistic form for specified reuse purpose.




**b. Guidelines and Specifications**

- Prepare to-scale layout drawing for perimeter construction. Require retention structure contractor to exercise care in following markers.
- Employ appropriate earth contouring, mounding, planting, and seeding to achieve a finished island consistent with the reuse purposes of the project.

**5. Modified Natural Form**

**a. Recommendation**

Use modified natural forms to harmonize existing bulkheads in mixed-use waterfront areas.




**b. Guidelines and Specifications**

- Employ curved edges on side(s) facing public open space, recreational facilities, or residential areas.
- Raise elevation of contained dredged material to create opportunity for future waterfront viewing point.

## **6. Multiple Modified Forms**

### **a. Recommendations**

Plan perimeter configuration and segment area sizes to meet intended reuse plans for multiple activities.




### **b. Guidelines and Specifications**

- Develop reuse master plan upon request of and in conjunction with local sponsor and related jurisdictions.
- Lay out basic perimeters of individual use segments in accordance with needs of each use (see sketch for examples).
- Add final form to perimeters of complex edges after disposal operation is completed within the more simple perimeters.

## **7. Modified Angular Forms**

### **a. Recommendations**

Employ perimeter form carefully designed to complement rectilinear edges of mixed or urban/industrial waterfront without copying its rigidity.



**b. Guidelines and Specifications**

- Design perimeter geometry in advance.
- Where feasible and consistent with local sponsors' plan or agreement, wood bulkheading or finished masonry walls are preferable to either steel sheet-piling or riprap.

**8. Bulkheading Variants**

**a. Recommendation**

Where the retention structure is planned along a bulkhead line, set bulkheads or revetments back slightly at intervals to enhance rhythm



**b. Guidelines and Specifications**


- Employ  $45^{\circ}$  angles or  $60^{\circ}$  angles at corners.
- Plant trees and shrubs in salients.

**9. Beach Variants**

**a. Recommendations**

Where artificial nourishment or natural establishment of beaches is feasible and planned, use special measures to ensure perimeter visual quality.






**b. Guidelines and Specifications**

- Employ cast mattresses or other protection that will not protrude (as would riprap) through the sand overlay.
- Use as shallow a slope as feasible for the outer face of the retention structure, preferably not steeper than 4H on 1V, to optimize vegetative take and minimize rill erosion.
- Seed and/or sprig entire face of retention structure along planned beach area. Plant shrubs and trees on crest (see Section C3, Plant Establishment for further guidance).

**10. Lee Variants**

**a. Recommendation**

Employ indented configuration for lee perimeter to accommodate selected reuse purposes.





**b. Guidelines and Specifications**

- Provide appropriate indentations, disposal material, and plantings for marsh establishment and wildfowl management.
- Provide deep indentation for holding basin, to be reused as boating facility.

## 11. Riversides

### a. Recommendation

**Design riverside or channel-side disposal facilities for best possible landscape compatibility.**




### b. Guidelines and Specifications

- **Establish minimum setback (see 16, Setback). Where a road is required between river and facility, set toe of slope back from road an additional distance.**
- **Vary retention structure perimeter along lines sympathetic with river edge.**
- **Plant trees and shrubs on face and crest of facility, particularly those sides which face the river or public and occupied areas.**
- **Concentrate disposal into minimum surface area feasible (with appropriate mounding design) in order to conserve floodplains to the highest degree possible.**

## 12. Land-Facing Edges

### a. Recommendations

**Design edges that are compatible with existing and potential adjacent landscape and land uses.**







## **b. Guidelines and Specifications**




- Set perimeter dikes sufficiently back from property lines, public roads, other public viewing points, and contrasting land uses.
- Employ foreground berms, mounds, and plantings to screen views of disposal facility.
- Avoid straight dike edges parallel to roads or within exposed view of adjacent contrasting land uses.
- Where foreground areas within property lines are abandoned farm lands or areas with unsightly elements, landscape designs should be provided for their amelioration. Normal or attractive foregrounds should be enhanced or protected. In either case, additional plantings of indigenous species, in suitable numbers and plant groupings, should be provided.

## **13. Perimeter Munding**

### **a. Recommendation**

Mounds should be developed on disposal facility perimeters to enhance their form qualities and to heighten the visibility of selected tree and shrub groupings. Three basic mound patterns are recognized although many others may be employed with equal effect.






One attractive variation is obtained by placing C twice as far from B as B is from A. Height is pleasingly varied by bringing the elevations of the three mounds to 25, 30, and 35 feet respectively.

#### b. Guidelines and Specifications



- Uewatered disposal material should be mounded on top of perimeter dikes. As each incremental dike is constructed, a new mound should be raised in proximity to the earlier mounds. Tree and shrub planting, as well as grass seeding, should be carried out as early as feasible following the completion of each dike and mound stage.
- The toes and crests of the mound slopes should be well rounded. Slopes should be 4H on 1V or shallower where possible to minimize erosion and enhance planting establishment and ease of maintenance. (Other erosion constraints will also apply as indicated in Table 3.)
- Mound dimensions should relate to dike width, but should be permitted to encroach on disposal area where width is sufficient. The resulting salient should be designed to avoid interference with effluent movement.



#### 14. Mbund Silhouette Control

##### a. Recommendation

Interval spacing and heights of mounds, particularly those on perimeter dikes, should be varied to increase visual interest and avoid monotony.




##### b. Guidelines and Specifications

- Mound placement should be neither too sparse nor monotonously close-spaced, but should occur at a frequency that breaks up the rigid elevation view of the facility.
- Spacing and heights should be varied and mounds should be grouped where feasible.
- An effective minimum construction plan should include a mound or mound group near the intersections of major sides of the perimeter structure.

#### 15. Foreground Berms and Mbunds

##### a. Recommendations

Placenment of berms and mounds in the foreground of an on-land disposal facility which is exposed to major public view or to adjacent contrasting land uses will aid in screening and enhancing facility appearance; this may be particularly useful in initial stages of project or where retention structures cannot be widened to support in-structure mounding and planting.




**b. Guidelines and Specifications**

- The mounds or berms should be varied in height, form and distance from the viewing area to avoid the appearance of a monotonous wall or concealing structure.
- Types of vegetation planted should be consistent with the plant species already established on adjacent lands.

**16. Setback**

**a. Recommendation**

Retention structure should be set back sufficiently to permit screening of CMD facility.



**b. Guidelines and Specifications**



- Setback from public roads, public viewing points, and contrasting land uses (residential, most institutional, and others) should be sufficient to permit accommodation of foreground berms and mounds (see preceding recommendation). Screen vegetation and other elements for enhancement.
- Normal setbacks from property lines required for CMD facilities may be adequate; additional setback should be provided where view

and land-use conditions warrant.

## 17. Interior Mounding

### a. Recommendation

Grade dewatered disposal material into mound/hill or varied topography in the facility interior.




### b. Guidelines and Specifications

- Relate interior mounds/hills with final graded retention structure for integrated landscape.
- Use final grading plan to determine desirable locations for borrow areas and increase the setting out of coarser materials in such locations (see Design Details, Section 19, for further guidance).


## 18. Planting Recommendations



Select species that are compatible in visual groupings and pattern them harmoniously with topography.



Select species that are part of the same native plant community. Select species that are easily self-propagating and fast growing.



Use masses of trees and shrubs with adequate spacing, rather than specimen, row, or patchy plantings.



Select species that are well adapted to identified moisture, soil, winds, spray, and other conditions; plant lists are given in Tables 7-9.



Densely plant evergreen trees or shrubs where screening would be especially beneficial.




Plant dike faces and crests to enhance blending of vegetation forms with topography.




Plan plantings and provide sufficient dike crown width to accommodate both plantings and operation roads.






Use plantings for focusing access points and other elements of interest in intended reuse areas.




Use wind-resistant tree and shrub species for windbreaks on cross dikes to reduce wave buildup within disposal areas.



Consider permeable berms of naturally or artificially deposited shell or gravel, where ecological and accretional conditions are favorable, to aid in protection of dike and promotion of marsh and tidal pond growth.







Plant in clusters so that mature crown masses can present strong visual form. Avoid single row plantings, since they reinforce rigid qualities of the dikes.



Evergreen trees should be planted on dike slopes and crown above deciduous trees and shrubs. Masses will appear more opaque. Evergreens will continue masking effect in winter in northern Districts.



## 19. Design Details



Evergreen shrubs, when planted as understory or edge plantings below deciduous trees in northern Districts, can provide strong winter features.

### Seepage ditch and berms

Where seepage occurs or is likely on onshore or inland sites, provide drainage ditch and view-buffering berm on shore and public sides.

### Dikes as terraces




As incremental dikes are constructed, trees and shrubs may be planted on the terraces, as well as on the crest of the uppermost dike.

### Regrading of incremental dikes

Regrading perimeter of completed disposal facility or completed segments. Raise and lower alternating areas by conventional cut-and-fill techniques.

### Rehandling basin

Incorporate rehandling basin within overall facility perimeter to decrease handling equipment exposure and to improve reuse potential of basin as future marina.



### Dike edge



Use quarried or field stone in wide size range, including large boulders and slabs, and arrange them in a naturalized and varied, rather than regimented, fashion.

### Coarse material

Where dredged material contains too high a proportion of fines (clays, silts) to ensure successful rooting of planned plantings, use of a bleeder pipe may be employed to promote settling out of coarse materials in a spur-diked containment, or in proximity to intended plantings (to minimize later hauling).

### Thickened slurry

Increase slurry percentage, as feasible, to increase deposition of material around pipe outfall. Pipe dike can be extended to adjacent locus for continued filling. Loci should correspond to point where grading and mounding are to be extensive. Grading equipment and bulldozers will be used to accentuate forms built upon these initially shallow rounds.



### **Phasing**

Plan the phasing of disposal operations to permit early reuse and landscape enhancement of the facility. Use spur dikes and cross dikes to complete segments.

### **Cross Dikes**

In planning, consider future use potential as trail alignments in park and recreation facilities.

## **C. IMPLEMENTATION**

### **1. Plant Selection Criteria**

#### **a. Introduction**

The selection of suitable plant materials will be a key element in any CMD facility landscape development program. Selection of appropriate species will be largely dependent on the location, physical design, and operational characteristics of the facility; the aesthetic and functional objectives to be achieved through plant establishment; and the site's physical constraints to plant growth and development. The potential physical contributions of higher plant species to soil/dredged material stabilization, erosion control, dust control, and modification of detrimental wind flows necessitate careful consideration of suitable species. In addition, the visual quality of CMD facilities can be significantly improved through the introduction of masses or groupings of tree specimens or other plant materials. Desirable views can be directed and undesirable elements screened. The visual appearance of the facilities can be given variety in form and texture

and geometric elements can be softened if the visual characteristics of plant foliage, branching habits, and leaf and bark colors are used attractively.

The sections that follow below, Section 1-b through 1-e, list and define criteria to be considered in the selection of plant materials for CMD facilities. Those that are asterisked are further checklisted against specific plant species in the Plant List, Table 7. (Because of their length, Tables 7-9 were placed at the end of Part III.) The plant lists were compiled from selected sources, which are identified in the Plant Lists section of the Bibliography.

Table 7, Plant List for Trees and Shrubs, lists those trees and shrubs that, from a review of the relevant literature, appear to be capable of establishment on CMD sites and for which information regarding selection criteria was readily available. Additional trees and shrubs are listed in less detail in Table 8. Selected herbaceous plant materials are listed in Table 9. Because identification of suitable herbaceous species has been adequately covered in other literature and because more immediate visual effects on a larger scale can be obtained through the use of higher plant forms, herbaceous species are not discussed in depth in this report.

The plant lists are intended to function as a basic framework for initial selection of potentially appropriate species. Where expertise in plant selection is available locally, proper guidance should be solicited in the final determination of species for specific CMD facilities.

#### **b. Plant community characteristics**

Careful analysis of the community characteristics of neighboring and local environments in the vicinity of the CMD facility will provide guidance in the selection of suitable plants. A community can be defined as a grouping or assemblage of organisms living in a prescribed area or

habitat. The term "association" is sometimes analogously used, but generally refers to a more specific grouping of organisms such as an association of plants.

The attributes of communities will vary according to diversity of species, the relative abundance of species, the nature of the trophic structure or food chain, the types of growth forms (e.g., trees, shrubs, herbaceous species) and the dominance of certain species over others. Of these, dominance is probably the most important in terms of plant selection, because dominant species will largely determine the conditions under which associated species will grow. In typical mixed woodlands, for example, stands of dominant trees will provide the shade necessary for the growth and development of lower forms of vegetation. In addition, rapid-growing species will provide protection for slower growing species that eventually will become dominant. The faster growing species will shield humus from the sun, retarding its decay and enhancing moisture retention. Thus it is important that an understanding of the functional characteristics of plant associations in neighboring environments be understood so that those effects deemed desirable can be replicated in the establishment of plants on the CMD facilities.

The desirability of selecting vegetation endemic to the project locale is also of key importance. Plants native to the area will signify their ability to adapt to the particular physical, hydrological, and climatic characteristics of the area or region (e.g., winter and summer temperatures, frosts, winds, sunlight intensity, fluctuations in available water, and air humidity) as well as indicate qualities such as the species' ability to self propagate locally.

Knowledge of these constraints will also aid in the selection of exotic species to be introduced to the CMD facility. However, exotics may require higher maintenance (e.g., irrigation, nutrient additives, and pruning),

because of their variant horticultural characteristics.

Care must be taken in the selection process, however, to analyze the value and potential magnitude of self propagation. In some cases, undesirable species may spread beyond control over an entire facility, preventing the establishment of more desirable species. In addition, self propagation cannot be anticipated with any accuracy as to timing within the short term or to spread to remote areas of the facility.

#### **C. Visual parameters**


While all of the plant selection criteria are highly interdependent, certain criteria are listed below as visual parameters because they will be more significant determinants of the visual qualities associated with the establishment of various species. (Asterisk indicates checklist item in Table 7).

1) Planting size and technique\*. Planting size should generally be sufficient to provide early visual effect, yet small enough to permit ease of establishment and maintenance within the economic constraints of the project. Planting trees of a large size will provide an immediate visual effect in limited quantities and at greater expense; planting trees of smaller size will provide less immediate visual effects in larger quantities at relatively lower expense. Priorities should be established early within the design phase so that the planting may be coordinated with the immediate and future needs of the site. The sizes of species to be planted will also be dependent on the availability of stock from local nurseries and other sources. Regional and seasonal variations may limit the selection process and should thus be considered early in the design phase.

2) **Growth rate\***. Plants will respond to various growing conditions by exhibiting different rates of growth. The genetically determined characteristic growth rate of a particular species will be modified by soil conditions, climatic factors, and other parameters. Fast-growing plants include many soft-wooded and short-lived species; most hardwood species are relatively slow growing and long-lived. Relative growth rates are indicated on the plant lists by three indices: F (Fast), M (Medium), and S (Slow).

3) **Height\***. Height, as indicated in the plant lists, refers to the average full height a plant species will attain under optimal growing conditions. Variations in climate, water and nutrient availability, and other factors will modify characteristic heights. Height has obvious implications in the landscape development of CDMD facilities, as the heights of plant materials will affect the silhouette of CDMD facilities and width and extent of views. Heights are given in feet in the plant lists.

4) **Silhouette\***. The highly geometric forms usually associated with the visual images of CDMD facilities can be softened or accentuated in silhouette by the selected addition of plant



materials. Trees and shrub clusters, either singly or in masses, can create strong visual images. In addition, silhouettes will change in character from season to season: foliage will reinforce the effect of mass plantings, while the loss of foliage in the winter will delineate branching habits or patterns and will expose or amplify views of evergreens. Silhouettes will also



be strengthened by dense understory or continuous vegetation. Representative silhouettes for selected species are illustrated in the plant lists.

5) Foliage/trunk characteristics\*. The visual images of tree trunks and foliage will vary with the distance from which the species are viewed and the individual characteristics of the species. Tree groupings that result in continuous visual images of masses when viewed from a distance, will be seen as a series of varied foliage textures and branching patterns when viewed from nearby. Likewise, trunk characteristics will vary in texture and color among species.

On the plant lists, the abbreviations used to describe foliage and trunk ("F/T") characteristics are: "E" - evergreen (foliage throughout the year) and "D" - deciduous (leaves lost in winter). Tonal color qualities are also noted, e.g. "light green", "silvery", and "a/c" (autumn color).

#### d. Physical parameters

1) Zone of hardiness\*. The hardiness zones are defined on the basis of average annual minimum temperatures and should be used as general guides in the plant selection process. Variant micro-climates within a given area may permit the growth of vegetation otherwise indicated as excluded (Wyman, 1951).

Figure 2, Hardiness Zones of the United States and Canada, is placed immediately before Table 7 for its use in conjunction with the plant lists.

2) Tolerance to salt spray\*. Few plants identified in the plant lists are capable of growing in close proximity to salt or brackish water. However, many are capable of growing within a zone affected by minor amounts of wind-borne salt spray and are indicated accordingly.

**3) Tolerance to disease and insects.** The selection process, aided by an empirical knowledge on a region-by-region basis, should consider the diseases and insects particular to the area and the ways, if necessary, of controlling or eliminating them. Plants with high resistance to disease infection and insect infestation should be selected whenever possible.

**4) Optimum soil condition\*.** Different species will develop and grow optimally in different planting mediums. These are indicated for each species on the plant list by the following abbreviations: L (loam), Sn (sand), G (gravel), Sl (silt), and Pt (peat). Although these are soil rather than dredged material types, plants for CMD sites should be selected that can survive well with only minimal, if any, medium treatment.

**5) Optimum root zone moisture\*.** Plants selected for CMD sites must be adaptable to the moisture content range of the planting medium. Optimum root zone moisture is indicated on the plant lists by M (moist), I (intermediate), and D (dry).

**6) Drought tolerance\*.** Drought tolerance is another expression of the plant's root zone moisture requirements. Where indicated, plants tolerant of prolonged periods of drought should be used in areas where watering is difficult and expensive. Drought tolerance is indicated on the plant lists by the abbreviation "Dt" .

**7) Tolerance to changes in the water table.** Over the years, the water table will change as a result of changes in the land formation and the eventual drying of the dredged material. Plants tolerant to such changes should be used.

In addition, short-lived plants or mixtures of plant types can be used to provide the diversity needed for the changes expected over time.

8) **Root system** Plants with tap roots or deep root systems should be used where earth mounding or diking of considerable height above freshwater table is planned.

e. **Vegetation as a food source for wildfowl**



The establishment of vegetation on CDMD sites will provide a direct food source (e.g. Zizania aquatica, wild rice) for many species of wildfowl and other forms of wildlife. Indirectly, plant species will provide habitats for insect life which in turn will be preyed upon by wildfowl and terrestrial animals. Protective cover for wildfowl can also be supplied by introducing plant species such as Rubus spp. (bramble). If the attraction of wildfowl to a CDMD site is a desired objective, care must be taken in the selection of plant materials to avoid establishing plant species that will prevent the establishment of those species of higher food value to wildfowl.

f. **Shelter belts**

Careful location of spur and cross dikes and the planting of shelter belts can help to control the detrimental effects of wind and minimize turbidity in the dredged material. A careful investigation of prevailing winds, particularly during seasons when disposal operations are active, will dictate the location of shelter belts.

As shown in Table 10 and Figure 3, the reduction of windspeeds on the leeward sides of shelter belts can be quite significant. For example, for a 30-foot shelter belt of medium density, a wind speed of 100 mph at 100 yards to the windward side of a shelter belt perpendicular to the wind will be reduced to 36 mph at a distance of 50 yards to the leeward side. It should be noted that a parallel series of windbreaks do not proportionately reduce wind speed.

A mixture of deciduous and evergreen trees will provide the

**Figure: 3****Windbreak Effect****a: Moderately penetrable windbreak****b: Dense windbreak**

Effects of windbreaks on the flow of wind.  
 Figures circled denote approximate wind  
 speeds in the various sections. Horizontal  
 distances (in yards) refer to windbreaks  
 30 ft. tall (after Kuhlewind, et al., 1955).

**Table: 10****Wind Speed Reduction**

Wind speeds near 30-ft high shelter belts of different density.  
 (After Caborn, 1965).

**WIND SPEED AS A PERCENTAGE OF THE UNOBSTRUCTED WIND SPEED**

Density of Belt	At Distances to Windward of Belt of (yards)			Within the Belt	At Distances to Leeward of the Belt of (yards)							
	100	50	0		0	20	50	100	150	200	250	300
Very open	100	98	94	96	102	80	72	69	74	86	97	100
Open	100	96	70	75	60	40	48	75	87	95	99	100
Medium	100	96	65	62	55	37	36	60	77	89	95	100
Dense	100	96	55	--	40	27	42	70	86	94	97	100
Very Dense	100	95	55	--	15	27	58	82	91	96	99	100

most effective wind shelter over the longest distance to the leeward of the shelter belt since a continuous cover of moderate density can be achieved from the base to the tip of the windbreak. Plants chosen of various heights and foliage characteristics will provide such a composition over their life span.

Tree species that are particularly suited to use in shelter belts include: Pinus, Thuja, Chamaecyparis, Fraxinus, Alnus, Betula, Salix, and Populus (Caborn, 1965). However, care should be exercised in selecting species adaptable to the physical conditions of the site as well. In addition, some species will be more wind tolerant and thus more suitable to the windward sides of shelter belts than other species.

## 2. Earth Preparation

### a. Introduction

A planting medium (soil or dredged material) will normally require pre-planting preparation to: 1) promote aeration, essential to root viability; 2) incorporate nutrients contained in leguminous plants and chemical and organic fertilizers into the subsurface; 3) improve the texture of the medium to facilitate root extension, which in turn will improve nutrient and water uptake capability; 4) allow the soil to absorb precipitation and runoff as well as to drain adequately to a subsurface water table; and 5) facilitate the actual implanting of plants, seeds, or other propagative materials.

It should be understood that soil and dewatered dredged material can be physically improved only to a relatively small degree, because of their fixed inherent characteristics deriving from parent geology, particle size, climatic and hydrologic influences, organic content, and general fertility. Rather than undertake extensive ameliorative methods, therefore, plants tolerant to the surveyed conditions should be selected. However, within

the limits of its capabilities, a dredged material can respond to various measures identified collectively as "earth preparation." These measures, discussed below, require effort and cost and are thus to be considered specific only to the actual areas planned for planting within the overall disposal facility.

b. Key considerations

1) Dredged material types. The generalized dredged material types identified in Table 6 (e.g., mud, silt, sand, peat, mixed types, etc.) pose varying constraints to landscape development that are important in the earth-forming phase of design as well as in terms of visual concerns and pre-planting preparation. Clay, silt, and organic materials, for example, exhibit the visual effects of erosion more readily than sands or gravels. Clay may retain salts at levels prohibitive to vegetative growth, will shrink and crack over periods of drought, and may prevent the proper drainage necessary for many types of vegetation. In gravel or sand, however, most salts, including valuable nutrients, may be leached out, and a planting medium of poor fertility may result. Gravel and sand may also retain too little moisture for many plant species. Drainage amelioration techniques are discussed below.

2) Cultivation. Modes of cultivation applicable to dredged material preparation include tilling or ploughing, disc harrowing, and rototilling. Equipment in each mode is available in both tractor-mounted and tractor-drawn models.


The purpose of ploughing dewatered dredged material is threefold: 1) to break up the material to improve texture and drainage; 2) to rid the surface of any vegetation that could prove competitive to the introduced planting; and 3) to incorporate the nutrients of the

destroyed plant material into the subsurface.

Deep ploughing will be necessary on material with high clay content and where impervious layers (clay pans or hardpans) have formed at shallow depths. Such layers may result from intermittent disposal and drying out of high-clay dredgings. Subsoil plows that can reach depths of 2-3 feet are recommended on high-clay material. Other material types may be plowed no deeper than 14-15 inches. Deep ploughs normally work one furrow at a time, being available as single-shared or double-shared ploughs.

Smaller ploughs, available singly or in gangs up to 6 in number, should be used to break up the large clods turned over by subsoil plowing or used directly on the more easily worked, friable materials.

Discing is the next step in the cultivation process. The purpose of discing is to further break up the ploughed ground in preparation for seeding. On tougher materials such as clay, an intermediate step may be necessary in which a spring-toothed harrow is used. Discing may be necessary in two passes (crosswise) before a suitably granular seedbed is achieved. Disc harrows range in size from 3 to 25 feet in width and have the capability of penetrating up to 10 inches in depth, with an average depth of 7 to 8 inches. On sandy soils a discing depth



of only six inches may be necessary. Rototillers may also be used instead of disc harrows. Rototillers are capable of tilling widths of 2 to 3 feet and to depths of 6 inches.

**3) Drainage amelioration.** The dewatered material, in order to be productive to plant growth, should contain a balance of coarse and fine-grained particles to allow both drainage and retention of moisture and nutrients through adsorption, gravity flow, and capillary action as well as to provide the voids necessary for the exchange of gases essential to the habitat of soil organisms and to root activity. Movement of material when wet and its compaction by heavy machinery during CMD operations can damage soil structure. Prior to planting and material preparation, therefore, an inspection of the site should be made to determine the extent of compaction and the need for ameliorative tilling.

Drainage may be improved by selectively depositing higher proportions of coarser materials within or through the upper horizons of the filled area. In sand, gravel, and other droughty materials, clay and silt may be added to improve the adsorptive capacity needed for moisture retention.

Soil or material may also be mounded up above the level of poor drainage to create micro-areas or pockets of free-draining land. Large massings of vegetation not tolerant to wet soils may be effectively accommodated in this manner.

Where dredged material is poor in structure and the addition of nutrients will not adversely affect water quality in the external environment, organic matter such as manures, woodchips, and straw may also be added. Compensation for soil nitrogen depletion resulting from bacterial decomposition of straw and wood chips may be required if planting is planned in the growing season following the straw or chip addition. The application of a nitrogen supplement at a rate of 50 pounds of the selected fertilizer per ton of straw or woodchips per acre of land may be effective in maintaining a desirable nitrogen level. Another supplement, sewage sludge, barring heavy toxins and pollutants, may be applied at a rate of 10-20



tons per acre. If odor should prove to be a problem the sludge could be disced in to a depth of 6 to 7 inches. Ploughing in of lime into high-clay materials can promote the binding and aggregation of particles and result in improved pore space and rooting conditions.

4) Plant nutrients. A knowledge of the availability of nutrients within the dredged material, based on the testing of representative material samples, is a necessary prerequisite to the selection of plants tolerant of low or high nutrient or salt levels, the application of selected nutrients to dredged material of low nutrient levels, and the proper timing of planting, which should be carried out on dredged materials with high levels of nutrients or salts only after adequate leaching has taken place. Samples of the dredged material should be collected from all representative areas where planting is planned in the CDMD facility.

Nitrogen (N) is essential for chlorophyll and protein development and thus for the healthy development of all plant parts, but particularly the stems and foliage. However, overly lush top growth with poor root systems may be promoted if excessive amounts of chemical nitrogen are applied; the resulting growth condition causes high vulnerability to drought and frost, either or both of which occur frequently at CDMD sites. In order to avoid this, little or no nitrogen should be applied in the first several years of plant growth, other than during the earth preparation process when organic fertilizers or time-release chemical fertilizers may be applied. The slow release of nutrients in the latter should prevent the rank growth effect of excessive nitrogen availability.

Phosphorus (P) is an important factor in the development of root systems as well as the leafy parts of plants. Since phosphorus becomes fixed in the soil, it is essential in the discing process to mix this nutrient deep into the

dredged material. This will promote the deep root system necessary for obtaining moisture in the deeper soil horizons and for drought tolerance.

Potassium (K) contributes to the general strength of the plant, disease resistance, deep rooting, and seed production. Potassium is also used in countering excessive nitrogen uptake, thus controlling or minimizing succulent and weak growth (Dept. of Public Works, Canada, 1971).

Again, it must be stressed that runoff of the nutrients into surrounding waters should be carefully controlled.

5) pH Value. pH value, or hydrogen potential, is a measure of alkalinity or acidity. The vast majority of plants are suitable for soils of neutral pH. However, certain higher plants have adapted themselves to slightly acid or alkaline soils. Such plants should be noted for CMD facility landscape development since facility conditions of acidity or alkalinity may necessitate the selection of such species (Tandy, 1970).

The pH level has been modified in alkaline soils by the addition of such compounds as aluminum sulfate (alum). Ground lime has been used in acid soils to pull the pH level towards neutrality. It may be assumed that under certain conditions, such modifying additives may also be effective in improving the pH of limited areas within a disposal facility, if planting is planned.

#### c. Special measures

Topsoil storage and use in planting, although not likely to be planned for coastal CMD sites, should be anticipated for inland sites. Topsoil is the complex layer of undisturbed native soil that overlies the subsoil. It normally contains a good balance of nutrients, soil particle sizes, and organic matter necessary for optimum plant growth. Any topsoil located on the site of a proposed CMD facility should be used

to its fullest in the landscape development program All site topsoil, prior to retention structure construction, should be stripped (avoiding mixture with the subsoil) and stored adjacent to the facility. It is ideally handled when moderately moist. Storage of the material in high mounds as well as its compaction by heavy machinery should be avoided. If stored over long periods of time, grasses or legumes should be planted for root development to maintain an optimum soil texture and nitrogen level.

Prior to the mixing of the topsoil with the top layer of the dredged material, soil samples should be taken and the proper nutrient addition taken into account.

Protection of existing vegetation from machinery during construction and operation of the CDMO facility should be provided. Adequate measures, such as the use of barriers, and the careful location of access for equipment should be promoted to protect and enhance existing trees and shrubs deemed worthy of saving. Careful control should also be instituted in the replacement of vegetation injured as a result of negligence.

### 3. Plant Establishment

Little research has been conducted to date on the relative effectiveness of different planting and seeding techniques for given tree and shrub species on dredged material. In view of this state of knowledge, care should be exercised in selecting, monitoring, and comparing alternative techniques and measures. In time, experience and the reporting of research and project results should permit more carefully defined recommendations.

#### a. Planting season

Plant establishment should be scheduled during normal, optimum planting seasons rather than at the end of disposal operations,

if such would require off-season planting. Planting or seeding concurrent with disposal or retention structure construction should be encouraged and can be made practicable through normal coordination between operations contractors or personnel and planting contractors or personnel. Optimum planting seasons are as follows:

Deciduous trees and shrubs	early spring
Conifers and evergreen shrubs	spring, autumn
Container and pot-grown plants	early spring, autumn


On light soils and in drier parts of the country, planting is best in the autumn, when droughts are not likely to be followed by hot weather. In such areas, autumn planting favors greater root development relative to the plant's foliage mass and will take greater advantage of ground water in the following spring and summer. Since roots may rot in winter in heavy and wet soils, planting on such soils and in northern areas is best in spring when the soil becomes warmer and favorable root development can take place. Planting should be postponed when the dredged material is wet or waterlogged, when the ground is frozen, and during periods of drought or drying winds. The importance of adequate preparation of ground prior to planting, discussed above, should not be overlooked.

**b. Bare-root plants**

All plants must be protected from moisture loss during shipment from the nursery prior to planting. Upon arrival and until actual planting, roots should be protected, and the entire plants kept in the shade and away from drying winds. Heeling in is one method that reduces the loss of moisture and is particularly useful for protecting bare-rooted plants. The plants are laid in an open trench at an angle to the ground and the roots are covered with moist earth. Moist sawdust, burlap, or tarpaulins may also be used. Care should be exercised in uncovering roots prior to planting.

### C. Balled and burlapped plants

In contrast to bare-root plants, evergreens, large shrubs, and trees can be stored and planted with the earth intact around the roots. The earth is kept in place by burlap tightly bound with twine or rope. Care should be taken not to crack or dry the root ball. The planting procedure is the same as that for pot or container-grown plants, which include seedlings grown in disintegratable containers such as peat pots, large shrubs or small trees grown in metal or plastic cans measuring up to a few feet in diameter, and semi-mature trees grown in wooden boxes measuring at least several feet on a side. When planting plant materials of these types, the holes should be excavated to a depth and width six inches to one foot greater than the diameter of the root ball.




*Small tree planting holes*

These dimensions allow the planting medium to be broken up to permit air and water penetration and to be supplemented with some ameliorant such as sand, peat, or topsoil, if necessary. . Simple hand methods using a shovel and/or hand auger may be employed. Mounted augers within a twelve-foot radius of their tractors may also be used to dig holes up to eighteen inches in diameter. Plants should be set plumb in their planting hole, kept to the same ground level as they were while growing in the nursery. The containers are, of course, removed prior to this step unless they are of a disintegratable nature; balled and burlapped plants require removal of the ropes and a loosening of the burlap. A few inches of mulch

may then be added to the bottom of the planting hole prior to planting. As discussed previously it is highly recommended that a slow-release fertilizer be used.

d. Staking and guying

With large or semi-mature trees six feet or greater in height, artificial supports may be used as temporary measures and should be eliminated when their usefulness has been terminated.



A single vertical stake may be used in some conditions. Double vertical stakes set perpendicular to the prevailing winds with ties to the tree trunk may also be used. Double-staking is by far the better method, especially if the plants are fast growing and soft wooded, because natural conditions that allow the trunk movement necessary for eventual independent support are emulated. A single stake may also be set at a  $45^{\circ}$  angle against the prevailing winds. All vertical stakes should be cut to just below the crotch of the tree to minimize injury to the branch structure (Tandy, 1970).

When staking and guying are used, the means of attachment to the tree should prevent abrasion of the bark. Ties must also be expandable so that the trunk or branches will not be strangled.

e. Seed

Seeding grasses and trees may be accomplished after the initial grading preparation is completed, the dredged material having been tilled and disced to a smooth texture. Seeding may be practical by hand on remote small areas. Hydroseeding may be used to spread seed as far as 200 feet from the source or farther if attachment hoses are employed. Manufacturers

claim such machines are capable of seeding one acre of land in approximately sixteen minutes. Their practical use on large sites is therefore quite evident and should be investigated in dredged material site applications. In addition, because of their ability to broadcast materials to great distances, hydroseeders may possibly be employed from a barge or other watercraft. This may prove advantageous for use with retention structures not capable of allowing vehicular access. Modern techniques now can broadcast a mixture of seeds, fertilizer, and mulch, permitting a one-step application. Because of the added ease offered, this technique should be investigated further. Hydroseeding or mulching material may also be colored to aid the operator in visually following the broadcast seed. In addition, various soil stabilizers may be added to the seed/mulch slurry to improve erosion control until proper plant growth takes over. A testing of these techniques under the adverse conditions of CDM operations should be fully investigated.

Applied mulch aids the seed by retaining needed moisture at the surface. It also controls the erosion to some degree. On steep banks with slopes greater than 3H on 1V, a deeper layer of chips may be required. This would necessitate another seeding technique called spot seeding. Mulch is first spread to a depth of 3-4 inches, uniformity not being critical, prior to planting the seeds under the mulch. Various hand tools may be used that enable the injection of selected amounts of seeds at a time. The area is simply raked clear of mulch, seeded, and then remulched to a depth of approximately one inch. The spacing interval will be dependent on the plant species (Zak et al., 1972).

#### **f. Cuttings**

Roots of plants that naturally spread by root suckers may be cut approximately into three-inch sections and used for planting. Mulching and planting techniques similar to those

discussed for spot seeding are used. Plants suitable for propagation by root cuttings include Robinia fertilis (Bristly Locust) and Comptonia peregrina (Sweet Fern) (Zak et al., 1972). Cutting may also be made from the branches of soft-wooded trees such as Salix spp. (Willow) and Populus spp. (Poplars). Particularly suited for wet areas, these suckers may be placed in the wet dredged material. As with all soft-wooded, water-loving plants, care should be taken not to establish them in areas where roots could cause interference with building structures, filters, or piping.

#### g. Sprigging

Underground sections, rhizomes, of some plants are capable of rooting and may be hand broadcast, plugged, or mechanically planted. Plugging involves planting a cylindrical portion of soil containing the rhizome.

Herbaceous plants are commonly planted by means of sprigging techniques. Zoysia spp. and Cynodon dactylon (Bermuda Grass) are examples of plants capable of being sprigged.

#### h. Maintenance


Watering, after initial application during planting, will probably not be needed for smaller plant forms, especially those which are drought tolerant. Planting done in the spring will require careful attention to spring rains. If the rains are minimal, a second watering may be necessary. Mature vegetation will require a more frequent and scheduled watering program. Water trucks or mobile pumps on freshwater sites should be employed where possible. Mulching is useful since it promotes water retention and controls weed growth. An application and maintained level of three to four inches of mulch around the base of the plant should be adequate. Weed growth may require control if the induced plants are being deprived of needed moisture and nutrients. The presence of grasses may be beneficial in that they can provide shade for



**young plants, preventing sunburn. In any case, weeds and grasses should be cut back in the fall to prevent their rainfall-laden weight from collapsing young plants.**

**Fertilizing plants will probably be necessary in the first several years of establishment. Thinning may also be used to achieve the desired level of stock density.**

**Figure: 2**



mission of hardness zones in Plant Lists indicates exotic species for which hardness zones have not yet been established.

- With permission of The Arnold Arboretum of Harvard University

**Table: 7**

**Plant List: Trees & Shrubs**


Zone of Hardiness:		Refer to Figure 2		Optimum Root Zone Moisture		M		Mist	
Height (Ft):	Growth Rate	Mature plant height in feet							
F:	M	Fast		Drought Tolerance		I:		Intermediate	
M	s	Medium		Salt-Spray Tolerance		D:		Dry	
s		Slow				Dt:		Drought Tolerant	
						St:		Salt-spray Tolerant	
								ant	
AC:	Acidic			Planting Techniques		cu:		Cutting	
Al:	Alluvium					Di:		Division	
Ak:	Alkaline					Rt:		Root Stock	
B:	Brackish					Sd:		Seeds	
Cl/M:	Clay/Marl					Sk:		Suckers	
G:	Gravel								
H:	Humus								
L:	Loam								
Mt:	Mst types								
M	Mid								
Pt:	Peat					a/c:		Autum Colors	
Po:	Poor					D:		Deciduous	
Ps:	Porous					E:		Evergreen	
Ri:	Rich								
Rk:	Rocky								
Sl:	Silt								
Sn:	Sand								

**NOTE:** The reader is cautioned not to consider the plant list as a definite index of species adaptable to CIMD sites, since many of the species have not yet been observed in situ; their adaptability should be considered potential until adequate field experience is obtained. Additional species in time may also be identified and added to the list. Suitable local horticultural and soils expertise should be enlisted by District Engineers prior to actual plant selection.


Sources for Tables 7, 8 and 9 are presented in the Bibliography.

## Plant List: Trees & shrubs


Table 7 (continued)

Botanical Name		Common Name		Foliage/Trunk Characteristics								Silhouette	
				Zone of Hardiness	Height, ft.	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique		
Acacia farnesiana	Sweet Acacia			8	10	F	Sr	M	Dt	St	Sd	D-small leaflets thorny, similar to wrightii	
Acacia latifolia	Wattle			9	10	F	Sr	M	Dt	St	Sd	D	
Acacia longifolia floribunda	Gossamer Acacia		Sydney	10	20			D	Dt			E-fine foliage, spreading	
Acacia wrightii	Catclaw			8	30	F	St	M	Dt	St	Sd	D-leaves bright green and hairy	
Acanthocereus	Cholla			9	30		Sn-M	D			Di		
Acer negundo	Box-elder			2	60	F		D	Dt			D-no autumn color	
Acer platanoides	Norway Maple			3	90	F	L	I				D-good shade tree	
Acer pseudoplatanus	Sycamore Maple			5	90					St		D-no autumn color	
Acer rubrum	Red Maple			3	120	F	Yst	M	Dt		Sd cu	D-dense, autumn color brilliant red	

# Plant List: Trees & shrubs

Botanical Name		Common Name		Table 7 (continued)									
Botanical Name		Common Name		Zone of Hardiness	Height (ft.)	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	Foliage/Trunk Characteristics	Silhouette
Acer saccharum	Sugar Maple	Tatarian Maple	Chamise	3	120	M	L	I			Sd Cu	D-dense, autumn color yellow to red	
				4	30	M		I				D-dense, fine bright green foliage, autumn color yellow/red	
Adenostema fasciculatum				7	10	- F	Sn- G	D	Dt		Sd cu	E-small needle shaped heathlike leaves	
Agave americana		Century Plant		8	6	S	Sn- L	D	Dt		Sk	E-trunkless, stiff spiny succulent leaves	
Aesculus hippocastanum	Horse Chestnut			3	75	F	L	I			Sd	D-weak wood	
Ailanthus altissima	Red Fruited Tree of Heaven			4	60	F	1st	1-D		St	Sd cu	D-coarse texture diecious	

# Plant List: Trees & shrubs

Botanical Name	Common Name	Table 7 (continued)							Foliage/Trunk Characteristics		Silhouette
		Zone of Hardiness	Height, ft.	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique		
Albizia julibrissin	Silk Tree	7	36		Po				Cu	D	
Alnus glutinosa	Black Alder	3	80	F	L	M			Sd cu	D-dark green, leaves stay on tree into fall	
Alnus maritima	Seaside Alder	6	30	F	Sr-L	M		St	Sd cu	D-lustrous green above, yellow stem broad leaves, bark smooth and light grey	
Amelanchier canadensis	Service Berry	3	30	M	L	M	Dt	St	Sd	D-grey bark, red orange autumn color	
Amyris elenifera	Sea Amyris	10	15		Sn	I				E	
Aralia elata	Japanese Angalica	3	45	M	Ri	I	Dt		Sd Rt	E-dark glossy, open, coarse	

## Plant List: Trees & shrubs


Plant List: Trees & shrubs										Table 7 (continued)			
Botanical Name		Common Name		Foliage/Trunk Characteristics						Silhouette			
Zone of Hardness	Height ft	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	Foliage/Trunk Characteristics			Silhouette		
7	75	M	Sn-G	I	Dt		Sd cu	E-dark glossy green					
10	13	S	Sn-G	I	Dt		Sd cu	E-dark green, trunk brown-red					
10	½	S	Sn-G	D	Dt		Sd cu	E-dark green, trunk brown-red					
10	6	S	Sn-G	D	Dt		Sd cu	E-dark green shaggy bark					
2	½	S	Sn-G	D	Dt		Sd cu	E-autumn color bronze					
8	4		Sn	I	Dt	St	Sd	D					
9	30		Sn-L	M		St		E-oblong curled leaves, trunk dark brown-red, scaly					
10	8	F	Sn-L	M		St	Sd cu	E-light green					

## Plant List: Trees & shrubs

Botanical Name		Common Name	Table 7 (continued)							Foliage/Trunk Characteristics	Silhouette
Baccharis	halimifolia	Sea-myrtle	4	Height ft	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	
Baccharis	pyramidalis	Fingerling	10	1/2	F	Sn-L	M		St	Sd cu	D-dark green leathery leaves, autumn color bronze to grey-green
Bambusa		Bamboos	10	100	M	L	1-D			Di	E-light green prostrate
Berberis	thunbergii	Japanese Barberry	5	8	F	Sn-L	M	Dt		Sd cu	D-autumn color scarlet, winter twigs thorny, red fruit
Betula	davurica	Dahurian Birch	4	60		G					D-bark peels off in regular pieces
Betula	papyrifera	Paper Birch	2	90	F	Sn	I			Sd	D-open, autumn color yellow, bark white, peels off in sheets



# Plant List: Trees & shrubs


Plant List: Trees & shrubs										Table 7 (continued)		
Botanical Name		Common Name		Foliage/Trunk Characteristics						Silhouette		
Zone of Hardiness	Height ft	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spr	Planting Technique					
5	30	F	G	M	Dt		Sd	D-open, autumn color yellow, bark white with triangular black markings				
10	2	M	Sn-L	M		St	Sd	D				
8	3		Sn-L	M		St	Sd	D				
6	48		PO				su	D grey bark				
10	75	M	Sl-M	M				E-leathery leave!				
10	25	M	Sn	D			Sd	D				
9	24	M	Sn	I		St	Sd	E				
5	40	M	L	I		St	Sd	E-bark dark grey to black and scaly				

## Plant List: Trees & shrubs

Botanical Name	Common Name	Table 7 (continued)						
		Zone of Hardiness	Height (ft.)	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant
<b>Bunelia reclinata</b>	<b>Buckthorn</b>	9	10	M	Sn	I		St
<b>Bunelia tenax</b>	<b>Tough Bunelia</b>	9	27	M	Sn	M		Sd
<b>Bursera sinaruba</b>	<b>Gunbo-linbo</b>	10	60	M	pt-L	I		cu
<b>Byrsonima lucida</b>	<b>Locust Berry</b>	10	3	M	AK	D		Sd
<b>Callicarpa americana</b>	<b>Beauty Berry</b>	10	6	M	L	I		Sd cu
<b>Capparis jamaicensis</b>	<b>Jamica Capper</b>	9	20		Sn	M		Sd cu
<b>Carya floridana</b>	<b>Florida Hickory</b>	10	75	S	Sn			Sd

Foliage/Trunk Characteristics	Silhouette
E	
E-similar to lauraginoso, spiny, shiny red hairs under leaves and on twigs	
D-bark smooth and red-brown	
E	
D-leaves white beneath	
E-leaves yellow-green above, brown scales below	
D	


# Plant List: Trees & shrubs

Plant List: Trees & shrubs													
Botanical Name		Common Name		Table 7 (continued)									
				Zone of Hardiness	Height (ft.)	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	Foliage/Trunk Characteristics	Silhouette
Carya glabra		Pignut Hickory		4	120	S	Sn-L	D	Dt		Sd	D-dense, autumn color yellow	
Carya ovata		Shagbark Hickory		4	120	S	Sn-L	D	Dt		Sd	D-dense, golden brown, bark flakes off in plates	
Casasia clusifolia		Seven-year Apple		10	10		Sn	M		St		E-numerous branches, leaves clustered	
Cassia aspera		Partridge Pea		9	2		Sn	I	Dt		CU	D-densely branching	
Cassia brachiata		Sensitive Pea		10	6					St	cu		
Castanea pumila		Chinquapin		5	50	M	PO	D	Dt		Sd	D	
Casaurina stricta		Coast Beefwood		10	30		B			St		E	
Ceanothus dentatus		Dwarf Ceanothus		10	3	S	Sn	I	Dt		Sd cu	E-dense	

## Plant List: Trees & shrubs

Plant List: Trees & shrubs										Table 7 (continued)				
Botanical Name		Common Name		Zone of Hardiness	Height ft	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	Foliage/Trunk Characteristics		Silhouette
Celtis australis		European Hackberry		6	75			D	Dt			D round, spreading habit		
Celtis occidentalis		Hackberry		4	70	F	Mst	I			Sd cu	D-dense		
Celtis pallida		Hackberry		7	6	F	Mst	I			Sd cu	D-spiny shrub		
Celtis pumila		Hackberry		5	12	F	Mst	I			Sd cu	D		
Ceratiola ericoides		Rosemary		9	8	M	Sn	D			Sd	E		
Chrysobalanus icaco		Coca-plum		10	25		H-Sn	M			Sd cu	E-leathery leaves		
Citharexylum fruticosum		Fiddlewood		9	30	M		D				E		
Clethra alnifolia		Summersweet		3	10	M	Sl	M			Sd cu	D-autumn color yellow/orange		
Coccoloba aurifolia		Pigeon Plum		10	45	M	Sn	D			cu	E-large leaves		
Coccoloba uvifera		Sea Grape		10	20	M	Sn	D	Dt	St	cu	E-large leaves		

## Plant List: Trees & shrubs


Botanical Name		Common Name		Table 7 (continued)							
Botanical Name	Common Name	Zone of Hardiness	Height ft	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	Foliage/Trunk Characteristics	Silhouette
<b>Coccothrinax agentata</b>	<b>Silver Palm</b>	10	20	M	Sn-L	M		St		E-fan palms	
<b>Cocos nucifera</b>	<b>Coconut Palm</b>	10	80	M	Sn	D	Dt	St	Sd	E-graceful but coarse, long leaves, trunk long and crooked	
<b>Codiaeum orgyanthemis</b>	<b>Croton</b>	10			Mst				Sd cu	E-thick lobed leaves	
<b>Codiaeum linearis</b>	<b>Narrowleaf Croton</b>	10	6		Mst				Sd cu	E-thick lobed leaves	
<b>Codiaeum fergusonii</b>	<b>Croton</b>	10			Mst				Sd cu	E-thick lobed leaves	
<b>Codiaeum punctatus</b>	<b>Silverleaf Croton</b>	10	3		Mst				Sd cu	E-thick lobed leaves	
<b>Codiaeum spp.</b>	<b>Croton</b>	10	6		Sn	I	Dt	St	Sd cu	E-thick lobed leaves	
<b>Colubrina aborescens</b>	<b>Coffee Colubrina</b>	10	25		+-L	M				E-leaves dark green, lustrous	
<b>Conocarpus erecta</b>	<b>Button Mangrove</b>	9	50		Mst	M		St		E-smooth silky foliage	

## Table 7 (continued)

Foliage/Trunk Characteristics	Silhouette
E-rough dark brown bark, undulate leaf margins	
D-dense, lustrous, autumn color scarlet	
D-dense	
D-rough leaves, reddish twigs	
D-dense, coarse leaves	
E-pyramidal habit., sharp needles, reddish bark	

# Plant List: Trees & shrubs

Table 7 (continued)

Botanical Name	Common Name	Zone of Hardiness	Height ft	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	Foliage/Trunk Characteristics	Silhouette
<b>Crataegus</b> crus-galli	<b>Hawthorn</b>	4	36	S	Cl	M	Dt		Sd Cu	D-rounded top, thorny, dense, lustrous, autumn color orange/scarlet	
<b>Cupressus</b> goveniana	<b>Tower Cypress</b>	9	25		Sn- Cl	D	Dt			E-dark green, bark red-brown scaly and ridged	
<b>Cupressus</b> macrocarpa	<b>Monterey Cypress</b>	7	75	F	Sn- Cl	D	Dt	St		E-scalelike, dark blue-green, bark brown-grey and ridged	
<b>Cyrilla</b> racemiflora	<b>Titi</b>	5	30	M	L	M			Sd cu	E-bark lustrous red-brown, leaves shiny and leathery	
<b>Dalbergia</b> brownei	<b>Rosewood</b>		9		Sn- L		Dt	St	Sd cu	E-some climbers	
<b>Dalbergia</b> ecastophyllum	<b>Shore Bean Shrub</b>	10	9		Sl- H	M			Sd cu	E-trailing branches, leaves pinnate	

## Plant List: Trees & shrubs

Table 7 (continued)

Botanical Name	Common Name	Zone of Hardiness	Height ft	Growth Rate	Optim Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	Foliage/Trunk Characteristics	Silhouette
<b>Dipholis salicifolia</b>	<b>Willow Bustin</b>	10	75		Sn- <sup>H</sup>	I				<b>E-pinnate leaves</b>	
<b>Drypetes lateriflora</b>	<b>Guina Palm</b>	10	25		H-Si	I				<b>E-alternate leathery leaves</b>	
<b>Elaeagnus angustifolia</b>	<b>Oleaster</b>	2	20		Sn-L	D	Dt	St		<b>D-dull grey green; dense; trunk crooked with peeling bark</b>	
<b>Elaeagnus commutata</b>	<b>Silverberry</b>	3	12		Sn-L	D	Dt			<b>D-branchlet red brown scales, leaves silvery</b>	
<b>Erica tetralix</b>	<b>Heath</b>	3	2	S	Pt	M			Sd cu	<b>E-needlelike woody, grey</b>	
<b>Ericameria ericoides</b>	<b>Heath Composite</b>	10	2.5	S	Sn	I		St		<b>E-heathlike</b>	
<b>Erithalis fruticosa</b>	<b>Dune Berry</b>	10	9		Sn	D		St		<b>E-leaves dark green glossy, smooth stems</b>	
<b>Escallonia rosea</b>	<b>Escallonia</b>	10	10	F		M			Sd cu	<b>E-glandular viscid stout branches</b>	




## Plant List: Trees & shrubs

Plant List: Trees & shrubs										
Botanical Name		Common Name		Table 7 (continued)						
				Foliage/Trunk Characteristics		Silhouette				
Zone of Hardiness	Height ft	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique			
9	00		Sn-I	D	Dt	St	Sd	E		
9	50		Sn-I	D	Dt			E		
9	30	F	Sn	M, I				E-loup shiny leaves, dull underside		
9	36	F	Sn	M, I				E		
9	25	F	Sn					E		
10	25		Hu	M				E-shrub or small tree with glabrous stems		
7	20		Sn	I			Sd Cu	E		
9	60	F	M	M				E-engulfs tree stems		

# Plant. List: Trees & shrubs

Table 7 (continued)

Botanical Name	Common Name	Zone of Hardiness	Height (ft.)	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	Foliage/Trunk Characteristics	Silhouette
<b>Ficus laevigata</b>	<b>Wild Fig</b>	10	36		H	M				E-elliptical or ovate, glabrous leaves	
<b>Forestiera porulosa</b>	<b>Florida Privet</b>	9	10		H	M		St		E-glabrous stems evergreen, leaves elliptic	
<b>Forsythia suspensa</b>	<b>Weeping Forsythia</b>	4	9	F	Ac	D, M	Dt		Cu	D-weeping branch yellow flowers	
<b>Fraxinus americana</b>	<b>White Ash</b>	3	120	F	Sl	M			Sd	D-dense foliage autumn color purple, yellow	
<b>Fraxinus nigra</b>	<b>Black Ash</b>	3	75	M	L	M			Sd	D-dense foliage	
<b>Fraxinus pennsylvanica</b>	<b>Green Ash</b>	2	60	F	Ak	M			Sd	D-dense foliage, autumn color yellow	

## Plant List: Trees & shrubs

Table 7 (continued)

Botanical Name	Common Name	Foliage/Trunk Characteristics								Silhouette
		Zone of Hardness	Height (ft.)	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	
<b>Fraxinus velutina</b>	<b>Velvet Ash</b>	7	45		Ak	D				D-open foliage
<b>Gaylussacia baccata</b>	<b>Black Huckleberry</b>	5	1.5		Sn	M			Sd Di	E
<b>Gossypium religiosum</b>	<b>Tree Cotton</b>	10	4	S	L	M			Sd	D-bushy, much branched
<b>Grevillea robusta</b>	<b>Silk-oak Grevillea</b>	10	50		Sn					E-long feathery leaves, white silky undersurface
<b>Guaiacum sanctum</b>		10	30		Sn	I			Sd	E-leaves with 3-4 pairs of obovate subsessile leaflets
<b>Guilandina bonduc</b>	<b>Nicker-nut</b>	10	12		Hu	M				ll-leaflets oblong-oval
<b>Guilandina crista</b>	<b>Wood Gossip</b>	10	12		Hu	M				ll-shrub scraggly, reclining over vegetation, viscid pubescent and prickly with


# Plant List: Trees & shrubs

Table 7 (continued)

Botanical Name	Common Name	Zone of Hardiness	Height (ft.)	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	Foliage/Trunk Characteristics	Silhouette
Hibiscus syriacus	Shrubal thea	4	21	M	Sn L	M	Dt		Cu	D-curved spines throughout	
Hibiscus tiliaceus	Sea Hibiscus	10	25	F	Sn	A, I	Dt	St	Sd cu	D	
Hippophae rhamnoides	Common Sea-buckthorn	3	30							D-greyish green willow-like leaves	
Hudsonia tomentosa	False Heather	4	1	F	Sn	D	Dt	St		E-dense, scale-like leaves	
Hydrangea arborescens	Shrub Hydrangea	4	10	M	Ps	I	Dt		cu	D	
Hypericum aspalanthoides	Sand Cypress	4	3	F	Sn	D			Sd cu	E	
Hypericum fasciculatum	Sand Cypress	4	2	F	Sn	D			Sd cu	E	

# Plant List: Trees & shrubs

Table 7 (continued)


Botanical Name	Common Name	Zone of Hardiness	Height (ft.)	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant:	Salt Spray Tolerant:	Planting Technique	Foliage/Trunk Characteristics	Silhouette
<i>Ilex opaca</i>	hollberry	10			H	I				E-leaves on stout petioles, flowers in terminal dense panicles, light colored smooth stems, shrub or small tree	
<i>Ilex glabra</i>	Gallberry	3	20	M	Sn	M			Sd Cu	E-lustrous, dark leaves	
<i>Ilex opaca</i>	American Holly	5	40	M	Sn-L	M	Dt		Sd cu	E-dense spiny leaves, not lustrous; bark smooth light grey	
<i>Ilex vomitoria</i>	Yaupon	7	24	M	Sn-L	M	Dt	St	Sd cu	E-long, lustrous leaves	
<i>Ilex verticillata</i>	Winterberry	3	9	M	L	M			Sd cu	D-autumn color yellow, red fruit borne with green leaves	
<i>Jacquinia keyensis</i>	Joewood	10	15		Sn-Sl	M, I				F	

## Plant List: Trees & shrubs

Botanical Name		Common Name		Zone of Hardiness	Height, ft.	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	Foliage/Trunk Characteristics	Silhouette
Juniperus communis	Common Juniper	2	10	M	Sn-Sl	D	Dt					E-needlelike, brown in winter, spreading	
Juniperus conferta	Shore Juniper	5	1		Sn	I	Dt	St				E-needlelike, blue/green, spreading	
Juniperus excelsa stricta	Greek Juniper	7	60	S								E-narrow, pyramidal habit	
Juniperus lucayana	West Indies Juniper	9	50									E-pyramidal habit small, pointed leaves	
Juniperus silicola	Southern Red Cedar	8	90		Sn	D						E-leaves scale-like, opp. or 3-4 whorled	
Juniperus procumbens	Creeping Juniper	4	2.5			I						E-wide-spreading, mound-like shrub, leaves needle-like, bluish, in whorls of 3	


## Plant List: Trees & shrubs

Table 7 (continued)

Botanical Name	Common Name	Zone of Hardiness	Height (ft.)	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	Foliage/Trunk Characteristics	Silhouette
<i>Juniperus virginiana</i>	Eastern Red Cedar	2	90	S	G,L	I				E-scalelike bark shredding in long strips	
<i>Kalmia latifolia</i>	Mountain Laurel	4	30	S	Ac	M	Dt		Sd Cu		
<i>Keteleeria fortunei</i>	Fortune Keteleeria	7	90			D				E-pyramidal habit, needlelike foliage	
<i>Koelreuteria paniculata</i>	Golden-rain Tree	5	30		Mst				Sd	D-no autumn color yellow summer flowers	
<i>Krugiodendron ferreum</i>	Ironwood	10	30		Hu	M				E-leaves ovate or elliptical, dark green above, paler beneath	
<i>Lagunaria patersonii</i>	Paterson Sugar-plum Tree	9	50					St		E-pyramidal habit	
<i>Lantana involucrata</i>	Lantana	9-10	6		L	I			Sd Cu		

## Plant List: Trees & shrubs

Table 7 (continued)

Botanical Name	Common Name	Table 7 (continued)							Foliage/Trunk Characteristics	Silhouette
<b>Lantana</b> câmară	<b>Common</b> Lantana	8	6						<b>E-smooth shrub, usually armed with small or stout recurved prickles</b>	
<b>Lantana</b> horrida		6	6						<b>E-shrubs, leaves opp., lanceolate to broadly ovate</b>	
<b>Larix</b> decidua	<b>European</b> Larch	5	100	S	Opt- L				<b>D-leaves soft bright green, bark dark grey- ish brown</b>	
<b>Larix</b> laricina	<b>Eastern</b> Larch	7	60		Opt st				<b>D-open foliage</b>	
<b>Larix</b> leptolepis	<b>Japanese</b> Larch	5	90	M-S	Opt- L				<b>D-leaves soft bluish green, bark grey peelin</b>	



## Plant List: Trees & shrubs

Table 7 (continued)

Botanical Name	Common Name	Foliage/Trunk Characteristics							Silhouette
		Zone of Hardiness	Height (ft.)	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique
<b>Lavatera assurgentiflora</b>	<b>Tree Mallow</b>	10	10		Sn				Sd cu
<b>Leiophyllum buxifolium</b>	<b>Sand Myrtle (Box)</b>	5	1'		Ac	M			Sd cu
<b>Lespedeza bicolor</b>	<b>Shrub Lespedeza</b>	4	10		Sn				Sd
<b>Leptospermum scoparium</b>	<b>Tea Tree</b>	9	20		Sn	D	Dt	St	Sd cu
<b>L. ibocedrus decurrens</b>	<b>California Incense Cedar</b>	5	35		Ri	M			
<b>L. ligustrum lucidum</b>	<b>Glossy Privet</b>	7	30	F	Mst	I	Dt	St	Sd cu Di
<b>Ligustrum ovalifolium</b>	<b>Privet</b>	5	15	F	Mst	I			id cu Di

# Plant List: Trees & shrubs

Table 7 (continued)

Botanical Name	Common Name	Zone of Hardiness	Height ft	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	Foliage/Trunk Characteristics	Silhouette
<b>Liquidambar styraciflua</b>	Sweetgum	4	25							D-broadly pyramidal, scarlet autumn color	
<b>Lonicera involucrata</b>	Bearberry	2	3	M	L	I			Sd Cu	D	
<b>Lonicera mackii</b>	Amur Honeysuckle	4	15	M	Mst	I	Dt			D-branchlets hairy, leaves dark green	
<b>Lonicera morrowii</b>	Honeysuckle	4	6	M	L	I				D-dense foliage	
<b>Lyonia ferruginea</b>	Rusty Lyonia	9	15		AC	I, I, )				E	
<b>Lyonia lucida</b>	Petter Bush	7	6		H	I				D-erect shrub with evergreen leaves, branches smooth	
<b>Lysiloma bahamensis</b>	Wild Tamarind	10	60		AC	I, I, )				E	

## Plant List: Trees & shrubs

Table 7 (continued)

Botanical Name	Common Name	Table 7 (continued)							Foliage/Trunk Characteristics	Silhouette
Botanical Name	Common Name	Zone of Hardiness	Height (ft.)	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	
<b>Maclura pomifera</b>	<b>Osage-Orange</b>	5	60	F			Dt			
<b>Magnolia grandiflora</b>	<b>Magnolia</b>	7	90	F	L	M	Dt	St		
<b>Magnolia virginiana</b>	<b>Sweet Bay</b>	5	60		Yst	M				
<b>Maytenus boaria</b>	<b>Chile Mayten</b>	9	35					St		
<b>Melaleuca leucadendra</b>	<b>Cajeput Tree</b>	10	40							
<b>Melia azedarach</b>	<b>Chinaberry</b>	7	45		Yst		Dt		Sd Cu	

## Plant List: Trees & shrubs

Table 7 (continued)

Botanical Name	Common Name	Table 7 (continued)							Foliage/Trunk Characteristics	Silhouette
Botanical Name	Common Name	Zone of Hardiness	Height ft	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	
<i>Metopium toxiferum</i>	Poison Wood	9	43		Sn	I				E-Resinous sap. Leaves with 3-7 ovate, coriaceous leaflets
<i>Myrica californica</i>	Wax-myrtle	7	36			M			Sd, Sk	E-lustrous, bronze
<i>Myrica cerifera</i>	Wax-myrtle	6	20	M	Sh	M	Dt	St	Sd, Sk	E
<i>Myrica gale</i>	Sweet-gale	4	5	S	Pt	M			Sd, Sk	D
<i>Myrica pensylvanica</i>	Bayberry	4	9	S	Sn-	M	Dt		Sd, Sk	D-dull green, semi-evergreen
<i>Nectandra coriacea</i>	Lancewood	10	30		H	M				E
<i>Nerium oleander</i>	Oleander	7	20			I	Dt	St	CU	E-bamboolike
<i>Nyssa sylvatica</i>	Black Gum	4	90	5	st	M				D
<i>Olea europaea</i>	Common Olive	9	25		st	D	Dt			E-gray/green foliage, silvery beneath



## Plant List: Trees & shrubs

Table 7 (continued)

Plant List: Trees & shrubs		Table 7 (continued)									
Botanical Name	Common Name	Zone of Hardiness	Height (ft.)	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	Foliage/Trunk Characteristics	Silhouette
Opuntia austrina	Prickly Pear	9	½			D	Dt		Sd, Cu	E-bright green, flat broad fleshy pads	
Opuntia humifusa	Prickly Pear	4	½	S	Sn Rk	D	Dt		Sd, Cu	E-spreading flat broad pads	
Opuntia lindheimeri	Prickly Pear	8	12	M	Sn G	D	Dt		Sd, Cu	E-spiny flat broad pads	
Opuntia serpentina	Cholla	9				D	Dt		Sd, Cu	E-cylindrical branches, spiny	
Osmanthus americanus	Wld Olive	7	70							E-leathery leaves bark dark brown and ridged	
Pandanus babiltsii	Screwpine	9		F		M	Dt	St	Sd, Sk	E-stiff, linear prickly edged leaves	
Parkinsonia aculeata	Jerusalem Thorn	9	30		Sn					D-open habit, green bark	
Paspalum caespitosum	Bunch Millet	10	1-1½		H	I				grass	



# Plant List: Trees & shrubs

Table 7 (continued)

Botanical Name	Common Name	Zone of Hardiness	Height (ft.)	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	Foliage/Trunk Characteristics	Silhouette
<b>Persea borbonia</b>	<b>Red Bay</b>	8	40	M	Sl, Pt	M	Dt	St	Sd, Cu	E	 1" = 120'
<b>Persea littoralis</b>	<b>Shore Bay</b>		60		Mst	M			Sd, Cu	E	
<b>Picea abies</b>	<b>Norway Spruce</b>	2	150	M	Sl, L	M		St		E-dense, dark green needles	
<b>Picea asperata</b>	<b>Dragon Spruce</b>	5	75							E-dense foliage light green/blue	 1" = 120'
<b>Picea mariana</b>	<b>Black Spruce</b>	3	40	S	St, I	M				E-dense needles	
<b>Picea pungens</b>	<b>Colorado Spruce</b>	2	100	F					Sd, Cu	E-pyramidal habit	
<b>Picea sitchensis</b>	<b>Sitka Spruce</b>	5	150	S	Al, Sl	M				E-pyramidal habit	



## Plant List: Trees & shrubs

Table 7 (continued)

Botanical Name	Common Name	Zone of Hardiness	Height (ft.)	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	Foliage/Trunk Characteristics	Silhouette
Picramnia pentandra	Bitterbush	1°			H	M				E-shrubs or small trees	
Pinus attenuata	Knobcone Pine	6	75	F	Sn, G	D	Dt			E-yellow/green	
Pinus banksiana	Jack Pine	2	75	F	Sn	D			Sd	E-2 needles in bundle, open	
Pinus clausa	Sand Pine	9	15	F	Sn, G	D	Dt	St		E-2 needles in bundle, flexible	
Pinus contorta	Lodgepole Pine	3	25	F	Sn	M	Dt		Sd	E-2 needles in bundle, stiff, dark green	

# Plant List: Trees & shrubs

Table 7 (continued)

Botanical Name	Common Name	Zone of Hardiness	Height, ft.	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	Foliage/Trunk Characteristics	Silhouette
<i>Pinus elliottii</i>	Slash Pine	8	80	F	Sn	M	Dt	St		E-Z needles in bundle, stiff, dark blue/green	
<i>Pinus elliottii</i> densa	Southern Pine	10	90		P0	D				E-open cones with rounded base. Scaly bark	
<i>Pinus nigra</i>	Black Pine	4	90	F	Sn	D	Dt	St	Sd	E-Z needles in bundles, dark green	
<i>Pinus pinaster</i>	Cluster Pine	7	90	F	Sn			St	Sd	E-Z needles in bundle, twisted & glossy green	
<i>Pinus radiata</i>	Monterey Pine	7	60	F	Sn			St		E-3 needles in bundle, bright green	



## Plant List: Trees & shrubs

Table 7 (continued)

Botanical Name		Common Name		Foliage/Trunk Characteristics										Silhouette
Zone of Hardiness	Height (ft.)	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	Foliage/Trunk Characteristics				Silhouette		
Pinus rigida	Pitch Pine	4	75	F	Rk		Dt		Sd	E-3 needles in bunch, open				
Pinus serotina	Pond Pine	6-9	75		Sn, L	M				E-3 needles in bundle, flexible dark yellow/green				
Pinus strobus	White Pine	3	150	F	Sn, L	I			Sd	E-5 needles in bundle, soft & flexible				
Pinus sylvestris	Scotch Pine	2	75							E-reddish bark; open, pyramidal habit				
Pinus taeda	Loblolly Pine	5	70	F	Sn, Mst	I	Dt		Sd	E-3 needles in bundle, stiff, yellow green				


## Plant List: Trees & shrubs

Table 7 (continued)

Botanical Name	Common Name	Height (ft.)	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	Foliage/Trunk Characteristics	Silhouette
<i>Pinus thunbergii</i>	Japanese Black Pine	90	F				St		E:-dense, spreading	
<i>Pinus torreyana</i>	Torrey Pine	45	F	Sn	I	Dt			E-5 needles in bundles, stiff, dark green	
<i>Piscibia piscipula</i>	Poisonwood	50							D	
<i>Pisonia aculeata</i>	Cock-spur	10		H	M				Dl-woody, climbing vines with branched thorns, ultimate branches curved and very sharp	
<i>Pithecellobium guadalupensis</i>	Black Bead	15							E:-spiny foliage	
<i>Pithecellobium unguis-cati</i>	Cats Claw	50		Sn	D				E-spiny foliage	
<i>Pittosporum crassifolium</i>	Karo	15-30		L		Dt	St	Cu Sd	E	

## Plant List: Trees & shrubs

Table 7 (continued)



Botanical Name	Common Name	Zone of Hardiness	Height ft.	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	Foliage/Trunk Characteristics	Silhouette
<b>Platanus acerifolia</b>	<b>London Plane</b>	3	<b>120</b>	M	Ri	M				<b>D-large, wide coarse leaves, bark flakes off to greenish/white below</b>	
<b>Platanus occidentalis</b>	<b>American Plane</b>	3	<b>150</b>	M	L	I	Dt		Sd, Cu	<b>D-large, wide, coarse leaves, bark flakes off to greenish/white below</b>	
<b>Populus alba</b>	<b>White Poplar</b>	3	<b>90</b>	F	L	D			Cu	<b>D-upper leaves gray/green, lower white</b>	
<b>Populus deltoides</b>	<b>Eastern Cottonwood</b>	2	<b>90</b>	F	Al	M			Sk	<b>D-dense foliage</b>	
<b>Populus fremontii</b>	<b>Fremont Cottonwood</b>	7	<b>90</b>	F	Ak	D			cu	<b>D-wide habit, open foliage</b>	

# Plant List: Trees & shrubs

Table 7 (continued)


Botanical Name	Common Name	Zone of Hardiness	Height (ft.)	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	Foliage/Trunk Characteristics	Silhouette
Populus heterophylla	Swamp Cottonwood	5	89	F	A1, S1	M				D-foliage dark green, paler below, bark red/brown, scaley	
Populus tremuloides	Quaking Aspen	1	80	F	Sn, L	D	Dt		Sk	D-open habit, yellow a/c	
Populus trichocarpa	Black Cottonwood	3	100	F	Ak				cu	D	
Prosopis glandulosa	Honey Mesquite	8	50	S			Dt			D-bright green feathery foliage	
Prosopis juliflora	Mesquite	7	20	F	lst	D	Dt		Sd	D-compound leaves	
Prunus caroliniana	Laurel Cherry	8	40		lst		Dt	St	Sd	E	
Prunus depressa	Beach Cherry	3	5		lst				Sd	D	
Prunus lyonii	Catalina Cherry	10	24		lst				Sd	E	

# Plant List: Trees & shrubs

Botanical Name		Common Name		Table 7 (continued)									
Botanical Name		Common Name		Zone of Hardiness	Height ft	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	Foliage/Trunk Characteristics	Silhouette
<b>Prunus maritima</b>		<b>Beach Plum</b>		3	6	M	Mst	D	Dt	St	Sd	D	
<b>Prunus pumila</b>		<b>Sand (dwarf) Cherry</b>		3	5	M	Mst	D	Dt		Sd	D-prostrate	
<b>Prunus serotina</b>		<b>Black Cherry</b>		3	90	M	Mst	M			Sd	D-dense foliage, with flowers	
<b>Prunus serrulata</b>		<b>Japanese Flowering Cherry</b>		5,6	25	F	Mst	I			Sd	D-white/pink flowers	
<b>Prunus virginiana</b>		<b>Choke Cherry</b>		2	25	M	Mst	M			Sd	D	
<b>Pseudotsuga taxifolia</b>		<b>Douglas Fir</b>		4-6	300	F	L	M				E-dense foliage	
<b>Pyrus arbutifolia</b>		<b>Red Chokeberry</b>		4	10	S	L	M				D-hollylike	




# Plant List: Trees & shrubs

Table 7 (continued)

Botanical Name	Common Name	Zone of Hardiness	Height (ft.)	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Brought Tolerant	Salt Spray Tolerant	Planting Technique	Foliage/Trunk Characteristics	Silhouette
<b>Quercus agrifolia</b>	<b>California Live Oak</b>	9	90	S	L, Gr	D	Dt		Sd	<b>E-dense, a/c purplish/red</b>	 1" = 120'
<b>Quercus alba</b>	<b>White Oak</b>	4	90	S	M t	M			Sd	<b>D-foliage dark green above, silvery beneath; bark, dark gray</b>	
<b>Quercus bicolor</b>	<b>Swamp White Oak</b>	3	60		M					<b>D-dense foliage, yellow/brown-red a/c</b>	
<b>Quercus chapmani</b>	<b>Chapmans Oak</b>	9	50		Sn				Sd	<b>D</b>	
<b>Quercus cinerea</b>	<b>Blue-jack Oak</b>	8	40		Sn			St	Sd	<b>D</b>	
<b>Quercus ilex</b>	<b>Holly Oak</b>	9	60	M	L	I		St	Sd	<b>E-holly-like dense dark green foliage; very hardy</b>	
<b>Quercus kelloggii</b>	<b>California Black Oak</b>	7	90		Sn, G					<b>D-dense foliage</b>	



# Plant List: Trees & shrubs

Table 7 (continued)

Botanical Name	Common Name	Zone of Hardiness	Height (ft.)	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	Foliage/Trunk Characteristics	Silhouette
<i>Quercus laevis</i>	Turkey Oak	8	30		Sn				Sd	D	
<i>Quercus laurifolia</i>	Laurel Oak	7	60			M			Sd	E-half evergreen, dark green	 1" = 120'
<i>Quercus macrocarpa</i>	Bur Oak	2	70	M	Mst Cl	D	Dt		Sd	D-a/c brown, yellow	
<i>Quercus montana</i>	Chestnut Oak	4	90		Rk	D				H-dense habit, dull orange a/c	
<i>Quercus myrtifolia</i>	Myrtle Oak	8-10			Sn	D			Sd	E	 1" = 120'
<i>Quercus rubra</i>	Red Oak	2	70	M	L	M			Sd	D-a/c brown, yellow	


# Plant List: Trees & shrubs

Table 7 (continued)

Botanical Name	Common Name	Zone of Hardiness	Height (ft.)	Growth Rate	Optimum Soil Condition	Optimum Root Moisture	Rooting habit	Alt Spray	Planting technique	Foliage/Trunk Characteristics	Silhouette
<i>Quercus velutina</i>	Black Oak	4	100	M	L	M-D	Dt		Sd	D-foliage dark green, a/c red	
<i>Quercus virginiana</i>	Live Oak	7	60	M	Sn	M			Sd	E-deciduous in northern limits only	
<i>Quercus virginiana maritima</i>	Dune Live Oak	8-10			Sn	D	Dt	St	Sd	E-small leaves	
<i>Randia aculeata</i>	White Berry	10	10		Sn	I				E-branched spiny shrub or small tree; scrub vegetation	
<i>Rapanea quianensis</i>	Myrsine	10			H	M				E-shrubs or low trees with thick branches; leaves entire, clustered near ends of stems	




## Plant List: Trees & shrubs

Plant List: Trees & shrubs										Table 7 (continued)	
Botanical Name	Common Name	Zone of Hardiness	Height (ft.)	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	Foliage/Trunk Characteristics	Silhouette
Reynosa septentrio- nalis	Darling Plum	10	30		H	M				E-leaves ovate or ovate-elliptical	 1" = 120'
	Rhamus californica	Coffee Berry	9	6			D		Sd, Cu	E	
Rhus copallina	Winged Sunac	4	15	F	Sn	D	Dt		Sd, su	D-lustrous green foliage; a/c scar let	
Rhus diversiloba	Poisonwood	8	8						Sd, cu	D-erect shrub	
Rhus glabra	Smooth Sunac	2	20		Sn	D			Sd, cu	D-a/c bright red	
Robinia fertilis (hispid)	Bristly Locust	6	1-7	M	su AC	I	Dt			D-flws., rose-colored or pale purple, freely fruiting; branch- ing shrub, stout stems, red bris- tles	
Robinia pseudoacacia	Black Locust	3	75	F	Sn, L	I	Dt		Sd, su	D-open foliage flowers pea-like and fragrant	


## Plant List: Trees & shrubs

Table 7 (continued)

Botanical Name	Common Name	Zone c	Hardi	Height	Growth	Optimu	Condi	Optimu	Zone	Drough	Tolera	Salt s	Plant	Foliage/Trunk Characteristics	Silhouette
Rosa rugosa	Rugose Rose	2	6	M	Sn	D	Dt	St	Su	D-dark green foliage, a/c orange					
Rosa virginiana	Shrub Rose	3	6	M	Mst	I			Su, Rt	D-glossy foliage; a/c scarlet, orange; winter twigs red					
Roystonea regia	Royal Palm	10	70				Dt			E-araceful foliage					
Rubus vitifolius	Blackberry	9	6		L				Sd, Cu, Sk	E-bright green, vinelike					
Sabal etonia	Palmetto Scrub Fan Palm	10	3		Sn	D				E-leaves dark green, filiferous					
Sabal minor	Dwarf Palmetto	9	4		Rk	M	Dt			E-stenless pale green stiff leaves					
Sabal palmetto	Cabbage Palm	8	90		Mst	I				E-coarse, fan-shaped; brownish gray bark					




## Plant List: Trees & shrubs

Plant List: Trees & shrubs											Table 7 (continued)												
Botanical Name		Common Name		Zone of Hardiness		Height ft		Growth Rate		Optimum Soil Condition		Optimum Root Zone Moisture		Drought Tolerant		Salt Spray Tolerant		Planting Technique		Foliage/Trunk Characteristics		Silhouette	
Sageretia	minutiflora	Rattan	Vine	7-11						Sn								Sd, Cu		D/E-dependent on zone, trailing, spiny, leathery leaves			
Salix	babylonica	Babylon	Weeping Willow	6	30	F				Sl, Al		M						Cu		D-fine texture foliage			
Salix	cordata	Bushy	Willow	2	5					Sn		M						Cu		D-clustered shrub			
Salix	discolor	Pussywillow		2	20	F				Sl, Al		M						Cu		D-light green foliage			
Salix	glaucophylla	Dune (Low)	Willow	2	15					Sn		M						Cu		D			
Salix	gooddingii	Goodding	Willow	7	60					Al		M								D-like Black Willow, yellow, narrow lanceolate twigs, leaves			

## Plant List: Trees & shrubs

Table 7 (continued)

Botanical Name	Common Name	Zone 4 Hardiness	Height (ft.)	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	Foliage/Trunk Characteristics	Silhouette
Salix hindsiana	Sandbar Willow	8-9	21		Sn	I				D-erect shrub, gray furrowed bark	
Salix hookeriana	Coast Willow	7	25			M			Cu	D-bright green foliage	
Salix humilis	Small Pussy-willow	3	8		Sn	M			Cu	D-ellanceolate leaves	
Salix interior	Sandbar Willow	2	30		Sn, Al	M			Cu	D-yellow/green foliage	
Salix lasiolepis	Sand Willow	6	30		Al	M			Cu	D-dark green foliage above, gray below	
Salix lucida	Shining Willow	2	20	F	Al, Sl	M			Cu	D-lustrous dark green foliage	
Salix nigra	Black Willow	3	30	F	Al	M			Cu	D-ridged, dark brown/black bark	
Salix pentandra	Bay-leaved Willow	4	60	F		M			Cu	D-dark green laurel-like foliage	


## Plant List: Trees & shrubs

Table 7 (continued),

Botanical Name	Common Name	Table 7 (continued),							Foliage/Trunk Characteristics	Silhouette
Botanical Name	Common Name	Zone of Hardiness	Height ft.	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	
<b>Salix petiolaris</b>	<b>Meadow Willow</b>	2	4			M			Cu	D-purple twigs
<b>Sassafras albidum</b>	<b>Sassafras</b>	4	125		L	I, D	Dt		Su	D-1, 2, 3 lobed leaves, aromatic
<b>Scaevola lumieri</b>	<b>Beach Berry</b>	10	5		Sn	D	Dt	St		E-pantropical
<b>Schaefferia frutescens</b>	<b>Yellow Wood</b>	10	36		Hu	I				D-tropical, light gray older stems with wart-like clusters, leaves shiny yellow green
<b>Schinus molle</b>	<b>California Pepper Tree</b>	9	40		P0	D	Dt			E-wide spreading branches
<b>Schinus terebinthifolius</b>	<b>Brazil Pepper Tree</b>	9, 10	40			D	Dt	St		E-dark green foliage
<b>Schoepfia chryso-phyloides</b>	<b>Whitewood</b>	10	25		H	I				E-young branches pale or white, older bark conspicuously grayish white




## Plant List: Trees & shrubs

Table 7 (continued)

Botanical Name	Common Name	Zone C Hardiness	Height	Growth	Optim. Cond't	Optim. Zone	Drought Tolerant	Salt Tolerant	Planting Technique	Foliage/Trunk Characteristics	Silhouette
Sequoia sempervirens	Redwood	10	265	F	Sn, L	M				E-flat light green segments of leaves	 1" = 340'
Serenoa repens	Saw Palmetto	8	3		Sn	D				Z-foliage dense, creeping	
Solanum verbascifolium	Shrub Solanum	10	30						Sd, Cu	E	
Sophora japonica	Japanese Pagoda Tree	4	75		Mst					U-open, rounded habit	
Swietenia mahogany	Madeira Mahogany	10	60		M					E	
Tamarix gallica	Tamarix	7, 8	12	M	Mst	M	Dt	St	Cu	U-blue/green scale-like leaves, small and feather-like; smooth bark	


# Plant List: Trees & shrubs

Table 7 (continued)

Botanical Name	Common Name	Zone of Hardiness	Height (ft.)	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	Foliage/Trunk Characteristics	Silhouette
<b>Taxodium distichum</b>	<b>Common Bald Cypress</b>	4	150		L	M				<b>D-open foliage, feathery, needle-like</b>	
<b>Taxus brevifolia</b>	<b>Western Yew</b>	6	75	S	H	M			Cu	<b>E-needles dark green</b>	
<b>Thespesia populnea</b>	<b>Seaside Mahoe</b>	10	60			M			Sd	<b>D-pantropical coastal areas</b>	
<b>Thrinax microcarpa</b>	<b>Brittle Thatch-palm</b>	10	30		Sn	D				<b>E-gray bark</b>	
<b>Thrinax parviflora</b>	<b>Jamaica Palm</b>	10	30							<b>E-pale green foliage</b>	
<b>Thuja occidentalis</b>	<b>American Arbor-vitae</b>	2	60							<b>E-columnar habit</b>	

# Plant List: Trees & shrubs

Table 7 (continued)

Botanical Name	Common Name	Zone of Hardiness	Height ft	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique	Foliage/Trunk Characteristics	Silhouette
<b>Thuja orientalis</b>	<b>Oriental Arbor-vitae</b>	6	50							<b>E-pyramidal, open habit</b>	 1"=120'
<b>Tilia americana</b>	<b>Basswood</b>	5	100	F	L	I			S	<b>D-open foliage; large, coarse leaves</b>	
<b>Tilia cordata</b>	<b>Little-leaf Linden</b>	3	90	F	Mst					<b>D-dense, pyramidal</b>	
<b>Tilia euchlora</b>	<b>Crimean Linden</b>	5	60	F						<b>D-glossy, bright green leaves</b>	
<b>Torrubia longifolia</b>	<b>Longleaf Blolly</b>	9	40							<b>E</b>	
<b>Trema lamarkiana</b>	<b>West Indies Trem</b>	10	20		H	M				<b>E-thickly pubescent twigs. Leaves upper surface rough pubescent</b>	
<b>Tsuga canadensis</b>	<b>Canada Hemlock</b>	3	90	M	Ac	M			S	<b>E-dense, needle-like dark green</b>	



## Plant List: Trees & shrubs

Botanical Name	Common Name	Table 7 (continued)							
		Zone of Hardiness	Height (ft.)	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant	Planting Technique
<b>Tsuga heterophylla</b>	<b>Western Hemlock</b>	6	200	1	Ac, L	M			S
<b>Ulex europaeus</b>	<b>Gorse</b>	4	6		Mst			St	
<b>Ulmus fulva</b>	<b>Slippery Elm</b>	3	60		Ri				Sd, CU
<b>Ulmus parvifolia</b>	<b>Chinese Elm</b>	5	50	1					E-dense foliage; red/purple a/c
<b>Ulmus pumila</b>	<b>Siberian Elm</b>	4	75	F		D			D-round habit, small leaves
<b>Umbellularia californica</b>	<b>California Laurel</b>	7	75		Mst				E-dense, round habit

Foliage/Trunk Characteristics	Silhouette
E-dense, needle-like	
D-low, densely spiny branched shrub used as sandbinder	
D-spreading branches, leaves unequal at base	
E-dense foliage; red/purple a/c	
D-round habit, small leaves	
E-dense, round habit	

# Plant List: Trees & shrubs

Botanical Name		Common Name	Table 7 (continued)								Foliage/Trunk Characteristics	Silhouette
<b>Vaccinium arboreum</b>	<b>Sparkle Berry</b>		7	27							E	
<b>Vaccinium corymbosum</b>	<b>Highbush Blueberry</b>		4	12	M	Mst	M				D-erect clump of stems	
<b>Vaccinium myrsinites</b>	<b>Shiny Blueberry</b>		9	2		Ac, Sn	I				E-foliage has bristly teeth	
<b>Vaccinium ovatum</b>	<b>California Hickberry, Blueberry</b>		8	12		Ac		Dt			E-stout branched	
<b>Vaccinium stamineum</b>	<b>Deerberry</b>		4	3	M	Ac	I				D	
<b>Vaccinium vacillans</b>	<b>Low Blueberry</b>		4	3	S	Ac	M	Dt			D-shiny green leaves	
<b>Viburnum lentago</b>	<b>Nanny Berry</b>		2	30	F	L	M		Sd, Cu		D-dense foliage, shiny green a/c purplish red	
<b>Vitex agnus-castus</b>	<b>Chaste Trees</b>		10	12		H	M				D-stems grayish, tomentose with strong, aromatic odor	
<b>Washingtonia filifera</b>	<b>Fan Palm</b>		8	75	S	Ak	M				E-light green foliage	

## Plant List: Trees & shrubs

Botanical Name	Common Name	Table 7 (concluded)						
		Zone of Hardiness	Maximum Height (ft.)	Growth Rate	Optimum Soil Condition	Optimum Root Zone Moisture	Drought Tolerant	Salt Spray Tolerant
<b>Washingtonia robusta</b>	<b>Mexican Washington Palm</b>	10	90			D	Dt	
<b>Ximenia americana</b>	<b>Hog Plum, Tallowood</b>	9	30					
<b>Yucca aloifolia</b>	<b>Spanish Bayonet</b>	9	25		Sn	D	Dt	
<b>Yucca filamentosa</b>	<b>Adams Needle, Silk Grass</b>	5	12	M	Sn	D	Dt	
<b>Zamia pumila</b>	<b>Florida Arrowroot Tree, Coontie</b>	10	1½		Sn	M	Dt	St
<b>Zanthoxylum herculis</b>	<b>Toothache Tree</b>	8	50			M		Sd, Cu
<b>Zanthoxylum fagara</b>	<b>Wild Line</b>	10	30	M	H, L	I		
		Foliage/Trunk Characteristics Silhouette E:-fanshaped, coarse foliage E:- smooth dark red brown bark E:-dark green foliage E E:- palm like leaver E:- prickly trunk E:-shrub, recurved prickles						



**Table: 8****Plant List of Additional Trees & Shrubs**

<u>BOTANICAL NAME</u>	<u>COMMON NAME</u>
<b>Elaeagnus umbellata</b> var. <b>cardinal</b>	<b>Autumn-olive</b>
<b>Euphorbia buxifolia</b>	<b>Shrub Spurge</b>
<b>Euphorbia ingallsi</b>	<b>Creeping Spurge</b>
<b>Euphorbia innocua</b>	<b>Spurge</b>
<b>Galactia canescens</b>	<b>Milk Pea</b>
<b>Juniperus camara</b>	<b>Juniper</b>
<b>Leucophyllum frutescens</b>	<b>White Leaf</b>
<b>Penstemon cordifolius</b>	<b>Heart-leaved Penstemon</b>
<b>Pithecellobium pallens</b>	<b>Pale Bead</b>
<b>Poinciana gilliesii</b>	<b>Bird of Paradise Shrub</b>
<b>Portulacaria afra</b>	<b>Speckboom</b>
<b>Prosopis reptans</b>	<b>Mesquite</b>
<b>Quercus durata</b>	<b>Leather Oak</b>
<b>Quercus oleoides</b> quatuna	<b>Texas Live Oak</b>
<b>Rubus arenicola</b>	<b>Sand Blackberry</b>
<b>Rumex crispus</b>	<b>Sorrel</b>
<b>Sabina barbadensis</b>	<b>Shore Juniper</b>
<b>Salix sitchensis</b>	<b>Silky Willow</b>
<b>Sideroxylon foetidissimum</b>	<b>False-nastic</b>
<b>Soriana maritima</b>	<b>Sea-blite</b>
<b>Stumpfia maritima</b>	<b>Cedar Wood</b>
<b>Tamarix articulata</b>	<b>Tamarix</b>

# **Table: 9**   **Plant List of Herbaceous Plant Material**

<b><u>BOTANICAL NAME</u></b>	<b><u>COMMON NAME</u></b>
<b>Abronia fragrans</b>	<b>Yellow Sand Verbena</b>
<b>Abronia latifolia</b>	<b>Red Sand Verbena</b>
<b>Abronia maritima</b>	<b>Chatt Flower</b>
<b>Achyranthes maritima</b>	<b>Hairy Wild Wheat</b>
<b>Agropyron dasystachyum</b>	<b>Wild Wheat</b>
<b>Agropyron pungens</b>	<b>Witch Grass, Couch Grass</b>
<b>Agropyron repens</b>	<b>Bush Aloe</b>
<b>Aloe arborescens</b>	<b>Sand Pigweed</b>
<b>Anaranthus arenicola</b>	<b>Marram Grass</b>
<b>Amophila arenaria</b>	<b>Big Blue Stem Grass</b>
<b>Andropogon furcatus</b>	<b>Big Blue Stem Grass</b>
<b>Andropogon gerardi</b>	<b>Beardgrass</b>
<b>Andropogon glomeratus</b>	<b>Beardgrass</b>
<b>Andropogon hirtiflorus</b>	<b>Coastal Beardgrass</b>
<b>Andropogon littoralis</b>	<b>Coastal Beardgrass</b>
<b>Andropogon scoparius littoralis</b>	<b>Beardgrass</b>
<b>Andropogon scoparius</b>	<b>Broom Sedge</b>
<b>Andropogon virginicus</b>	<b>Thinble Weed</b>
<b>Anemone cylindrica</b>	<b>Sea Sandwort</b>
<b>Arenaria peploides</b>	<b>Three-awned Grass</b>
<b>Aristida gyrans</b>	<b>Three-awned Grass</b>
<b>Aristida purpurascens</b>	<b>Wormwood</b>
<b>Artemisia caudata</b>	<b>Sand Sagebrush</b>
<b>Artemisia pycnocephala</b>	<b>Dusty Miller</b>
<b>Artemisia stelleriana</b>	<b>Butterflyweed</b>
<b>Asclepias tuberosa</b>	<b>Desert Aster</b>
<b>Aster tortifolius</b>	<b>Orach</b>
<b>Atriplex acanthocarpa</b>	<b>Seabeach Orach</b>
<b>Atriplex arenaria</b>	<b>Saltbush</b>
<b>Atriplex canescens</b>	<b>Orach</b>
<b>Atriplex littoralis</b>	<b>Orach</b>
<b>Atriplex patula</b>	<b>Saltwort</b>
<b>Batis maritima</b>	<b>Tar Flower</b>
<b>Befaria racemosa</b>	<b>Four O' clock</b>
<b>Boerhaavia coccinea</b>	
<b>Brassica geniculatum</b>	<b>Black Mustard</b>
<b>Brassica nigra</b>	<b>Hungarian Brome Grass</b>
<b>Bromus inermis</b>	<b>Sea Rocket</b>
<b>Cakile endentula</b>	<b>Dune Grass</b>
<b>Calamovilfa longifolia</b>	<b>Butterfly Mriposa</b>
<b>Calochortus venustus</b>	<b>Sea Bean, Bay Bean</b>
<b>Canavalia lineata</b>	

**Table 9 (continued)**

**BOTANICAL NAME**

Capparis cynophallophora  
 Carex arenaria  
 Carex kobomugi  
 Carex silicea  
 Cassia fasciculata  
 Castilleja litoralis  
 Cenchrus pauciflora  
 Cenchrus tribuloides  
 Centaurea solstitialis  
 Chenopodium album  
 Chenopodium ambrosioides  
 Chloris glauca  
 Chloris petraea  
 Chrysopsis graminifolia  
 Chrysopsis mariana  
 Cirsium pitcheri  
 Cnidoscolus stimulosus  
 Conradina grandiflora  
 Coreopsis gigantea  
 Corispermum hyssopifolium  
 Coronilla varia  
 Cynodon dactylon  
 Cyperus brunneus  
 Cyperus lecontei  
 Digitaria filiformis  
 Digitaria sanguinalis  
 Distichlis spicata  
 Echinocystis fabacea  
 Elymus arenarius  
 Elymus arenicola  
 Elymus canadensis  
 Elymus flavescens  
 Elymus mollis  
 Elymus robustus  
 Encelia californica  
 Equisetum arvense  
 Eragrostis amabilis  
 Eragrostis hypnoides  
 Eragrostis oxylepis  
 Erigeron canadensis  
 Eriogonum latifolium  
 Ernodea litoralis  
 Eryngium maritimum  
 Erysimum capitatum  
 Erythrina arborea  
 Eschscholzia californica

**COMMON NAME**

Bay-leaved Cappap  
 Sedge  
 Japanese Sedge  
 Sand Sedge  
 Dune Senna  
 Coastal Paint Brush  
 Sand-spur  
 Sand-spur  
 Pigweed  
 American Wormseed  
 Finger Grass  
 Finger Grass  
 Golden Aster  
 Golden Aster  
 Beach Thistle  
 Nettle  
 Shrub Mint  
 Tree Coreopsis  
 Bugseed, Tumbleweed  
 Crown Vetch  
 Bermuda Grass  
 Sedge  
 Coca-grass  
 Finger Grass  
 Finger Grass  
 Spike Grass  
 Wild Cucumber  
 Sea Lyme-grass  
 Sea Rye Grass  
 Wild Rye  
 Yellow Rye Grass  
 Dune Grass  
 Wild Rye  
 Bush Sunflower  
 Horsetail  
 Love-grass  
 Love-grass  
 Love-grass  
 Fleabane  
 Buckwheat  
 Coastal Ernodea  
 Sea Holly  
 Wall Flower  
 Coral Bean  
 California Poppy

**Table 9 (continued)**

<b>BOTANICAL NAME</b>	<b>COMMON NAME</b>
<b>Eugenia myrtoidea</b>	<b>Box Leaf Stopper</b>
<b>Euphorbia polygonifolia</b>	<b>Seaside Spurge</b>
<b>Festuca arenaria</b>	<b>Sand Fescue</b>
<b>Festuca arundinacea</b>	<b>Reed Fescue</b>
<b>Festuca rubra</b>	<b>Red Fescue</b>
<b>Finbristylis castanea</b>	<b>Sand Rush</b>
<b>Franseria chamissonis</b>	<b>Sand Ambrosia</b>
<b>Geobalanus oblongifolius</b>	<b>Gopher Apple</b>
<b>Grindelia humilis</b>	<b>Gum Plant</b>
<b>Guilandina bonduc</b>	<b>Nicker Vine</b>
<b>Guilandina crista</b>	<b>Nicker Vine</b>
<b>Haplopappus canus</b>	<b>Golden Bush</b>
<b>Helianthemum scoparium</b>	<b>Rush-rose</b>
<b>Helianthus debilis</b>	<b>Dune Sunflower</b>
<b>Heliotropium convolvulaceum</b>	<b>Heliotrope</b>
<b>Heliotropium curassavicum</b>	<b>Heliotrope</b>
<b>Heterotheca grandiflora</b>	
<b>Heterotheca subaxillaris</b>	<b>Golden Aster</b>
<b>Holcus lanatus</b>	<b>Velvet Grass</b>
<b>Hydrocotyle bonariensis</b>	<b>Seaside Pennywort</b>
<b>Hymenocallis keyensis</b>	<b>Key Spider-lily</b>
<b>Hymenocallis palmeri</b>	<b>Dune Spider-lily</b>
<b>Ipomoea per-caprae</b>	<b>Railroad Vine</b>
<b>Ipomoea spp.</b>	<b>Morning-glory</b>
<b>Ipomoea stolonifera</b>	<b>Beach Morning-glory</b>
<b>Iva frutescens</b>	<b>Marsh Elder</b>
<b>Iva inbricata</b>	<b>Marsh Elder</b>
<b>Jaumea carnosa</b>	
<b>Juncus longistylis</b>	<b>Coastal Rush</b>
<b>Juncus roemerianus</b>	<b>Needlerush</b>
<b>Lathyrus japonicus</b>	<b>Beach Pea</b>
<b>Lathyrus littoralis</b>	<b>Beach Pea</b>
<b>Lathyrus maritimus</b>	<b>Beach Pea</b>
<b>Lathyrus sylvestris</b>	<b>Flat Peavine</b>
<b>Lechea maritima</b>	<b>Pinweed</b>
<b>Lespedeza bicolor</b>	
<b>Lespedeza stipulacea</b>	
<b>Linonum carolinianum</b>	<b>Sea Lavender</b>
<b>Lippia nodiflora</b>	<b>Cape Weed</b>
<b>Lithospermum canescens</b>	<b>Puccoon</b>
<b>Lotus tenuis</b>	<b>Narrow Leaf Trefoil</b>
<b>Lupinus arboreus</b>	<b>Yellow Lupine</b>
<b>Lupinus chamissonis</b>	<b>Bush Lupine</b>
<b>Lupinus cumlicola</b>	<b>Sand Lupine</b>
<b>Lupinus littoralis</b>	<b>Seashore Lupine</b>
<b>Lupinus perennis</b>	<b>Wild Lupine</b>

**Table 9 (continued)**

<u>BOTANICAL NAME</u>	<u>COMMON NAME</u>
<b>Mytenus</b> phyllanthoides	<b>Guttapercha</b>
<b>Melilotus</b> albus	
<b>Melilotus</b> officinalis	
<b>Mesembryanthemum</b> aequilaterale	<b>Sea Fig</b>
<b>Mesembryanthemum</b> crystallinum	<b>Ice Plant</b>
<b>Mnanthochloe</b> litoralis	<b>Key Grass</b>
<b>Muhlenbergia</b> capillaris	<b>Hari Grass</b>
<b>Nicotiana</b> glauca	
<b>Oenothera</b> cheiranthifolia	<b>Sand Primrose</b>
<b>Oenothera</b> drummondii	<b>Evening Primrose</b>
<b>Oenothera</b> humifusa	<b>Evening Primrose</b>
<b>Oenothera</b> linearis	<b>Sundrops</b>
<b>Oenothera</b> micronata	<b>Sea Primrose</b>
<b>Panicum</b> amarulum	<b>Coastal Panic Grass</b>
<b>Panicum</b> amarum	<b>Dune Panic Grass</b>
<b>Panicum</b> clandestinum	<b>Deertongue Grass</b>
<b>Panicum</b> portoricense	<b>Panic Grass</b>
<b>Panicum</b> virgatum	<b>Switch Grass</b>
<b>Paspalum</b> vaginatum	<b>Salt Joint-grass</b>
<b>Phalaris</b> arundinacea	<b>Reed Canary Grass</b>
<b>Phalaris</b> canariensis	
<b>Phragmites</b> communis	<b>Reed Cane</b>
<b>Phytolacca</b> americana	
<b>Poa</b> compressa	<b>Canada Bluegrass</b>
<b>Poa</b> macrantha	<b>Seashore Bluegrass</b>
<b>Polygonum</b> aviculare	<b>Knotweed</b>
<b>Polygonum</b> glaucum	<b>Seaweed Knotgrass</b>
<b>Polygonum</b> paronychia	<b>Smartweed</b>
<b>Polygonum</b> punctatum	
<b>Polygonum</b> tenue	<b>Shore Knotweed</b>
<b>Polypremum</b> procumbens	<b>Dune Gentian</b>
<b>Pteridium</b> aquilinum	<b>Bracken Fern</b>
<b>Pteridium</b> latiusculum	<b>Bracken Fern</b>
<b>Reneria</b> maritima	<b>Beach Stars</b>
<b>Salicornia</b> perennis	<b>Glasswort</b>
<b>Salicornia</b> virginica	<b>Glasswort</b>
<b>Salsola</b> kali	<b>Saltwort</b>
<b>Setaria</b> italica	<b>Foxtail</b>
<b>Selaginella</b> rupestris	<b>Club Moss</b>
<b>Sesuvium</b> maritimum	<b>Sea-purslane</b>
<b>Silybum</b> marianum	<b>Milk Thistle</b>
<b>Smilax</b> auriculata	<b>Greenbriar</b>
<b>Smilax</b> bona-nox	<b>Bullbriar</b>
<b>Solanum</b> dulcanara	<b>Bitter Nightshade</b>
<b>Solidago</b> sempervirens	<b>Evergreen Goldenrod</b>
<b>Solidago</b> sempervirens mexicana	<b>Gulf Goldenrod</b>



**Table 9 (concluded)**

<b><u>BOTANICAL NAME</u></b>	<b><u>COMMON NAME</u></b>
<b>Sorghum halepense</b>	<b>Means Grass</b>
<b>Sorghum vulgare</b>	<b>Sorghum</b>
<b>Spartina foliosa</b>	<b>Salt-marsh Grass</b>
<b>Spartina michauxiana</b>	<b>Slough Grass</b>
<b>Spartina patens</b>	<b>Salt-meadow Grass</b>
<b>Spartina townsendii</b>	<b>Cord Grass</b>
<b>Spartina juncea</b>	<b>Spanish Broom</b>
<b>Sporobolus domingensis</b>	<b>Rush Grass</b>
<b>Sporobolus virginicus</b>	<b>Rush Grass</b>
<b>Sporobolus wrightii</b>	<b>Bunch Grass</b>
<b>Stenotaphrum secundatum</b>	<b>St. Augustine Grass</b>
<b>Stipa spartea</b>	<b>Porcupine Grass</b>
<b>Sueda linearis</b>	<b>Sea-blite</b>
<b>Sueda maritima</b>	<b>Sea-blite</b>
<b>Tournefortia gnaphalodes</b>	<b>Sea Lavendar</b>
<b>Tradescantia foliosa</b>	<b>Spiderwort</b>
<b>Trifolium procumbens</b>	<b>Hop Clover</b>
<b>Uniola paniculata</b>	<b>Sea Oats</b>
<b>Vicia villosa</b>	<b>Hairy Vetch</b>
<b>Vinca minor</b>	<b>Periwinkle</b>
<b>Vinca rosea</b>	<b>Periwinkle</b>
<b>Vitis cordifolia</b>	<b>Grape</b>
<b>Vitis labrusca</b>	<b>Grape</b>
<b>Vitis mustangensis</b>	<b>Miscadine Grape</b>
<b>Vitis rupestris</b>	<b>Sand Grape</b>
<b>Waltheria americana</b>	<b>Coast Chocolate</b>
<b>Wedelia trilobata</b>	<b>Wedgegrass</b>
<b>Xanthium pennsylvanicum</b>	
<b>Zoysia tenuifolia</b>	<b>Miscarin Grass</b>

## **LITERATURE CITED**

- Ashby, William C. 1964. Vegetation development on a strip-mined area in Southern Illinois. Transaction of the Illinois State Academy of Science. Vol. 57 (2).
- Boyd, M.D., Saucier, R.T., Keeley, J.W., Montgomery, Brown, R.D., Mathis, D.B., Guice, C.J. November, 1972. Disposal of dredge spoil, problem identification and assessment and research program development, Technical Report H-72-8, U.S. Army Engineer Waterways Experiment Station, Vicksburg, Mississippi.
- Caborn, J.M. 1965. Shelterbelts and windbreaks. Department of Forestry and Natural Resources, University of Edinburgh, Faber & Faber Ltd., London.
- Commonwealth of Massachusetts. 1971. Regulations for the disposal of solid wastes by sanitary landfill. Department of Public Health. Division of Environmental Health, Bureau of Community Sanitation.
- Department of Public Works, Canada. 1971. Landscape and site development. Information Canada, Ottawa, Ontario, Canada.
- Department of the Army. 1967. Corps of Engineers. Office of the Chief of Engineers. Consideration of aesthetic values in water resource development. ER 1165-2-2. Washington, D.C.
- Department of the Army. 1971. Corps of Engineers. Office of the Chief of Engineers. Environmental quality in design of civil works projects. EM 1110-2-38. Washington, D.C.
- Department of the Army. 1971. Corps of Engineers. Office of the Chief of Engineers. Earth and rock-fill dams general design and construction considerations. EM 1110-2-2300. Washington, D.C.
- Department of the Army. Corps of Engineers. Office of the Chief of Engineers. Design and construction of levees (in preparation). EM 110-2-1913, Washington, D.C.
- Downing, M.F. 1971. "Landform Design", Landscape reclamation. Research Team of University of Newcastle-upon-Tyne, IPC Science and Technology Press, Guildford, England.
- Harrison, J.E., and Chisholm L.C. 1974. Identification of objectionable environmental conditions and issues associated with confined disposal areas. Contract report D-74-4. Prepared by Arthur D. Little, Inc., under Contract to the U.S. Army Engineer Waterways Experiment Station, Vicksburg, Mississippi.

- Hudson, Norman. 1971. Soil conservation. Cornell University Press, Ithaca, New York.**
- Hutnik, Russell J. and Davis, Grant, eds. 1973. Ecology and reclamation of devastated land. Volumes I and II. Gordon and Breach, New York.**
- Iurka, H.H. and Tetelman, B. 1960. Slope and rounding design. Report of Committee on Roadside Development, Highway Research Board, Washington, D.C.**
- Kuhlewind, Bringmann, and Kaiser. 1955. Richtlinien für Windschutz, Deutsche Landwirtschafts-Gesellschaft-Verlags. Frankfurt-am-Main.**
- Lovejoy, D., ed. 1973. Land use and landscape planning. Leonard Hill Boosk, Atlesbury, England. p. 214.**
- McAleer, J. 1974. Artificial islands and platforms in Long Island Sound. A staff study for the Long Island Sound Study, New England River Basins Commission. (permission for use pending).**
- Murphy, W.L. and Zeigler, T. W 1974. Practices and problems in the confinement of dredged materials in Corps of Engineers projects. Technical Report D-74-2. U.S. Army Engineer Waterways Experiment Station.**
- Robinette, G.O. 1972. Plants/people/and environmental quality. National Park Service and American Society of Landscape Architects Foundation. Washington, D.C.**
- Roy Mann Associates. 1973. General guidelines for use of the Great Lakes shoreline. Incorporated as Part VI "Management Guidelines" from A Plan for Michigan's shorelands. Prepared by the Michigan Department of National Resources.**
- Sorg, Thomas J., and Hickman H. Lanier. 1968. Sanitary landfill facts. U.S. Department of Health, Education and Welfare, Public Health Service. Publication no. 1792. National Center for Urban and Industrial Health, Solid Wastes Program Cincinnati, Ohio.**
- Tandy, C. ed. 1970. Handbook of urban landscape. Crane Russak and Co. Architectural Press.**

- Van Eesteren, C., Van Der Steur, A. J. and Van Genderen, W (A working committee). 1963. Planning and creation of an environment, experiences in the Ysselneerpolders. 7th Congress of the International Architects Union.**
- Vyle, C.J. 1971. Practical techniques for establishing vegetation on derelict land, in Landscape Reclamation. Research team of University of Newcastle-Upon-Tyne, IPC Science and Technology Press, Guilford, England.**
- Wyman, D. 1951. Trees for American gardens. MacMillan, New York.**
- Zak, J.M., Troll, J., Havis, J.R., Hyde, L.C., Kaskeski, P.A., Hamilton, WW 1972. A handbook for the selection of some adaptable plant species for Massachusetts roadsides, report 24-R5-2656-Roadside Development, Department of Plant and Soil Sciences, College of Food and Natural Resources. University of Massachusetts.**

#### **SELECTED BIBLIOGRAPHY**

##### **General References**

- Bachus, Brigadier General W.O. 1974. Dredge disposal ideas. North Central Division, U.S. Army Corps of Engineers.**
- Boccardy, J.A. and Spaulding, Id. M Jr. 1968. Effects of surface mining on fish and wildlife in Appalachia. Bureau of Sport Fisheries and Wildlife, U.S. Government Printing Office.**
- Chatry, F. Landscape plans for Red River Waterway. Planning Division, U.S. Army Corps of Engineers, New Orleans District.**
- Fabos, J.G., Milde, G.T. and Weinmayr, M 1698. Frederick Law Olmsted, Sr.: Founder of Landscape Architecture in America University of Massachusetts Press, Amherst.**
- Graetz, K.E. 1973. Seacoast plants of the Carolinas. U.S. Department of Agriculture, Soil Conservation Service. Raleigh, North Carolina.**
- Hitchcock, S.W 1972. Can we save our salt marshes? National geographic. Vol. 141 (6): pp. 729-765.**
- Kachel, T.J. 1971. Anatomy of the visual environment. New Man Publication, Carbondale, Illinois.**

- Linesch, J.H. 1967. Offshore innovation: industrial camouflage for oil drillers. Landscape Architecture. Vol. 58 (1): pp. 33-38.**
- McHarg, I.L. 1969. Design with nature. Natural History Press, Garden City, New York.**
- Michigan Department of Natural Resources. 1973. A plan for Michigan's shorelands.**
- Osmundson, T.F. 1973. Breakthrough: U.S. engineers shift policy with new levee design. Landscape Architecture. Vol. 63 (2).**
- Roberts, M.F. 1971. Tidal marshes of Connecticut: A primer of wetland plants. The Connecticut Arboretum Reprint Series #1.**
- Spaulding, W.M., Jr. and Ogden, R.D. 1968. Effects of surface mining on the fish and wildlife resources of the United States. Bureau of Sport Fisheries and Wildlife, U.S. Government Printing Office.**
- Swanson, S.L. 1972. Annual technical report of the Corvallis Plant Materials Center. U.S. Department of Agriculture, Soil Conservation Service, in cooperation with Oregon State Game Commission and the U.S. Army Corps of Engineers.**
- University of Delaware, College of Marine Studies. 1973. Coastal vegetation of Delaware. University of Delaware Press.**
- University of Newcastle-Upon-Tyne Research Team 1971. Landscape reclamation. Vol. 1. Business Press.**
- University of Newcastle-Upon-Tyne Research Team 1971. Landscape reclamation. Vol. 2. Business Press.**
- U.S. Army Corps of Engineers, Buffalo District. 1969. Dredging and water quality problems in the Great Lakes. Vol. 1, Summary Report. U.S. Army Corps of Engineers, Buffalo District.**
- U.S. Army, Office of the Chief of Engineers. 1972. Landscape planting adjacent to floodwalls, levees and dam embankments. ETL 1110-2-113, DAEN: CVE-M U.S. Army, Office of the Chief of Engineers.**

**U. S. Department of the Interior. 1967. Surface mining and our environment. U. S. Government Printing Office, Washington, D. C.**

**Windom H.L. 1972. Environmental response of salt marshes to desposition of dredged materials. As reprinted in ASCE National Water Resources Engineering Meeting. Atlanta, Georgia.**

**Woodhouse, WW Jr., Seneca, E.D. and Broone, S.W Marsh building with dredge spoil in North Carolina. Coastal Engineer Research Center, U.S. Army Corps of Engineers. NOAA Office of Sea Grant, Department of Commerce, North Carolina Coastal Research Program Grant No. GH-73.**

### **Sources, Plant Lists**

**Bailey, L.H. and E.Z. 1941. Hortus second: A concise dictionary of gardening and general horticulture. MacMillan, New York.**

**Bailey, L.H. 1966. Manual of cultivated plants. MacMillan, New York.**

**Bailey, L.H. 1935. The standard cyclopedia of horticulture. 3 volumes. MacMillan, New York.**

**Brockman, C.F. 1968. Trees of North America. Golden Press, New York.**

**Fernald, M.L. 1950. Gray's manual of botany. American Book Co.**

**Hitchcock, A.S. 1950. Manual of the grasses of the United States. U. S. Government Printing Office, Washington, D. C.**

**Kadlec, V.A. and Wentz, W.A., Jr. 1974. State-of-the-art survey and evaluation of marsh plant establishment techniques: induced and natural. Volume I: Report of Research. Contract Report D-74-9, prepared by the School of Natural Resources, University of Michigan--Ann Arbor, under contract to the U.S. Army Engineer Waterways Experiment Station, Vicksburg, Mississippi.**

**Kearney, T.H. and Peebles, R.H. 1960. Arizona flora. University of California Press, Berkeley.**

**Long, R.W. and Lakela, O. 1971. A flora of tropical Florida. University of Miami Press, Miami.**

**McCurdy, D.R., Spangenburg, W.G. and Doty, C.P. 1972. How to choose your tree. Southern Illinois University Press, Carbondale and Edwardsville.**

- Munz, P. and Keck, D. 1959. A California flora. University of California Press, Berkeley.**
- Petrides, G.A. 1972. A field guide to trees and shrubs. 2nd ed. Houghton Mifflin, Boston.**
- Petry, L. 1969. A beachcombers botany. Chatham Conservation Foundation.**
- Rehder, A. 1951. Manual of cultivated trees and shrubs. MacMillan, New York.**
- Spencer, E.R. 1974. All about weeds. Dover, New York.**
- Swartz, D. 1971. Collegiate dictionary of botany. Ronald Press.**
- U.S. Department of Agriculture, Soil Conservation Service. 1973. Seacoast plants of the Carolinas: for conservation and beautification. Raleigh, North Carolina.**
- U.S. Department of the Army, Corps of Engineers. 1957. Dune formation and stabilization by vegetation and plantings. Office of Chief of Engineers. Beach Erosion Board. Technical memorandum no. 101.**
- Wentz, W.A., Smith, R.L. and Kadlec, J.A. 1974. State-of-the-art survey and evaluation of marsh plant establishment techniques: induced and natural. Volume II: A selected annotated bibliography on aquatic and marsh plants and their management. Contract Report D-74-9, prepared by the School of Natural Resources, University of Michigan--Ann Arbor, under contract to the U.S. Army Engineer Waterways Experiment Station, Vicksburg, Mississippi.**
- Wynan, D. 1971. Wynan's gardening encyclopedia. MacMillan, New York.**
- Wynan, D. 1973. Shrubs and vines for American gardens. MacMillan, New York.**
- Wynan, D. 1974. The Saturday morning gardener: A guide to once-a-week maintenance. Revised ed. MacMillan, New York.**
- Zim, H.S. and Martin, A.C. 1952. Trees. Simon and Schuster, New York.**

In accordance with ER 70-2-3, paragraph 6c(1)(b), dated 15 February 1973, a facsimile catalog card in **Library** of Congress format is reproduced below.

Mann (Roy) Associates, Inc.

Landscape concept development for confined dredged material sites, by Roy Mann, William A. Niering, Robert Sabbatini, and Peter Wells. Vicksburg, U. S. Army Engineer Waterways Experiment Station, 1975.

168 p. illus. 27 cm. (U. S. Waterways Experiment Station. Contract report D-75-5)

Contract No. DACW39-74-C-0104 (DMRP Work Unit No. 5E01).

Bibliography: p. 163-168.

1. Disposal areas. 2. Dredged material disposal.  
3. Landscaping. I. Mann, Roy. II. Niering, William A., joint author. III. Sabbatini, Robert, joint author.  
IV. Wells, Peter, joint author. (Series: U. S. Waterways Experiment Station, Vicksburg, Miss. Contract report D-75-5)  
TA7.W34c no.D-75-5